

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road:- Dhaka Phulwariya Path me Chaknagri to Narkatia Harijan Toli Tak	Length-0.955 Km
Estimated Cost- Rs.:- 3,92,700.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

तकनीकी प्रतिवेदन

पथ का नाम :- ~~दाका-फुलवडिया रोड में चकनगरी से मदिना हरिजन रोली तक~~

प्रखंड का नाम :- ~~दाका~~

पथ की लम्बाई :- ०.१५५ कि०मी.

शीर्ष :- MMGSY.

प्राक्कलित राशि :- ₹- ३,१२,७००.००

अनुरक्षण अवधि :- निर्माणोपान,

~~दाका-फुलवडिया रोड में चकनगरी से मदिना हरिजन रोली तक~~ में अतिवृष्टि/वाढ़

से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० ३,१२,७००.००. रु० है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1-9-2020

कनीय अभियंता

ग्रामीण कार्य विभाग


कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, दाका


07/09/2020

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल, दाका


ate for Restoration work of Road from Dhaka Phulwariya Path me Chaknagri to Narkatia Harijan Toli Tak for the year 2020-21 in Dhaka Block.

Length:- 0.955Km


Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bats)				
CH:-820M to 835M 15.00x4.25+5.00x0.450 = 31.22M ³				
CH:-835M to 840M 5.00x4.50+6.00/2x1.50 = 39.38M ³				
CH:-840M to 845M 5.00x4.25+5.00/2x0.450 = 10.41M ³				
CH:-890M to 905M 15.00x3.50+4.05/2x0.450 = 25.48M ³				
CH:-905M to 917M 12.00+10.00/2x5.00+6.00/2x1.40 = 84.70M ³				
Total = 191.19M ³	M ³	191.19	2053.84	3,92,674.00
		Total=	Rs.	3,92,674.00
			Say Rs.	3,92,700.00


7.9.2020

JE.


07/09/2020

AE.


07/09/2020

EE.


Red Faint

T.A.T.S is accorded for Rs. 3,92,700 = ∞

(.....crore Three Ninety Two

Seven hundred)


SE (R.W.D.)
works Circle
Motihari


29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Dhaka Phulwariya Path me Chaknagri to Narkatia Harigan Toli Tak

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 52 M

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental
- (iv) Restored Length:- 52 M


24/12/2020
Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul