

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Dhaka Phulwariya Road to Bhagwanpur Bakhari	Length-1.480 Km
Estimated Cost- Rs.:- 5,65,500.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- ढाका - फुलनडिहा रोड से मन्वानपुर तक

प्रखंड का नाम :- ढाका

पथ की लम्बाई :- 1.480 कि.मी.


शीर्ष :- 1470.3y.

प्राक्कलित राशि :- रु. 5,65,500.00


अनुरक्षण अवधि :- निर्माणाधीन

प्रस्तुत प्राक्कलन ढाका - फुलनडिहा रोड से मन्वानपुर तक में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथारों में यातायात पुनर्स्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि रु. 5,65,500.00 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथारों में Brick Bats से भरने का प्रावधान किया गया है, तथा आवश्यकता अनुसार पथ में ह्यूम पाईप का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनूसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, ढाका।


07/09/2020


सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, ढाका



07/09/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, ढाका


Estimate for Restoration work of Road from Dhaka Phulwariya Road to Bhagwanpur Bakhari for the year 2020-21 in Dhaka Block.

Length:- 1.480 Km

Sl No.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron Including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) CH:- 300M to 350M $50.00+48.00/2 \times 4.10+5.50/2 \times 0.400+1.20+0.400/3 = 156.80M^3$ CH:- 610M to 630M $20.00+18.00/2 \times 4.00+4.50/2 \times 0.400 = 32.30M^3$ CH:- 750M to 790M $40.00+38.00/2 \times 4.0+4.50/2 \times 0.400 = 66.30M^3$ Less for H.P $2 \times 22/7 \div 4 \times (1.23)^2 \times 5.00$ (-) 11.88 M³ Total= 243.52M³	M ³	243.52	2147.40	5,22,935.00
2	Supplying Fitting and and fixing Hume pipe 1000mm dia Hume pipe all complete as per approved design specification and direction of E/I. 2Row x 2 Nos. x 2.50M = 10M	M	10	4258.65	42587.00
			Total=	Rs.	5,65,522.00
				Say Rs.	5,65,500.00


1.9.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

TA/TX is accorded for Rs. 5,65,500 = 00
Five Sixty Five
Five hundred


28.12.20
S.E. (R.W.D.)
works Circle
Motihari
29.12.20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div." Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Dhaka Phulwariya Road to Bhagwanpur Bakhari

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 80 M

3 Name of Damage:- Road damaged due to Flood

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 80 M.


Executive Engineer
R.W.D. (W) Div."
Raxaul