

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road:- Yadavpur Bakhari to yadavpur Bakhari Ward No-06	Length- 1.965 Km
Estimated Cost- Rs.:- 9,47,800.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- यादनपुर बस्ती से यादनपुर बस्ती नाले नं० 6

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 1.965 कि०मी०


शीर्ष :- T.M.Sy.

प्राक्कलित राशि :- ₹. 9,47,800.00.


अनुरोध अवधि :- - - -

प्रस्तुत प्राक्कलन यादनपुर बस्ती से यादनपुर बस्ती नाले में अतिवृष्टि/बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० 9,47,800.00 रु० है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुरोधित दर के अनुरूप है।


1.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, दाका

for Restoration work of Road from Yadavpur Bakhari to yadavpur Bakhari
No-06 for the year 2020-21 in Dhaka Block.

Length:- 1.965 Km

Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
24-0M to 50M 52.00x4.10x0.300 = 61.50M ³				
24-710M to 770M 52.00x4.0+6.0/2x1.00+2.00+1.00/3 = 400.00M ³				
Total = 461.50M ³	M ³	461.50	2053.84	9,47,847.00
		Total	Rs.	9,47,847.00
			Say Rs.	9,47,800.00

[Signature]
7.9.2020
J.E.

[Signature]
07/09/2020
A.E.

[Signature]
07/09/2020
E.E.

Est. Farto

T.A./S is accorded for Rs. 9,47,800 = ~
(.....crore. Nine.....lacs. Forty Seven.....thousand
Eight.....hundred only.

[Signature]
29-12-20
S.E. (R.W.D.)
works Circle
Motihari


Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Yadavpur Bakhari To Yadavpur Bakhari Ward
No-6

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 110 M
3. Name of Damage:- Road damaged due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipments Tools being used in restoration works:- -
 - (iii) Procedure take up in restoration works:- Departmental.
 - (iv) Restored Length:- 110 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul