

GOVERNMENT OF BIHAR

FDR (2020-21)



बिहार सरकार

Name of Road:- Masaurha chandmohan to Sishani	Length- 0.970 Km
Estimated Cost- Rs.:- 5,78,400.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- मसौदा चौरमोहन दे बिसहनी

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 0.975 किमी


शीर्ष :- MM 654.

प्राक्कलित राशि :- ₹. 5,78,400.00.

अनुरक्षण अवधि :- - - - -

प्रस्तुत प्राक्कलन मसौदा चौरमोहन दे बिसहनी में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि गो0...5,78,400.00... रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से मरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता

ग्रामीण कार्य विभाग


कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, दाका


07/09/2020

कार्यपालक अभियंता


ग्रामीण कार्य विभाग

कार्य प्रमण्डल, दाका

Rate for Restoration work of Road from Masaurha chandmohan to Sishani for the
2020-21 in Dhaka Block.
Length:- 0.970 Km


Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded Jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
CH:-75M to 110M 35.00x4.0+5.0/2x0.450+1.50+0.600/3 = 133.875M ³				
CH:-350M to 368M (Approach bridge) 2x4.00x4.00x0.450 = 14.40M ³				
CH:-380M to 400M 20.00x4.00x0.600 = 48.00M ³				
CH:-600M to 640M 40.00x4.00x0.300+0.900+0.400/3 = 85.333M ³				
Total = 281.608M ³	M ³	281.608	2053.84	5,78,378.00
		Total	Rs.	5,78,378.00
			Say Rs.	5,78,400.00


7.9.2020
J.E.


07/09/2020
A.E.


07/09/2020
E.E.

Post Fee Rs. T.A./S is accorded for Rs. 5,78,400.00
(.....crore Five Seventy Eight
.....lacs Th
.....Four hundred paise)


S.E. (R.W.D.)
works Circle
Motihari
29-11-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Masaurha Chandmohan to Sishani

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 110 M

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 110 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul