

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Gawandri Kundwa Chainpur to Kharuhi Tak	Length-0.720 Km
Estimated Cost- Rs.:- 3,43,600.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- रानन्दी कुण्डा-चैनपुर से रानन्दी तक

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 0.720 कि०मी०

शीर्ष :- MMCSY.

प्राक्कलित राशि :- रु. 3,43,600.00.


अनुरक्षण अवधि :- निर्माणोत्पीन

प्रस्तुत प्राक्कलन रानन्दी कुण्डा-चैनपुर से रानन्दी तक में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० 3,43,600.00 रु० है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, दाका


Rate for Restoration work of Road from Gawandri Kundwa Chainpur to Kharuhi Tak for the year 2020-21 In Dhaka Block.

Length:- 0.720 Km

Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
CH:- 280M to 300M 20.00x4.00x5.00/2x0.600+1.00+0.600/3 = 266.00M ³				
CH:- 350M to 360M 10.00x4.00x0.300+0.600+0.300/3 = 16.00M ³				
CH:- 410M to 420M 10.00x4.00x0.600 = 24.00M ³				
CH:- 650M to 680M 30.00x4.00x0.450 = 54.00M ³				
Total = 160.00M ³	M ³	160.00	2147.40	3,43,584.00
		Total	Rs.	3,43,584.00
			Say Rs.	3,43,600.00


19/12/20
J.E.


07/09/2020
A.E.


07/09/2020
E.E.

Post Facto T.A./T.S is accorded for Rs. 3,43,600 = Rs.
(.....crore.....Three lacs.....Forty Three thousand.....) only
Six hundred


28/12/20
S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

ate:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Gawandri kundwa chainpur to kharahi Tak.

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 70 m
3. Name of Damage:- Road damaged due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental.
 - (iv) Restored Length:- 70 m


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul