

GOVERNMENT OF BIHAR
FDR (2020-21)



Name of Road- Bhandar Chowk Saphi Village (Jamuaghat)	Length- 3.12Km
Estimated Cost- Rs.: 10,22,300.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- मंठार चौक से सपही गौन (जमुआपाइ)

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 3.12 कि०मी०


शीर्ष :- 3054 -

प्राक्कलित राशि :- ₹- 10,22,3000.00

अनुरक्षण अवधि :- - - -

प्रस्तुत प्राक्कलन मंठार चौक से सपही गौन (जमुआपाइ) में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० ₹- 10,22,3000.00 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से मरने का प्रावधान किया गया है। प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


7.9.2020
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020
सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका

**Estimate for Restoration work of Road from Bhandar Chowk Saphi Village
(Jamuaghat) for the year 2020-21 in Dhaka Block.**

length:- 3.12 Km

Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
CH- 130M to 1350M $51.00 \times 48.00 / 2 \times 5.00 \times .680 / 2 \times 1.40 + 2.50 + 1.40 / 3 = 497.76 M^3$ Total = 497.76 M ³	M ³	497.76	2053.84	10,22,319.00
		Total	Rs.	10,22,319.00
			Say Rs.	10,22,300.00

[Signature]
T.E. A.A.O.
I.E.

[Signature]
07/07/2020
A.E.

[Signature]
07/07/2020
E.E.

Est. for Rs. 10,22,300.00
TA/JS is accorded for Rs. 10,22,300.00
(..... crore..... Ten..... lacs..... Twenty Two..... thousand
..... hundred only.

[Signature]
S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Bhandar chawck - Saphi Village (Jamunghat)

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 50 m

3. Name of Damage:- Road cutting due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 50 m


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul