



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR
FDR

YEAR 2021-22

Detailed Project Report

Division : Rosera

District :

Samastipur

Block :

Singhia

Name of
Road :

Bara Chouk To Sonmanni Via Laxminia

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

FDR

Detailed Estimate for

Bara Chouk To Sonmanni Via Laxminia

Block :

District :

Singhia
Samastipur

ABSTRACT OF COST FOR ROAD

SI No	Item of Work		Amount (In Rs)
			As per Estimate
1	Total Cost for Pavement Works		873558.11
	Total Cost of Project :		Rs - 873558.11
	Total Cost Including (GST + L.Cess) 13% :		Rs - 113562.55
	Total :		Rs - 987120.66
	Say (Lakh) :		Rs - 9.87

Junior Engineer

RWD (W) Section, Singhia

Asstt. Engineer

RWD (W) S. Div. Singhia

Executive Engineer

RWD (W) Div, Rosera

Project : Samastipur
Block : Singhia


FDR
Bara Chouk To Sonmami Via Laxminia

SI No	Reference To Mord Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
				L (m)	B (m)	D (m)				
1	401	Supply filling brick bat compacted manually								
			8	20.00	2.25	0.35	cum	126.00		
			2	30.00	1.50	0.40	cum	36.00		
			5	35.00	1.50	0.15	cum	39.38		
			8	40.00	2.25	0.10	cum	72.00		
			3	35.00	3.75	0.45	cum	177.19		
			4	20.00	1.25	0.10	cum	10.00		
		Total Quantity :					cum	460.56	1896.72	873558.11
		Total Cost of Pavement in Rs :								8.74

Total Length (Km): 0.900


Junior Engineer
RWD (W) Section, Singhia


Asst. Engineer
RWD (W) S. Div. Singhia


Executive Engineer
RWD (W) Div, Rosera