



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

DETAILED PROJECT REPORT

MUKHYA MANTRI GRAM SAMPARK YOJNA

Estimate for Permanent Restoration

2020 - 2021

4125
21.6.21

STATE :- BIHAR
DISTRICT :- Vaishali
BLOCK :- Jandaha



REVISED ESTIMATE FOR MURADABAD TO MILKI JAPARHA

TOTAL LENGTH OF ROAD	:- 3.830 Km
TOTAL COST OF CONSTRUCTION	:- Rs. 2.941 Lakhs
COST AS PER WORK DONE	:- Rs. 275.583 Lakhs
COST AS PER NOT WORK DONE	:- Rs. 16.041 Lakhs
5 YEAR MAINTENANCE COST	:- Rs. 13.086 Lakhs
TOTAL COST OF PROJECT	:- Rs. 307.651 Lakhs

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD WORKS DIVISION, MAHNAR
VAISHALI

प्रतिवेदन


पथ का नाम :- मुरादाबाद मिल्की जसपरहा


पथ की लम्बाई :- 3.830 कि०मी०


प्रस्तुत प्राक्कलन (275.470 लाख) वर्ष-2020 में आयी बाढ़ के कारण क्षतिग्रस्त पथ के पूर्व पुर्नस्थापन हेतु सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के निदेश के आलोक में तैयार किया गया है। पथ का निर्माण मुख्यमंत्री ग्राम संपर्क योजनान्तर्गत लगभग चार वर्ष छः माह पूर्व किया गया है वर्तमान में यह पथ पंचवर्षीय अनुरक्षण अवधि के अन्दर है। पथ की कुल लम्बाई 3.830 कि०मी० है। पथ में गड़ढ़े को भरने के लिए (विभिन्न पथांश में) WBM-III एवं लगभग 0.050 कि०मी० में Primix Carpet का प्रावधान किया गया है। जिसका मापी प्राक्कन में परिशिष्ट के रूप में संलग्न है। पथ का फोटोग्राफ एवं विवरणी MIS में प्रविष्टि की जा चुकी है।

इस पथांश के पूर्व पुर्नस्थापन से मुरादाबाद एवं मिल्की जसपरहा के लोगों को आवागमन में सुविधा होगी।

यह प्राक्कलन ग्रामीण कार्य विभाग के मार्गदर्शिका के अनुरूप तैयार किया गया है जिसमें तकनीकी परीक्षक कोषांग द्वारा निर्गत अद्यतन बेसिक दर को समर्पित किया गया है।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता

इस पुर्नस्थापन का कार्य का निरीक्षण अप्पोजेन्सरी. डार किया गया है। कार्य प्राक्कलन के अनुरूप एवं लंबे ५५६ है।


Superintending Engineer
Rural Works Department
Works Circle Muzaffarpur

Mukhya Mantri Gram Sampark Yojna (MMGSY)

FORMAT F-5

GENERAL ABSTRACT OF COST

Block:--Jandaha

District:--Vaishali

Length of Road:-- 3.830 KM

Name of Road:-- Revised Estimate For Muradabad To Milki Japarha

SL. No.	Item of Work	Amount
A	TOTAL COST OF FLOOD DAMAGE	₹ 2.941 Lakhs
B	COST AS PER WORK DONE	₹ 275.583 Lakhs
C	COST AS PER NOT WORK DONE	₹ 16.041 Lakhs
D	FIVE YEAR MAINTENANCE COST	₹ 13.086 Lakhs
TOTAL COST OF PROJECT		₹ 307.651 Lakhs


25/05/24

Junior Engineer


25/5/24

Asstt. Engineer


25/5/24

Executive Engineer

95 
25/5/24

Superintending Engineer
Rural Works Department
Works Circle Muzaffarpur

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

Revised Estimate For Muradabad To Milki Japarha

DISTRICT

Vaishali

BLOCK

Jandaha

LENGTH OF ROAD (in Km)

3.830

LENGTH OF BT PAVEMENT

LENGTH OF CC PAVEMENT

LENGTH OF NO WORK

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	PREPARATORY WORKS, SITE CLEARANCE, DISMANTLING	0.000
2	EARTHWORK	0.133
3	GSB	0.412
4	WBM GRADE II	0.000
5	WBM GRADE III	1.157
6	PRIME COAT	0.170
7	TACK COAT	0.060
8	PREMIX CARPET	0.797
9	SEAL COAT	0.211
10	CEMENT CONCRETE PAVEMENT	0.000
11	HARD SHOULDERING	0.000
12	SIDE DRAINS	0.000
13	PROTECTION WORKS / Boulder Pitching	0.000
14	ROAD FURNITURES, KM STONES, TRAFFIC & DIRECTION SIGN, PMGSY LOGO	0.000
	SUB TOTAL OF PAVEMENT COST IN LAKHS =	2.941
	Sub Total ₹ :-	2.941
	TOTAL COST OF PROJECT IN LAKHS =	2.941



Junior Engineer
RWD Works Division, Mahnar



Assistant Engineer
RWD Works Division, Mahnar



Executive Engineer
RWD Works Division, Mahnar

Sl. No.	SDB SL. NO	MORD Ref. No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
5	5.2	503	Tack Coat Providing and applying tack coat with bitumen emulsion (Rs-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the preapred granular surfaces treated with primer & celaned with hydraulic broom as per technical specification claus 503	Sqm	1	10.00	3.75		37.50		
				Sqm	1	40.00	3.75		150.00		
					1	60.00	2.60 (av)		156.00		
			Net Area	Sqm					343.50	17.41	5,980.00
6	5.11	509	premix carpet of 20 mm thickness Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	Sqm					343.50		
			Net Area	Sqm					343.50	231.97	79,681.70
7	5.2	503	seal coat Type B Providing, laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grades and cross fall using Type B as per the specification in clause 510 (With Bituminous Binder S-90)	Sqm					343.50		
			Net Area	Sqm					343.50	61.52	21,132.00
			B) SUB TOTAL OF BITUMINOUD ITEM =								1,23,837.70
			TOTAL COST OF PAVEMENT IN RS. (A+B)=								2,94,079.70

5.11 x
Bret 95/512
Sud 05/172

25/05/21
25/05/21
25/05/21

and seal coat

25.05.2021
RWD Mahmar
RWD

Executive Engineer
R.W.D., Work Div., Mahmar

2,79,051

Revised Estimate For Muradabad To Milki Japaha

Sl No.	Item	Unit	As Per BQ/ Agreement			Work already done			Work Not Done			Work To Be Done After Damaged Due To Flood			Total			Variation in Amount			Remark
			Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount	Amount (9+15)	Difference in Amount (15-6)	%				
1	Setting Out Pillars > Providing & Fixing of Working Benchmark Pillars 1 nos. per km & 4 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I (including Royalty & Labour Cost), Working Benchmark Pillars	km	3.830	3,240.07	12,409.00	3.830	3,240.07	12,409.00	0.000	3,240.07	0.00	0.000	3,240.07	0.00	12,409.00	0.00	0%	0%			
2	Reference pillars	km	3.830	1,518.49	5,816.00	3.830	1,518.49	5,816.00	0.000	1,518.49	0.00	0.000	1,518.49	0.00	5,816.00	0.00	0%	0%			
3	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I (including Royalty & Labour Cost).	ha	2.680	35,785.53	95,905.00	2.666	35,785.53	95,404.00	0.014	35,785.53	501.00	0.000	35,785.53	0.00	95,905.00	0.00	0%	0%			
4	Construction Of Embankment with approved materials Deposition at site from roadway cutting and excavation from drains and foundation of other structures graded and compacted to meet requirement of table as per Technical Specification Clause 303.1.	Cum	4,330.450	127.48	5,52,046.00	4,084.810	127.48	5,20,732.00	245.640	127.48	31,314.00	0.000	127.48	0.00	5,52,046.00	0.00	0%	0%			
5	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5. (including Royalty & Labour Cost). For 1000 m Lead Cum	Cum	4,732.150	165.57	7,83,502.00	4,425.210	165.57	7,32,682.00	306.940	165.57	50,820.00	0.000	165.57	0.00	7,83,502.00	0.00	0%	0%			
6	Construction of Subgrade and Earthen Shoulders with 5% Local sand mixed with Rotavator to achieve minimum soaked CBR value of 5 % .> Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (including Royalty & Labour Cost).	Cum	3,767.290	149.39	5,62,795.00	3,303.980	149.39	4,93,582.00	463.310	149.39	69,214.00	89.100	149.39	13,311.00	5,76,106.00	13,311.00	2%	2%			
7	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	Cum	301.610	87.95	26,527.00	253.420	87.95	22,288.00	48.190	87.95	4,238.00	0.000	87.95	0.00	26,527.00	0.00	0%	0%			
8	Granular Sub-base with Coarse Graded 1 Material > Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. (including Royalty & Labour Cost)	Cum	1,936.090	2,643.93	51,18,886.00	1,936.090	2,643.93	51,18,886.00	0.000	2,643.93	0.00	15.600	2,643.93	41,245.00	51,601,131.00	41,245.00	1%	1%			
9	WBM Grading 2 (By Manual Means) > Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (including Royalty & Labour Cost)	Cum	431.440	4,572.98	19,72,946.00	397.210	4,572.98	18,16,433.00	34.230	4,572.98	1,56,533.00	0.000	4,572.98	0.00	19,72,946.00	0.00	0%	0%			
10	WBM Grading 3 (By Manual Means) > Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (including Royalty & Labour Cost)	Cum	431.440	4,490.48	19,37,373.00	397.210	4,490.48	17,85,664.00	34.230	4,490.48	1,53,709.00	25.763	4,490.48	1,15,686.00	20,53,059.00	1,15,686.00	6%	6%			

25/05/24

Sl. No.	Item	As Per Bill / Agreement				Bidding Price			Bidding Price			Bidding Price			Bidding Price			Bidding Price		
		Unit	Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount
11	Providing and applying primer coat with Bitumen emulsion (R-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.75-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	5,752.500	49.62	2,85,639.00	5,754.500	49.62	2,83,219.00	448.120	49.62	22,236.96	343.500	49.62	17,044.00	1,02,481.00	1,02,481.00	17,044.00	6%		
12	Providing and applying tack coat with bitumen emulsion (R-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with primer & related with hydraulic boom as per technical specification clause 503	Sqm	5,752.500	17.41	1,00,151.00	5,754.500	17.41	92,349.00	448.120	17.41	7,802.00	343.500	17.41	5,980.00	1,04,131.00	1,04,131.00	5,980.00	6%		
13	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 13.2 mm to 0.3 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 505	Sqm	5,752.500	231.97	13,34,407.00	5,754.500	231.97	12,30,457.00	448.120	231.97	1,03,950.00	343.500	231.97	79,682.00	14,14,289.00	14,14,289.00	79,682.00	6%		
14	Providing, laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grades and cross fall using Type B as per the specification in clause 512 (With Bituminous Binder S-90)	Sqm	5,752.500	61.52	3,53,894.00	5,754.500	61.52	3,26,325.00	448.120	61.52	27,566.00	343.500	61.52	21,132.00	3,75,026.00	3,75,026.00	21,132.00	6%		
15	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS-383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with screeds, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	Cum	1,748.690	7,121.85	1,24,53,908.00	1,748.690	7,121.85	1,24,53,906.00	0.000	7,121.85	0.00	0.000	7,121.85	0.00	1,24,53,908.00	0.00	0%			
16	Kilometre stone - Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1700 (including Royalty & Labour Cost), 3 km stone	Noe	4.000	2,460.79	9,843.00	4.000	2,460.79	9,843.00	0.000	2,460.79	0.00	0.000	2,460.79	0.00	9,843.00	0.00	0%			
17	(ii) 200 m stone	Noe	16.000	685.25	10,964.00	16.000	685.25	9,594.00	2.000	685.25	1,371.00	0.000	685.25	0.00	10,964.00	0.00	0%			
18	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC28, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	each	26.000	505.76	38,438.00	0.000	505.76	0.00	26.000	505.76	38,438.00	0.000	505.76	0.00	38,438.00	0.00	0%			
19	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	44.640	83.98	3,749.00	44.640	83.98	3,749.00	0.000	83.98	0.00	0.000	83.98	0.00	3,749.00	0.00	0%			
20	Painting New Letters and Figures of any Shade with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	176.000	0.39	69.00	176.000	0.39	69.00	0.000	0.39	0.00	0.000	0.39	0.00	69.00	0.00	0%			

SR
TE

10) Providing and fixing 'tags' of NIMCST Project - Providing and fixing of typical NIMCST information sign board with 150mm thick, 150mm wide and 150mm high. The lower plate will be welded with 150mm x 25mm x 5mm. The angle iron frame of the lower most plate and 150mm x 12mm x 12mm plate will be welded to the 150mm x 25mm x 5mm plate. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All N.S. will be above enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All required framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1701.1 (including Royalty & Labour Cost).

	no	2.000	9,999.23	19,998.00	2.000	9,999.23	19,998.00	0.000	9,999.23	0.00	19,998.00	0.00	0%
22	Providing and fixing of Retro reflective cautionary, mandatory and information sign board as per IRC-87 made of 1.5 mm thick MS steel duly above white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.5 of NORD for rural road of required shade and colour supported and welded on 47mmx47mmx12mm sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm 600mm below ground level as per approved drawing clause 1701.2.2.	Nos	8.000	3,791.20	30,330.00	3,791.20	30,330.00	0.000	3,791.20	0.00	30,330.00	0.00	0%
23	600 mm x 450 mm rectangular, (School & Place)	Nos	7.000	4,441.98	31,094.00	4,441.98	31,094.00	0.000	4,441.98	0.00	31,094.00	0.00	0%
24	900 mm side octagon	Nos	2.000	8,548.89	17,098.00	8,548.89	17,098.00	0.000	8,548.89	0.00	17,098.00	0.00	0%
25	Painting lines, dashes, arrows, etc. on roads in two coats on old work with ready mixed road marking paint conforming to IS:664 on bituminous/concrete surfaces, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at site and traffic control as per drawing and technical specification Clause 1702	Sqm	250.000	828.00	2,31,095.00	828.00	2,31,095.00	0.900	828.00	745.00	2,31,840.00	0.00	0%
26	Zebra Crossing	Sqm	32.000	828.00	26,496.00	828.00	26,496.00	32.000	828.00	26,496.00	26,496.00	0.00	0%
27	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fill, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC-98/1997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC-98 - 1997 and approved drawings.	RM	105.000	1,038.32	1,09,024.00	1,038.32	54,512.00	52.500	1,038.32	54,512.00	1,09,024.00	0.00	0%
28	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 302.	No	2.310	361.34	835.00	361.34	835.00	0.000	361.34	0.00	835.00	0.00	0%
29	Reinforced cement concrete	No	3.000	835.22	2,506.00	835.22	2,506.00	0.000	835.22	0.00	2,506.00	0.00	0%
30	Cement mortar	No	55.440	268.45	14,883.00	268.45	14,883.00	0.000	268.45	0.00	14,883.00	0.00	0%
31	Removing all type of Hume pipe and stacking - upto 900mm dia Hume pipe	No	5.000	163.03	815.00	163.03	815.00	0.000	163.03	0.00	815.00	0.00	0%
32	Earthwork in excavation for structures as per drawing and technical specifications Clause 303.1 including setting out, construction of shoring and bracing, removal of stump and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	Cum	119.230	204.70	24,400.00	204.70	6,866.00	85.660	204.70	17,535.00	24,400.00	0.00	0%
33	Diversion-Construction Of Embankment with approved materials deposition at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table as per Technical Specification Clause 303.1	Cum	36.000	127.48	4,589.00	127.48	0.00	36.000	0.000	4,589.00	4,589.00	0.00	0%

[Handwritten signature]

[illegible]

चेक-लिरट

1	शक्ति का संख्या	
2	शीर्ष	
3	प्रमंडल का नाम	FDR
4	पथ का नाम	महजार
5	पथ की लम्बाई	मुशायबाद से मिलकी जसपरहा
6	प्रमंडल का नाम (पूर्व में जिसको स्वीकृति प्रदत्त है)	3.830 Km
7	प्रमंडल का नाम (जिनके द्वारा वर्तमान में कार्य किया जाना है)	महजार
8	कार्य प्रमंडल का नाम	महजार
9	जिला का नाम	महजार
10	प्रशासनिक स्वीकृति की राशि :-	केशाली
11	प्रशासनिक स्वीकृति का प्रसंग :-	308.18 Lakhs.
12	पूर्व में प्रदत्त तकनीकी स्वीकृति की राशि :-	BRRDA (HS)-MMLTSY-242/14 P-II-4944/यलना दि 19/11/14
13	तकनीकी स्वीकृति का प्रसंग :-	304.71 Lakhs.
14	एकरारनामा की राशि :-	304.71 Lakhs.
15	संवेदक का नाम एवं निबंधन संख्या :-	289.134 Lakhs
16	एकरारनामा के अनुसार कार्य प्रारंभ करने की तिथि :-	Pratyaksha Const, Agreement: 28/11/14 15/06/2015
17	एकरारनामा के अनुसार कराये गये कार्य की राशि :-	261.506 Lakhs.
18	वर्तमान में कार्य की स्थिति :-	सम्पन्न
19	क्या एकरारनामा विखंडित किया गया है अथवा बंद किया गया है	नहीं
20	क्या एकरारनामा विखंडित करने के फलस्वरूप अग्रधन एवं जमानत की राशि जब्त की गयी है	नहीं
21	कार्य को पूर्ण कराने में अग्रधन एवं जमानत की राशि कर जब्त से अधिक लगने वाले राशि हेतु संबंधित संवेदक पर कार्यपालक अभियंता द्वारा दावा किया गया है	नहीं
22	एकरारनामा विखंडित करने की स्थिति में क्या कार्यपालक अभियंता द्वारा संवेदक को काली सूची में डालने का प्रस्ताव दिया गया है	नहीं
23	क्या पुनरीक्षित प्राक्कलन में किये गये प्राक्धानों की अनुशांसा सक्षम प्राधिकार (अधीक्षण अभियंता) के द्वारा स्थल निरीक्षण कर की गई है	हाँ
24	पुनरीक्षित प्राक्कलन की राशि :-	276.71 Lakhs.
25	पुनरीक्षित प्राक्कलन एवं मूल प्राक्कलन की राशि में अंतर :-	2.79 Lakhs.
26	पुनरीक्षित प्राक्कलन की राशि में वृद्धि (प्रतिशत में) :-	1.01%
27	पुनरीक्षित प्रशासनिक स्वीकृति का कारण :-	FDR पूर्व प्रशासनिक स्वीकृति की राशि के अनुरूप है।

7E

रामेश्वर
कार्यपालक अभियंता का हस्ताक्षर

प्रमोद कुमार