

certified copy

1. Name of the work : Munni ghat to Munni Yadav tola UNDER MMGSY.
2. No. of roads. : One
3. Length of the road. : 0.65 K.M.
4. Name of the Agency & Address : Pankaj Kumar,
Mohalla - Azad Colony Maripur, P.O. - H.P.O.
P.S. - Kazi Mohammadpur, Distt. - Muzaffarpur
5. Agreement No. : 56/SBQ/2018-19
6. Approval of Rate : S.E., R.W.D. Muzaffarpur, letter No. 838 enc.
dt. 04.06.2018 on 10.00 % below from
Schedule rate.
7. Agreement value of the work:-
(a) Construction cost : Rs. 40,35,131.00
(b) Maintenance cost : Rs. 1,09,137.00
Rs. 41,44,268.00 Less 10.00% below from
Schedule rate.
Rs. 37,29,841.00
(Rupees Thirty Seven lakh Twenty Nine
Thousand Eight Hundred forty one Only).
8. EMD (1%) : Rs. 37,298.00
APG (3.75%) : Rs. 1,39,869.00
Rs. 1,77,167.00

Executive Engineer
R.W.D. Works Division
Muzaffarpur East-1

Performance security (including earnest money) deposited by the Agency in the form of FD amounting to Rs. 1,78,000.00 The details of FD is as follow:-

- (i) Union Bank of India, Muz. FD A/c No. 735103030000403 Rs. 1,35,000.00
- (ii) Union Bank of India, Muz. FD A/c No. 735103030000345 Rs. 43,000.00
Rs. 1,78,000.00

(Rs. One Lakh Seventy Eight Thousand Only)

9. Date of work Order : 09.06.2018
10. Date of completion : 08.03.2019 (Nine Months)
11. Security Deposit : 9% (Nine percent) to be deducted from the
gross amount of each running Bill.
12. Defect liability period : Five years from the actual date of completion
of the work.
13. Refund of performance security and security deposit : After five years from the actual date of
completion of the work.
14. Total item of Agreement : 38 (Thirty Eight) item in each road.

Note:-S.B.D. Rules, terms and conditions will be applicable.

Pankaj Kumar

Executive Engineer
R.W.D. Works Division
Muzaffarpur East-1

Sl. No.	Description of Items	QTY.	Unit	Rate	
				In Figure	In word
32	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 SOR Item No.-10.2 A (1) (v) 600 mm x 450 mm rectangular	1.000 ✓	No.	3728.54 ✓	Three Thousand Seven Hundred Twenty Eight Rupees and Fifty Four Paises
33	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. SOR Item No.-8.13	50.000 ✓	sqm	839.60 ✓	Eight Hundred Thirty Nine Rupees and Sixty Paises
34	Maintainance for 1st year	1.000	Year	12005.00 ✓	Twelve Thousand Five Rupees and No Paises
35	Maintainance for 2nd year	1.000	Year	15569.00 ✓	Fifteen Thousand Five Hundred Sixty Nine Rupees and No Paises
36	Maintainance for 3rd year	1.000	Year	22501.00 ✓	Twenty Two Thousand Five Hundred One Rupees and No Paises
37	Maintainance for 4th year	1.000	Year	27651.00 ✓	Twenty Seven Thousand Six Hundred Fifty One Rupees and No Paises
38	Maintainance for 5th year	1.000	Year	31411.00 ✓	Thirty One Thousand Four Hundred Eleven Rupees and No Paises

sd
Executive Engineer
R.W.D. Works Division
Muzaffarpur East-1

20/2/18

Pankaj Kumar