



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Noonpur Simana Noonpur Near Binda Paswan House	
DISTRICT		Vaishali	
DIVISION		Hajipur	
BLOCK		Hajipur	
DAMAGED LENGTH OF ROAD		:	0.500 KM
CONSTRUCTION COST		:	4.18 4.596 Lac

Submitted By :-
Executive Engineer
RWD Work Division, Hajipur

Inspection Report for Flood Damage Work

Date:-

1 Name of PIUs :- R.W.D works Division, Hajipur

2 Name of Block/Road :- Hajipur / Noonpur Simana to Noonpur near
Binda paswan House

(A) For Road:

1. Damage Location/Chainage :- 0-0.250 km
2. Damage Length :- 0.250
3. Nature of Damage :- water logging and wash out due to flood.
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:- Brick bats — 202.50 m³
 - (ii) Equipment's/Tools being used in Restoration works:- Tractor, J.C.B, Road Roller.
 - (iii) Procedure taken up in Restoration works: work is Satisfactory.
 - (iv) Restored Length :- 0.250 km

(B) For Bridge:

— N/A

1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:-
 - (ii) Equipment's/Tools being used in Restoration works:-
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :-

Signature of JE/AE/EE

Signature

(Name of Inspection)

GENERAL ABSTRACT

Name of Road Noonpur Simana Noonpur Near Binda Paswan House

District Vaishali

Block Hajipur

Division Hajipur

Length of Road (in Km) 0.500 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	4.180 4.596
3	Sand Filling	0.000
4	Sand bag	0.000
5	H.P.	0.000
	SUB TOTAL	4.180 4.596
	GRAND SUB TOTAL	4.180 4.596

S.K.
28.11.21
RWD

Sanjay
27.11.21
AE
RWD

Pam
29.11
EE
RWD

As For S.E. RWD (W) Circle Muz
Letter No 1979 Dated 01/10/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division Muz west

Technically Sanctioned for Rs. 4.18 lacs
(Rs. four lacs eighteen thousand) only
(provisionally)

Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

27.12.21

I. NO. (REV. NO.)		Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		Providing and Laying of Brick Bats Providing laying spreading & compacting Brick Bats including spreading in uniform thickness hand packing (Manual Means) As Per MB No-2817 & Page No-1 & 2				
			Cum	202.505	2064.56	418083.72
			Total	202.505	2269.79	459643.82
Total Cost :-						459643.82

say 418084=00

Sanjay
27.11.21
AE

Sr
27.11.21
S.E

Sanjay
27.11.21