



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Jarang Rampur To Daudnagar Road	
DISTRICT		Vaishali	
DIVISION		Hajipur	
BLOCK		Vaishali	
TOTAL LENGTH OF ROAD		:	7.240 KM
CONSTRUCTION COST		:	11.492 Lac

Submitted By :-
Executive Engineer
RWD Work Division, Hajipur

12.025 Lac
10.958 Lac
11.021

Inspection Report for Flood Damage Work

Date:-

28/10/21

1 Name of PIUs :-

RWD, works division Haripur

2 Name of Block/Road :-


Vashti / Jirang Rempur to Deudmatar Road


(A) For Road:


1. Damage Location/Chainage :- 0 to 7.24 km
2. Damage Length :- 0.777 km.
3. Nature of Damage :- Flood
4. Details of Restoration Works :- Brick bats
- (i) Material being used in Restoration works:- Brick bats (529*787mm) Humapike 10.2m
- (ii) Equipment's/Tools being used in Restoration works:- J.C.B, Tractor, Labour
- (iii) Procedure taken up in Restoration works: Manual work is Satisfactory.
- (iv) Restored Length :- 0.777 km

(B) For Bridge:

1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
- (i) Material being used in Restoration works:-
- (ii) Equipment's/Tools being used in Restoration works:-
- (iii) Procedure taken up in Restoration works:-
- (iv) Restored Length :-


Signature of JE/AE/EE


28/10/21


Signature

(Name of Inspection)

प्रतिवेदन


कार्य का नाम:- जारांग सागर से दाउदगंगा पथ


.....पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड- दाउदगंगा
वित्तीय वर्ष - 21-21
प्राक्कलित राशि - Rs. 11.02 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 11.02 लाख है, प्रखण्ड-दाउदगंगा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक दिनांक द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है। MIS - 44


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

GENERAL ABSTRACT

Name of Road Jarang Rampur To Daudnagar Road

District Vaishali

Block Vaishali

Division Hajipur

Length of Road (in Km) 7.240 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	10.938
3	Sand Filling	0.000
4	Sand bag	0.000
5	H.P.	0.083
	SUB TOTAL	11.021
	GRAND SUB TOTAL	11.021

10.938
12.025
10.938
12.025
12.025
12.938

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD

As Per S.E. RWD (M) Circle Muz
Letter No 1178 Dated 01/10/2021
Expenditure has been entered by inspecting
E.E. RWD. (M) Division Muz west

Technically Sanctioned for Rs. 11.021 lac
(Rs. Eleven lacs two thousand one hundred)
only (provisionally)

[Signature]
27/12/21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur
27.12.21

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1			Providing and Laying of Brick Bats Providing laying spreading & compacting Brick Bats including spreading in uniform thickness hand packing (Manual Means) As Per MB No. & Page No 15-19	Cum Total	529.787 529.787	2064.56 2269.78 2153.47	1093794.04 1202499.34 1140880.41
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 As Per MB No. & Page No.....	Cum Total	0.000 0.00	553.72	0.00
3		WRD 5.7.40	Sand bag Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/ As Per MB No. & Page No.....	Nos Total	0 0.00	36.49	0.00
Total Cost :-							4140880.41

Approved
20/11/24
AE

120249934
9282 1093777
20/11/24

DETAILED COST ESTIMATE OF HUMIE PIPE

Sl. No.	SOR Item no.	Description	Qty. (Nos.)	Length (m)	Quantity	Unit	Rate (Rs)	Amount in Rs.
2 Nos.								
3	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 300 mm dia as per design in Single Row MB No..... & Page No-7-7	4	2.5	10.00	m	834.29	8,342.90
Grand Total :								8,342.90

Signature
20/11/20

Asst. Dy. Sd/-
20/11/20
A E

904
20/11/20