

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Mauna Bishunpur Mangal Sthan Road to Mauna Bishunpur Harijan Tola	
DISTRICT		Vaishali	
DIVISION		Hajipur	
BLOCK		Patedhi Belsar	
TOTAL LENGTH OF ROAD	:	0.640	KM
CONSTRUCTION COST	:	1.343	Lac

**Submitted By :-
Executive Engineer
RWD Work Division, Hajipur**

1.366

Inspection Report for Flood Damage Work

Date:- 18/11/2021

1 Name of PIUs :- R.W.D. work Division Hajipur

2 Name of Block/Road :- Patedhi Belsar

(A) For Road:

1. Damage Location/Chainage :- ~~500 to 550 m~~ 0 to 50 m
2. Damage Length :- ~~5 m - 50 m~~ 30 m
3. Nature of Damage :- flood
4. Details of Restoration Works :- Bumbo and sand bag.
- (i) Material being used in Restoration works:- ~~gunny Pilling~~ (120/M), 3309 MY
- (ii) Equipment's/Tools being used in Restoration works:- JCB, Tractor, labour
- (iii) Procedure taken up in Restoration works:- Manual
- (iv) Restored Length :- 30 m

(B) For Bridge:

1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
- (i) Material being used in Restoration works:-
- (ii) Equipment's/Tools being used in Restoration works:-
- (iii) Procedure taken up in Restoration works:-
- (iv) Restored Length :-

Signature of JE/AE/EE

Signature

(Name of Inspection)

प्रतिवेदन

कार्य का नाम:- मौना विद्युत् मंगल स्थान से मौना विद्युत्
हरिजन चेला
मौना से जोड़ा जाने वाला सड़क से से चरमपुर और हरिजन
पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में चेला
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- पट्टी चेला
वित्तीय वर्ष - 21-22
प्राक्कलित राशि - Rs. 1.366 लाख

1.366
1.343 Lakh
0.843 Lakh.

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 1.366 लाख है,
प्रखंड- पट्टी चेला में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक दिनांक द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है। MIS - 38

18/11/2021

कनीय अभियंता

18/11/21
सहायक अभियंता

18/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

GENERAL ABSTRACT

Name of Road Mauna Bishunpur Mangal Sthan Road to Mauna Bishunpur Harijan Tola
District Vaishali
Block Patedhi Belsar
Division Hajipur
Length of Road (in Km) 0.640 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	0.000
3	Sand Filling	0.000
4	Sand bag	1.302 1.266
5	bamboo piles	0.064 0.077
	SUB TOTAL	1.366 1.343
	GRAND SUB TOTAL	1.366 1.343

PS 2
18/11/2021
JE
RWD

AE 18/11/21
RWD

EE 18/11/21
RWD

As Per S.E. RWD (W) Circle Muz
Latter No 1179 Dated 01/10/2021
Estimate has been revised by inspecting
E.E. RWD. (W) Division NPH 2 west

Technically sanctioned for Rs. 1.366 lacs
(Rs. one lac thirty six thousand six hundred).
only provisionally

21.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur
27.12.21

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		WRD 5.7.40	Sand bag Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/ As Per MB No. 2.8.3.9 & Page No. 1.3 to 1.3	Nos Total	3309 3,309.00	29.37 38.25	130275.33 426569.25
2		WRD 5.7.7	Labour for cutting and fixing of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I	M Total	120 120.00	53.52 64.00	6422.4 7687.20
Total Cost :-							134256.45

136697.73

Sgt 136698.00

8/11/21

18/11/21
D.E


18/11/21
D.E


Name of Road :- Mauna Bishunpur Mangal Sthan Road to Mauna Bishunpur Harijan Tola

Block :- Patedhi Belsar

Appendix - IV

Measurement for sand filling in sand bag								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1	3.5	1	30		2.5		1.5	112.5
Total								112.5
Nos of sand bag @0.0347 cum/bag								3309


Junior Engineer,
Rural Works Department,
Work Section,
Hajipur


Assistant Engineer,
Rural Works Department,
Work Sub Division,
Hajipur


Executive Engineer,
Rural Works Department,
Work Division,
Hajipur