

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Dhikha Mataiya Chok Bakhari Shiv Nagar Madho Mataiya	
DISTRICT		Vaishali	
DIVISION		Hajipur	
BLOCK		Vaishali	
TOTAL LENGTH OF ROAD	:	1.400	KM
CONSTRUCTION COST	:	0.886	Lac

**Submitted By :-
Executive Engineer
RWD Work Division, Hajipur**

~~0.928 kcal~~
0.86 kcal

Inspection Report for Flood Damage Work

Date:-

20/11/21

1 Name of PIUs :-

RWD, works division Hajipur

2 Name of Block/Road :-

Vashti / Dhikha Matiya charok Bakhari Shiv Nagar
Madho Matiya

(A) For Road:

1. Damage Location/Chainage :- 1st K.M.
2. Damage Length :- 0.0085 K.M.
3. Nature of Damage :- Flood
4. Details of Restoration Works :- Brickbat (35.845 m³) 600mm x 10m x 30cm x 5.0m
 - (i) Material being used in Restoration works:- Brickbats, Humebat
 - (ii) Equipment's/Tools being used in Restoration works:- J.C.B, Tractor & Labour
 - (iii) Procedure taken up in Restoration works:- Manual
 - (iv) Restored Length :- 0.0085 K.M.


(B) For Bridge:


work is satisfactory.


1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:-
 - (ii) Equipment's/Tools being used in Restoration works:-
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :-


20/11/21
J.E.

Signature of JE/AE/EE


20/11/21
J.E.


20/11/21
AE


20/11/21

Signature

(Name of Inspection)

प्रतिवेदन

कार्य का नाम:- हिफ्ट। मतेरा चौक बस्तारी मिक्कण्डा गावों मतेरा पथ


.....पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड- तेजापुर
वित्तीय वर्ष - 21-22
प्राक्कलित राशि - Rs. 0.86 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 0.86 लाख है,
....., प्रखंड- तेजापुर में यातायात बहाली हेतु आपातकालिन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक दिनांक द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है। MTS - 35


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

GENERAL ABSTRACT

Name of Road Dikhha Mataiya Chok Bakhari Shiv Nagar Madho Mataiya

District Vaishali

Block Vaishali

Division Hajipur

Length of Road (in Km) 1.400 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	0.740 / 0.772
3	Sand Filling	0.000
4	Sand bag	0.000
5	H.P.	0.121 / 0.114
	SUB TOTAL	0.861 / 0.886
	GRAND SUB TOTAL	0.886

1.814

0.114

0.928

0.928

0.861

[Signature]
20/11/21

JE
RWD

[Signature]
20/11/21

AE
RWD

[Signature]
20/11/21

EE
RWD

As Per S.E. RWD (W) Circle Muz
Letter No 1178 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD. (W) Division Muz west

Technically Sanctioned for Rs. 0.861 lac
(Rs. Eighty six thousand one hundred) only
(provisionally)

[Signature]
27/12/21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1			Providing and Laying of Brick Bats Providing laying spreading & compacting Brick Bats (Manual Means) As Per MB No. 2785 & Page No 4-4	Cum Total	35.845 35.845	2064.56 22697.8 2228.70 2453.47	74004.15 81260.26 80246.70 77494.13
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 As Per MB No. & Page No.	Cum Total	0.000 0.00	553.72	0.00
3		WRD 5.7.40	Sand bag Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/ As Per MB No. & Page No.	Nos Total	0 0.00	36.49	0.00
Total Cost :-							77494.13

5.5
27/11/14

As per
27/11/14
AE

27/11/14

80246.70
81260.26
74004.15

DETAILED COST ESTIMATE OF HUME PIPE

Sl. No.	SOR Item no.	Description	Qty. (Nos.)	Length (m)	Quantity	Unit	Rate (Rs)	Amount in Rs.
1 No.								
1	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per design in Single Row MB No..... & Page No-....	0	2.5	-	m	3,930.53	-
1	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 600 mm dia as per design in Single Row MB No.2785... & Page No-4-4	2	2.5	5.00	m	1576.90 1,454.50	7884.50 7,272.50
1	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 300 mm dia as per design in Single Row MB No.2785... & Page No-5-5	2	2.5	5.00	m	834.29	4,171.45
Grand Total :								14,443.95

1205595

Am 27/11

428/2011/27
A E

10/10/2021
F-5