

GENERAL ABSTRACT


Name of Road NH-77 Dharampur Phanchayat Bhawan to Mothaha Yadav Tola Ram Das Rai House Tak
District Muzaffarpur
Block Minapur
Division Muzaffarpur East-2
Length of Road (in Km)

Sl no	DESCRIPTION	AMOUNT (LAKHS)
1	Brick-Bats	272,651.53 285383.82
2	H.P	42,826.58 37559.70
	GARAND SUB TOTAL	310,500.43 327143.52
TOTAL COST OF PROJECT IN LACS=		315,527.53 327144.00

3,15,496.15 Rs, 3.272 Lacs,


31.10.2021
J.E



31/10/21
A.E


9/11/20
E.E
~~3.156 Lacs~~
3.155 Lacs

Technically Approved for Rs 3.106 Lacs (Rs Three Lacs
Ten thousand Six hundred) only
Technically Approved for Rs 3.156 Lacs (Rs Three Lacs
fifteen thousand Six hundred) only

As Per S.E. RWD (W) Circle Muz.
Letter No. 1472/2021 dated 04/10/2021
Estimate No. 1472/2021 dated 04/10/2021
E.E. RWD. (W) Division Muz. East-1

Technically ^{sanctioned} Approved for Rs. 3.155 lacs
(Rs. Three lacs fifteen thousand five
hundred) only provisionally


21.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur


21.12.21

Name of Work

NH-77 Dharampur Phanchayat Bhawan to Mothaha Yadav Tola Ram Das Rai House Tak

Sl no	SDB Sl No	MORD Ref No	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick-Bats Providing and Laying of Brick Bats Providing laying spreading & compaction Brick Bats including Spreading in Uniform thickness hand packing (Manual Means)	Cum	132.05	2064.56	2,73,625.15 279651.59
2		11.20	Appendix-I Providing and laying reinforced cement concrete pile NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry			4287.10 3793.89	42871.00 37938.90
			1000mm dia	RM	10.00	-4175.97	41759.70
			Total				-327448.52

315 496.155
315 572.52
310 590.49

By
E.E

A.E
31/10/17

J.E
31.10.2021

Say 3106 lay
Say 3155 lay

Inspection Report for Flood Damage Work

Date:- 27.11.2021

1 Name of PIUs :- EE, RWD, Muzaffarpur East-II

2 Name of Block/Road :- minepur / NH-77 Dherampur Panchayat Bhawan to
Prathaha Jader to Ram Das Rai house tan.

(A) For Road:

1. Damage Location/Chainage :- 60/10, 0.485 km
2. Damage Length :- 0.041 km
3. Nature of Damage :- cuts in road
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:- NP3 heavy pipe of 1000 mm dia and brick bats 132.05 m³ S.A. 1/20/21
 - (ii) Equipment's/Tools being used in Restoration works:- Tractor, JCB
 - (iii) Procedure taken up in Restoration works:- Departmental
 - (iv) Restored Length :- 0.041 km

(B) For Bridge:

1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:-
 - (ii) Equipment's/Tools being used in Restoration works:-
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :-

27.11.2021

Signature of JE/AE/EE

9/11/21

27.11.21

Signature
Executive Engineer
R. W. D. Inspection Division
Muzaffarpur East-I