

प्रतिवेदन

शीर्ष :- FDR Part 'A' (Temporary Restoration)

पथ का नाम :- Restoration of Road from Kurhani / Repair of Repair of PMGSY
Rampur Naika hat to Rampur Balra Sahni tola Under F.D.R.

प्रखंड:- कुदनी
प्राक्कलित राशि:- 7.897 लाख
पथ की लम्बाई 1.121 KM

प्रस्तुत प्राक्कलन वर्ष 2021 में आई अति वृष्टि / बाढ़ के पानी का तीव्र प्रवाह के कारण पथ में काफी कटान / टूटान हो गया है। जिसके कारण आमजन को काफी कठिनाई के साथ-साथ आवागमन अवरुद्ध हो गया। विभागीय निर्देश के आलोक में प्रशासनिक विधि व्यवस्था एवं आवागमन प्रभावित नहीं होने देने के मद्देनजर क्षतिग्रस्त भाग में ब्रिक्स बट्स (ईट का टुकड़ा) से भराई कर उसके ऊपर रोड रोलर से COMPACTION का कार्य कराया गया है।

साथ ही प्राक्कलन में प्रयुक्त सामग्रियों वर्तमान अनुसूचित दर के आधार पर नये श्रम एवं सामग्री दर को प्रावधानित कर दर वि श्लेषण किया गया है। प्राक्कलन स्वीकृति हेतु समर्पित किया जाता है।

MIS FDR module में की गई ऑनलाइन प्रविष्टि की प्रति संलग्न है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा कुदनी



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल कुदनी



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल गुजपफरपुर पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIDs : EE, RWD (W) DIV -Muzaffarpur East -1
- 2 Name of Block/Road:- Kurhani / Repair of Repair of road from PMGSY Rampur Nalka hat to Rampur Balra Sahn tola

A For Road

- 1 Damage Location/Chainage:- At many places.
- 2 Damage Length: 0.093 km
- 3 Nature of Damage:-C/W,R/W Breached & embankment damaged.
- 4 Details of Restoration Works:-Brick Bats -365.38 cum
 - i Material being used in Restoration Works:-Brick bats. **Work is Satisfactory.**
 - ii Equipments/Tools being used in Restoration Works:- Roller, tractor,tipper,trailer,jcb, manual tools.
 - iii Procedure Taken up in Restoration Works:-Breached portion is filled with Brick bats & embankment repaired for protected from further damaged due to flood water using Brick bats.
 - iv Restored Length:- 0.093 km

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length

Signature of JE/AE/EE

K. Anshu
29/11/21
AE

Signature

(Name of Inspector)

GENERAL ABSTRACT

Name of the Road :- PMGSY Rampur Naika hat to Rampur Balra Sahni tola
District Muzaffarpur
Block Kurhani
Division Muzaffarpur East-1

Length of Road (in Km) 1.121 KM

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	7.843 - 7.897
2	Sand Filling	0.000
3	Sand bag	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	7.843 - 7.897
TOTAL COST OF PROJECT IN LACS =		7.843 - 7.897

Say Rs. 7.84 Lacs

[Signature]
JE
RWD

K. Anilish
25/11/21
AE
RWD

[Signature]
EE
RWD

As Per S.E. FWD (W) Circle Muz
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division Mahmer

Technically Sanctioned for Rs. 7.84 Lacs (Provisionally)
Lacs eighty four thousand only (Provisionally)

[Signature]
31.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur
[Signature]
31.12.21

Name of the Road :- PMGSY Rampur Naika hat to Rampur Balra Sahni tola

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat <i>brick bats</i> Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do - danger signal etc. Including cost of labour and Materials .all complete				
			Appendix - I	Cum	365.4	1809.41	661151.46
				Total	365.38	2161.18	789660.38
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	0.000		
				Total	0.00	0.00	0.00
Total Cost :-							789660.38

N. K. Singh
A.E.

K. Anshu
25/11/21
A.E.

S. P. Singh
5-12-21
SP 10/6

GST 12% 79338.17
LC 1% 6611.51
37221.26
784432.240