

प्रतिवेदन

शीर्ष :- FDR Part 'A' (Temporary Restoration)


पथ का नाम :- Restoration of Road from L068 to Kishunpur Belaur Kawadi Tola Under F.D.R.

प्रखंड:- कुढ़नी
 प्राक्कलित राशि:- 2.671 लाख
 पथ की लम्बाई 1.935 KM


प्रस्तुत प्राक्कलन वर्ष 2021 में आई अति वृष्टि / बाढ़ के पानी का तीव्र प्रवाह के कारण पथ में काफी कटान/टूटान हो गया है। जिसके कारण आमजन को काफी कठिनाई के साथ-साथ आवागमन अवरुद्ध हो गया। विभागीय निर्देश के आलोक में प्रशासनिक विधि व्यवस्था एवं आवागमन प्रभावित नहीं होने देने के मद्देनजर क्षतिग्रस्त भाग में ब्रिक्स बट्स (ईट का टुकड़ा) से भराई कर उसके ऊपर रोड रोलर से COMPACTION का कार्य कराया गया है। साथ ही प्राक्कलन में प्रयुक्त सामग्रियों वर्तमान अनुसूचित दर के आधार पर नये श्रम एवं सामग्री दर को प्रावधानित कर दर वि श्लेषण किया गया है। प्राक्कलन स्वीकृति हेतु समर्पित किया जाता है। MIS FDR module में की गई ऑनलाइन प्रविष्टि की प्रति संलग्न है।



कनीय अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रशाखा कुढ़नी



सहायक अभियंता
 ग्रामीण कार्य विभाग
 कार्य अवर प्रमंडल कुढ़नी



कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल मुजफ्फरपुर पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs :- EE , RWD (W) DIV -Muzaffarpur East -1
- 2 Name of Block/Road 94 L068 to Kishunpur Belaur Kawadi Tola


A For Road


- 1 Damage Location/Chainage:- **At many places.**
- 2 Damage Length:-**0.1143 km**
- 3 Nature of Damage:-C/W,R/W Breached & embankment damaged.
- 4 Details of Restoration Works:-**Brick Bats – 124.46 cum**
 - i Material being used in Restoration Works:-**Brick bats. Work is Satisfactory.**
 - ii Equipments/Tools being used in Restoration Works:- **Roller, tractor,tipper,trailer,jcb, manual tools.**
 - iii Procedure Taken up in Restoration Works:-**Breached portion is filled with Brick bats & embankment repaired for protected from further damaged due to flood water using Brick bats.**
 - iv Restored Length:- **0.1143 km**

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length


Signature of JE/AE/EE


K Anilish
25/11/21
A-E


29.11.21


Signature
(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-	94 L068 to Kishunpur Belaur Kawadi Tola		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Kurhani		
TOTAL LENGTH OF ROAD	:	1.935	KM
CONSTRUCTION COST	:	2671 2.67	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

GENERAL ABSTRACT

Name of the Road :-

94 L068 to Kishunpur Belaur Kawadi Tola

District

Muzaffarpur

Block

Kurhani

Division


Muzaffarpur East-1

Length of Road (in Km)


1.935 KM

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	2.671
2	Sand Filling	0.000
3	Sand bag	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	2.671
TOTAL COST OF PROJECT IN LACS =		2.671


Say Rs. 2.67 Lacs



JE
RWD



AE
RWD



EE
RWD


As Per S.E. RWD (N) Circle Muz

Letter No 1174 Dated 01/10/2021

Estimate has been verified by inspecting

E. E. RWD. (N) Division Muzaffarpur

Technically sanctioned for Rs. 2.67 Lacs (Rs. Two Lacs
Sixty Seven thousand) only (provisionally)


31.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur


31.12.21

Name of the Road :- 94 L068 to Kishunpur Belaur Kawadi Tola

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat <i>Brick bats</i> Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do - danger signal etc. - Including cost of labour and Materials .all complete				
			Appendix - I	Cum	124.5		225209.13
			Total		124.46	1809.49	225212.56
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical Specification Clause 305.3.9				
			Appendix - II	Cum			
			Total		0.00	0.00	0.00
Sub Total Cost							225212.56
GST 12%							27025.51
LC 01%							2252.13
SF (101.47/cum)							12629.15
Total Cost :-							267119.35

267165.05

12678.74

7025.09

2252.09

K. Dinkar
25/11/21
SRE

S. S. S.
29/11/21