

प्रतिवेदन

शीर्ष :- FDR Part 'A' (Temporary Restoration)

पथ का नाम :- Restoration of Road from T02 Sahpur Maricha Chowk to Sahpur Maricha Bhumihaar And Mall Tola. Under F.D.R.

प्रखंड:- कुदनी
प्राक्कलित राशि:- 21.210 लाख
पथ की लम्बाई 1.214 KM

प्रस्तुत प्राक्कलन वर्ष 2021 में आई अति गृष्टि/बाढ़ के पानी का तीव्र प्रवाह के कारण पथ में काफी कटान/दूटान हो गया है। जिसके कारण आगमन को काफी कठिनाई के साथ-साथ आवागमन अवरुद्ध हो गया। विभागीय निर्देश के आलोक में प्रशासनिक विधि ध्वस्त एवं आवागमन प्रभावित नहीं होने देने के मद्देनजर क्षतिग्रस्त भाग में ब्रिक्स बट्स (ईट का टुकड़ा) से भराई कर उसको ऊपर रोड रोतर से COMPACTION का कार्य कराया गया है। साथ ही प्राक्कलन में प्रयुक्त सामग्रियों वर्तमान अनुसूचित दर के आधार पर नये श्रम एवं सामग्री दर को प्राक्कलित कर दर विरलेषण किया गया है। प्राक्कलन स्वीकृति हेतु समर्पित किया जाता है।

MIS FDR module में की गई ऑनलाइन प्रविष्टि की प्रति संलग्न है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा कुदनी



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल कुदनी



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फरपुर पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs :-EE , RWD (W) DIV -Muzaffarpur East -1
- 2 Name of Block/Road:- T02 Sahpur Maricha Chowk to Sahpur Maricha Bhumihar And Mali Tola.

A For Road

- 1 Damage Location/Chainage:- At many places.
- 2 Damage Length:-0.236 km
- 3 Nature of Damage:-C/W,R/W Breached & embankment damaged.
- 4 Details of Restoration Works:-Brick Bats – 988.53 cum
 - i Material being used in Restoration Works:-Brick bats. **Work is Satisfactory.**
 - ii Equipments/Tools being used in Restoration Works:- Roller, tractor,tipper,trailer,jcb, manual tools.
 - iii Procedure Taken up in Restoration Works:-Breached portion is filled with Brick bats & embankment repaired for protected from further damaged due to flood water using Brick bats.
 - iv Restored Length:- 0.236 km

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)



ग्रामीण कार्य विभाग


Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR




Name of the Road :-	T02 Sahpur Maricha Chowk to Sahpur Maricha Bhumihar And Mall Tola		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Kurhani		
TOTAL LENGTH OF ROAD	:	1.214	KM
CONSTRUCTION COST	:	21.216 21.22	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

GENERAL ABSTRACT		
Name of the Road :-		T02 Sahpur Maricha Chowk to Sahpur Maricha Bhumihar And Mali Tola
District	Muzaffarpur	
Block	Kurhani	
Division	Muzaffarpur East-I	
Length of Road (In Km)		1.214 KM
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	21.219 21.215
2	Sand Filling	0.000
3	Sand bag	0.000
4	Bamboo Piles	0.000
GRAND SUB TOTAL		21.219 21.215
TOTAL COST OF PROJECT IN LACS =		21.219 21.215
		Say 21.22 Lacs
 JE RWD  AE RWD  EE RWD		

As Per S.E. RWD (H) Circle Muz.
 Letter No 1179 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. RWD. (H) Division 1446/2021

Technically Sanctioned for Rs. 21.22 lacs (Rs. Twenty
 one lacs twenty two thousand) only (provisionally)


 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur
 31/12/21

Name of the Road :- T02 Sahpur Maricha Chowk to Sahpur Maricha Bhumihar And Mali Tola

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat <i>brick bats</i> Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller driver and khelasi making and maintaining diversion light barrier - do - do - danger signal etc. Including cost of labour and Materials .all complete				
			Appendix - I	Cum	988.5		1788680.87
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9	Total	988.53	1809.49	1788735.45
			Appendix - II	Cum			
			Total	Total	0.00	0.00	0.00
Sub Total Cost							1788735.45
GST 12%							214648.22
LC 01%							17887.35
SF (101.47/cum)							100306.14
Total Cost :-							2121576.86

[Signature]
Jte

K. D. D. D.
25/11/21
AE

[Signature]
28.11.21

21.21907.16
21.219 day