

Inspection Report for Flood Damage Work

Date

1 Name of PILs

mv2 east of

2 Name of Block/Road

shripur moniya folia hotel near f
Seraiya Belli/wann Road side.

A For Road

1 Damage Location/Chainage

many location

2 Damage Length

250 m

3 Nature of Damage

Beach due to flood

4 Details of Restoration Works

i Material being used in Restoration Works

Bamboo 660m, 240m
Bricks Buts. E.C. Bag with lac
358.55 m³ 3500 bags

ii Equipments/Tools being used in Restoration Works

Roller, L.C. B, Tractor

iii Procedure Taken up in Restoration Works

N/A

iv Restored Length

250 m
N/A

The work found satisfactory.

B For Bridge

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works

i Material being used in Restoration Works

ii Equipments/Tools being used in Restoration Works

iii Procedure Taken up in Restoration Works

iv Restored Length

N/A

Signature of JE/AE/EE

[Signature]

24-11-17

Signature of Inspector
(Name of Inspector)
प्रमाणित अभियन्ता
काम प्रमण्डल, महानगर

FDR

YEAR (2021-2022)

GENERAL ABSTRACT OF COST

Restoration of Road from Shivpur Nariya Tola Hote Hue to
Saraiya Bahilwara Road tak in Saraiya Block under F.D.R. RWD,
Works Division, Muzaffarpur East-1

Block :- Saraiya

District :- Muzaffarpur

Sl
No.

Description

Amount

Road Restoration Cost

- Rs.

9,58,757.00
9,58,100.00

Total

9,58,100.00

Say Rs.

9,58,100.00

Say Rs. 9. 158 Lacs

[Signature]
Junior Engineer
RWD, Works Section
Saraiya

Assistant Engineer
RWD, Works Sub-Div.
Saraiya

[Signature]
Executive Engineer
RWD, Works Division
Muzaffarpur East-1

As Per S.E. RWD (M) Circle Muz.
Letter No 1174 dated 01/10/2021
Expenditure has been verified by inspecting
E.E. RWD. (M) Division Muzaffarpur

Technically Sanctioned for Rs. 9.158 Lacs (Rs. Nine
Lacs fifteen thousand eight hundred) only (Provisionally)

[Signature]
Superintending Engineer
Rural Works Department
Work Circle Muzaffarpur

27/12/21

Abstract of Cost & Detailed Estimate for
Restoration of Road from Shivpur Noniya Tola Hote Hue to Saraiya
Bahilwara Road tak in Saraiya Block under F.D.R., RWD, Works
Division, Muzaffarpur East-1

Sl. No.	SO R	Item of Work	Quantity	Unit	Rate	Amount
1		2	6	7	8	9
1		Providing and laying Brick bats, including all taxes etc. all complete job as per specification and direction of E/I.			2064.86	240248.00
		As per M.B	358.550	m ³	2107.18	774891.00
2		Providing E.C. Bag filled with Local Sand etc. all complete job as per specification and direction of E/I.			39.37	137,795.00
		As per M.B	3500.00	Bgs	38.25	433875.00
3		Providing Bamboo Pile etc. all complete job as per specification and direction of E/I.			53.53	32118.00
		As per M.B	600.00	m	54.00	32436.00
4		Providing Bamboo Runners etc. all complete job as per specification and direction of E/I.			16.46	5596.00
		As per M.B	340.00	m	31.83	10822.00
5	5.6. 2.4	Labour for laying, fitting and fixing NP3 pipe with collars in line level and grade as well providing approved jointing materials and joints properly filled to make them water proof all complete as per specification and direction of E/I. (Hume pipe available within a lead of 40 mtr 1000 mm dia or 100 mm dia NP3 H.P)				
		As per M.B	0.00	m	3992.28	0.00
					Total Rs.	9,58,024.00
					Say Rs.	9,58,100.00

[Signature]
Junior Engineer
RWD, Works Section
Saraiya

Assitant Engineer
RWD, Works Sub-Div.
Saraiya

[Signature]
24.11.21
Executive Engineer
RWD, Works Division
Muzaffarpur East-1