



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILS PROJECT REPORT FOR MOTERABLE (FDR)

YEAR (2021-2022)



DISTRICT	:-	SHEIKHPURA
BLOCK	:-	GHAT KUSUMBHA
NAME OF BRIDGE	:-	Construction of Bridge on Sirari-Koyla Road Alapur over Gankhoriya Soti.(BR-31R-100)
TOTAL LENGTH OF BRIDGE	:-	0.024 KM
TOTAL LENGTH OF DAMAGE PART	:-	0.024 KM
TOTAL LENGTH OF EFFECTIVE PART	:-	0.040 KM
TOTAL COST OF EMERGENT REPAIR	:-	1.91 Lac
AVERAGE COST PER KM	:-	79.66 Lac
TOTAL COST OF PROJECT	:-	1.91 Lac

SUBMITTED BY:

EXECUTIVE ENGINEER
RWD (W) DIVISION, MUNGER
SHEIKHPURA

स्थल निरीक्षण प्रतिवेदन

वर्ष-2021-22 के बाढ़ में क्षतिग्रस्त पथों में कराये गए मोटरेबुल कार्य की जाँच।


पुल का नाम :- घाटकुसुम्मा प्रखण्ड अन्तर्गत सिरारी-कोयला-आलापुर पथ में गनखोरिया सोती पर बने पुल के पहुँच पथ।

पुल के पहुँच पथ की लम्बाई :- 24मीटर

प्राक्कलित राशि :- 1.91/- लाख।

अधीक्षण अभियन्ता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर के पत्रांक-1162 दिनांक 16.11.2021 द्वारा प्राप्त निदेश के अनुपालन में आज दिनांक 22.11.2021 को ग्रामीण कार्य विभाग, कार्य प्रमण्डल, शेखपुरा के अधीन बाढ़ से क्षतिग्रस्त पथ का निरीक्षण सहायक अभियन्ता, श्री जितेन्द्र तिवारी के साथ वर्ष 2021-22 में बाढ़ में क्षतिग्रस्त पथ का कराये गए मोटरेबुल कार्य का स्थल निरीक्षण किया। जाँच के समय कार्य प्रमण्डल, शेखपुरा के कार्यपालक अभियन्ता श्री विमल कुमार, सहायक अभियन्ता श्री अनिल कुमार, एवं कनीय अभियन्ता श्री पंकज कुमार उपस्थित रहे।

उक्त पहुँच पथ के निरीक्षण के दौरान पाया गया कि पहुँच पथ में बने बड़े गड्ढों में Moorum से भरकर उसके उपर G.S.B. (Gr.II) (जगह-जगह 200mm एवं 150mm मुटाई में) डालकर सम्पीडन का कार्य कराया गया है, जिसका शत प्रतिशत जाँच किया गया है, एवं उक्त पहुँच पथ के प्राक्कलन एवं मापीपुस्त में दर्ज की गई मापी को कार्य स्थल के अनुसार पाया।


सहायक अभियन्ता
ग्रा0का0वि0, कार्य प्रमं0
झाड़ा


कार्यपालक अभियन्ता
ग्रा0का0वि0, कार्य प्रमं0
झाड़ा

DETAILS PROJECT REPORT FOR MOTERABLE (FDR)
YEAR (2021-2022)

GENERAL ABSTRACT OF COST

Block:--GHAT KUSUMBHA

District:--SHEIKHPURA

Length of Road:-- 0.024 KM

Name of Road:-- Construction of Bridge on Sirari-Koyla Road Alapur over
Gankhoriya Soti.(BR-31R-100)

Sl. No.	Item of Work	Amount
A	COST OF EMARGENT REPAIR	1.67 Lacs
B	ADD 1% LABOUR CESS ON EMERGENT REPAIR	0.02 Lacs
C	ADD 12% GST ON EMERGENT REPAIR	0.20 Lacs
D	ADD 10% SEGNIORAGE FEE ON EMERGENT REPAIR	0.02 Lacs
E	TOTAL COST OF EMERGENT REPAIR	1.91 Lacs
F	AVERAGE COST PER KM	79.66 Lacs
G	FIVE YEAR MAINTENANCE COST INCLUDING LABOUR CESS & GST	0.00 Lacs
TOTAL COST FOR EMERGENT REPAIR OF ROAD		1.91 Lacs


Junior Engineer
RWD (w)
Division,Sheikhpura


Asstt. Engineer
RWD (w) Division,Sheikhpura


Executive Engineer
RWD (w)
Division,Sheikhpura

Ref. E.E. Letter No. 1720 dt. 23.11.2021
② Technically ^{Sanctioned} Approved for Rs. 1.91 Lakh
(Rupees one lakh ninety
one thousand.....) Only
for Construction work & 5 Years Maintenance.
Certified Copy


Superintending Engineer
Rural Works Department
Works Circle, Munger


Superintending Engineer
Rural Works Department
Works Circle, Munger