



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILS PROJECT REPORT FOR MOTERABLE (FDR)

YEAR (2021-2022)



DISTRICT	:-	SHEIKHPURA
BLOCK	:-	GHAT KUSUMBHA
NAME OF BRIDGE	:-	Construction of Bridge At Khandua 03 of Road from T01-T01 Bhadaus More Sirari Mahsar Koyla Baoghat Road (BR-21D.000)
TOTAL LENGTH OF BRIDGE	:-	0.030 KM
TOTAL LENGTH OF DAMAGE PART	:-	0.300 KM
TOTAL LENGTH OF EFFECTIVE PART	:-	0.032 KM
TOTAL COST OF EMERGENT REPAIR	:-	1.53 Lac
AVERAGE COST PER KM	:-	50.98 Lac
TOTAL COST OF PROJECT	:-	1.53 Lac

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD (W) DIVISION, MUNGER
SHEIKHPURA

स्थल निरीक्षण प्रतिवेदन

वर्ष-2021-22 के बाढ़ में क्षतिग्रस्त पथों में कराये गए मोटरबुल कार्य की जाँच।

पुल का नाम :- घाटकुसुम्मा प्रखण्ड अन्तर्गत T01 मदीस मोड़ सिरारी महत्तार कोचला बाउघाट
पथ में खंघा-03 पर पुल का पहुँच पथ।

पुल के पहुँच पथ की लम्बाई :- 30मीटर।

प्राक्कलित राशि :- 1.53/- लाख।

अधीक्षण अभियन्ता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर के पत्रांक-1162

दिनांक 18.11.2021 द्वारा प्राप्त निदेश के अनुपालन में आज दिनांक 22.11.2021 को ग्रामीण कार्य विभाग, कार्य प्रमण्डल, शेखपुरा के अधीन बाढ़ से क्षतिग्रस्त पथ का निरीक्षण सहायक अभियन्ता, श्री जितेन्द्र तिवारी के साथ वर्ष 2021-22 में बाढ़ में क्षतिग्रस्त पथ का कराये गए मोटरबुल कार्य का स्थल निरीक्षण किया। जाँच के समय कार्य प्रमण्डल, शेखपुरा के कार्यपालक अभियन्ता श्री विमल कुमार, सहायक अभियन्ता श्री अनिल कुमार, एवं कनीय अभियन्ता श्री पंकज कुमार उपस्थित रहे।

उक्त पहुँच पथ के निरीक्षण के दौरान पाया गया कि पहुँच पथ में बने बड़े गड्ढों में Moorum डालकर उसके उपर G.S.B. (Gr.II) (जगह-जगह 200mm मुटाई में) समीपन का कार्य कराया गया है, जिसका शत प्रतिशत जाँच किया गया है, एवं उक्त पहुँच पथ के प्राक्कलन एवं मापीपुस्त में दर्ज की गई मापी को कार्य स्थल के अनुसार पाया।


सहायक अभियन्ता
प्रा०का०वि०, कार्य प्रम०
आशा


कार्यपालक अभियन्ता
प्रा०का०वि०, कार्य प्रम०
आशा

DETAILS PROJECT REPORT FOR MOTERABLE (FDR)

YEAR (2021-2022)

GENERAL ABSTRACT OF COST

Block:--GHAT KUSUMBHA

District:--SHEIKHPURA

Length of Road:-- 0.030 KM

Name of Road:-- Construction of Bridge At- Khanda-03 of Road from T01-T01
Bhadaus More Sirari Mahsar Koyla Baoghat Road (BR-31R-098)

SL. No.	Item of Work	Amount
A	COST OF EMARGENT REPAIR	1.34 Lacs
B	ADD 1% LABOUR CESS ON EMERGENT REPAIR	0.01 Lacs
C	ADD 12% GST ON EMERGENT REPAIR	0.16 Lacs
D	ADD 10% SEGNIORAGE FEE ON EMERGENT REPAIR	0.02 Lacs
E	TOTAL COST OF EMERGENT REPAIR	1.53 Lacs
F	AVERAGE COST PER KM	50.98 Lacs
G	FIVE YEAR MAINTENANCE COST INCLUDING LABOUR CESS & GST	0.00 Lacs
TOTAL COST FOR EMERGENT REPAIR OF ROAD		1.53 Lacs


Junior Engineer
RWD (w)
Division,Sheikhpura


Asstt. Engineer
RWD (w) Division,Sheikhpura



Executive Engineer
RWD (w)
Division,Sheikhpura

Ref. E.E. Letter No. 1720 dt. 23.11.2021

① ^{Sanctioned} Technically Approved for Rs. 1.53 lakh
(Rupees one lakh fifty
three thousand) Only

for construction work & 5 Years Maintenance.

Certified Copy


Superintending Engineer
Rural Works Department
Works Circle, Munger


Superintending Engineer
Rural Works Department
Works Circle, Munger