



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILS PROJECT REPORT FOR MOTERABLE (FDR)

YEAR (2021-2022)



DISTRICT	:-	SHEIKHPURA
BLOCK	:-	GHAT KUSUMBHA
NAME OF BRIDGE	:-	Construction of Bridge Over Kanuhari Soti At T01-T01 Bhadaus More Sirari Mahsar Koyla Baoghat Road (BR-31R-096)
TOTAL LENGTH OF BRIDGE	:-	0.025 KM
TOTAL LENGTH OF DAMAGE PART	:-	0.025 KM
TOTAL LENGTH OF EFFECTIVE PART	:-	0.075 KM
TOTAL COST OF EMERGENT REPAIR	:-	2.53 Lac
AVERAGE COST PER KM	:-	101.22 Lac
TOTAL COST OF PROJECT	:-	2.53 Lac

SUBMITTED BY:

EXECUTIVE ENGINEER
RWD (W) DIVISION, MUNGER
SHEIKHPURA

स्थल निरीक्षण प्रतिवेदन

वर्ष-2021-22 के बाढ़ में क्षतिग्रस्त पथों में कराये गए मोटरेबुल कार्य की जाँच।

पुल का नाम :-


घाटकुसुमा प्रखण्ड अन्तर्गत T01 भदौस मोड़ सिरारी महसार कोयला बासघाट पथ में कनुहारी सोती पर बने पुल के पहुँच पथ।

पुल के पहुँच पथ की लम्बाई :- 25 मीटर।

प्राक्कलित राशि :- 2.53/- लाख।

अधीक्षण अभियन्ता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर के पत्रांक-1162 दिनांक 16.11.2021 द्वारा प्राप्त निदेश के अनुपालन में आज दिनांक 22.11.2021 को ग्रामीण कार्य विभाग, कार्य प्रमण्डल, शेखपुरा के अधीन बाढ़ से क्षतिग्रस्त पथ का निरीक्षण सहायक अभियन्ता, श्री जितेन्द्र तिवारी के साथ वर्ष 2021-22 में बाढ़ में क्षतिग्रस्त पथ का कराये गए मोटरेबुल कार्य का स्थल निरीक्षण किया। जाँच के समय कार्य प्रमण्डल, शेखपुरा के कार्यपालक अभियन्ता श्री विमल कुमार, सहायक अभियन्ता श्री अनिल कुमार, एवं कनीय अभियन्ता श्री पंकज कुमार उपस्थित रहे।

उक्त पहुँच पथ के निरीक्षण के दौरान पाया गया कि पहुँच पथ में बने बड़े गड्ढों में Moorum डालकर उसके ऊपर G.S.B. (Gr.II) (जगह-जगह 200mm मुटाई में) समीपन का कार्य कराया गया है, जिसका शत प्रतिशत जाँच किया गया है, एवं उक्त पहुँच पथ के प्राक्कलन एवं मापीपुस्त में दर्ज की गई मापी को कार्य स्थल के अनुसार पाया।


सहायक अभियन्ता
ग्राहकाधिकार, कार्य प्रमण्डल
झाझा


कार्यपालक अभियन्ता
ग्राहकाधिकार, कार्य प्रमण्डल
झाझा
92.11.2021

DETAILS PROJECT REPORT FOR MOTERABLE (FDR)

YEAR (2021-2022)

GENERAL ABSTRACT OF COST


Block:--GHAT KUSUMBHA


District:--SHEIKHPURA


Length of Road:-- 0.025 KM

Name of Road:-- Construction of Bridge Over Kanuhari Soti At T01-T01 Bhadaus
More Sirari Mahsar Koyla Baoghat Road (BR-31R-096)

SL. No.	Item of Work	Amount
A	COST OF EMARGENT REPAIR	2.22 Lacs
B	ADD 1% LABOUR CESS ON EMERGENT REPAIR	0.02 Lacs
C	ADD 12% GST ON EMERGENT REPAIR	0.27 Lacs
D	ADD 10% SEGNORAGE FEE ON EMERGENT REPAIR	0.02 Lacs
E	TOTAL COST OF EMERGENT REPAIR	2.53 Lacs
F	AVERAGE COST PER KM	101.22 Lacs
G	FIVE YEAR MAINTENANCE COST INCLUDING LABOUR CESS & GST	0.00 Lacs
TOTAL COST FOR EMERGENT REPAIR OF ROAD		2.53 Lacs


Junior Engineer
RWD (w)
Division,Sheikhpura


Asstt. Engineer
RWD (w) Division,Sheikhpura


Executive Engineer
RWD (w)
Division,Sheikhpura

Ref. E.E. Letter No. 1720 23.11.2021

① ^{Sanctioned} Technically Approved for Rs. 2.53 Lakh

(Rupees Two Lakh Fifty
three thousand Only)

for construction work & 5 Years Maintenance.

Certified copy

Sanctioned

Superintending Engineer
Rural Works Department
Works Circle, Munger

Ed
Superintending Engineer
Rural Works Department
Works Circle, Munger