



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

2021-22

FDR

FLOOD DAMAGED REPORT




Restoration of Road From Hasanpur Panja Chowk To Hasanpur High MMGSY[SC]hool Via Bajrangbali Mandir Near River Ganga


DISTRICT	:-	Vaishali	
DIVISION	:-	Mahnar	
BLOCK	:-	Mahnar	
TOTAL LENGTH OF ROAD	:-	0.600	KM
ART-A TOTAL COST OF INTIAL RECTIFICATION / RESTORATION	:-	2.02	Lac
TOTAL COST OF PROJECT	:-	2.02	Lac


प्रतिवेदन

1. पथ का नाम :- Hasampur Panna Chocole to Hasampur Highway (School via Baranagali Mandir Near River Ganga)
2. पथ की लम्बाई :- 0.600 km
3. प्रखण्ड का नाम :- महनार
4. क्षतिग्रस्त की लम्बाई :- 0.080 km
5. प्राक्कलित राशि :- 2.02 लाख
6. वर्ष-2021 का बाढ़ एवं अतिवृष्टि :-

यह प्राक्कलन उक्त पथ के वर्ष-2021 में आई बाढ़/अतिवृष्टि के कारण
चैनेज..... CM 450 to 600mm चैनेज
कुल 80 मीटर में पथ की हुई क्षति के अस्थायी मरम्मत/पुनर्स्थापन कार्य का है।
इस मूल पथ की कुल लम्बाई- 0.600 कि०मी० है। यह पथ पंचवर्षीय अनुरक्षण अवधि
के अन्दर/बाहर है। इस प्राक्कलन में कराये गये अस्थायी मोटरेबुल कार्य मद आदि
सम्मिलित है। क्षतिग्रस्त कार्य MIS पर अंकित है तथा इसके फोटोग्राफ लिये जा चुके
हैं, जो संलग्न है। कराये जाने वाले कार्य के दर वर्तमान चालू अनुसूचित दर पर
आधारित है। यह प्राक्कलन विभागीय पत्रांक-4555, पटना, दिनांक-05.11.2021 एवं
विभागीय पत्र संख्या-4589, दिनांक-13.11.2021 से प्राप्त निदेशानुसार तैयार किया गया
है। यह पथ MIS के क्रमंक 73 पर अंकित है।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, महनार।

Inspection Report for Flood Damage Report

Date :

- 1 Name of PIUs : EE, Mahmar
- 2 Name of Block/ Road : Mahmar, Hasampur Panna Chowak to
→ Hasampur Agha Mubisy (S) School w/a
Batraangbali Mandir Near River Ganga,
- A. For Road
- 1 Damage Location/Chainage : CH 430 to 600 mtr
- 2 Damage Length : 0.08 km
- 3 Nature of Damage : Base
- 4 Details of Restoration Works : Brick bats, Local sand (Temporary Restoration)
- i. Material being used in Restoration works : Brick Bats, Local sand 94.13 cum
- ii. Equipments/Tools being used in Restoration works : Roller, Tanker, Tractor, Hammer
- iii. Procedure taken up in Restoration works : Brick Bats compacted with Roller
- iv. Restored Length : 80 mtr
- B For Bridge
- 1 Damage Location/Chainage :
- 2 Damage Length :
- 3 Nature of Damage : NA
- 4 Details of Restoration Works :
- i. Material being used in Restoration works :
- ii. Equipments/Tools being used in Restoration works :
- iii. Procedure taken up in Restoration works :
- iv. Restored Length :

Signature of JE / AE / EE

Signature
(Name of Inspector)

FLOOD DAMAGED REPORT

GENERAL ABSTRACT OF COST

Block:- Mahnar District:- Vaishali
Length of Road:- 0.600 KM
Name of Road:- Restoration of Road From Hasanpur Panja Chowk To Hasanpur High MMGSY[SC]hool
Via Bajrangball
Mandir Near River Ganga

SL. No.	Item of Work	Amount
A	TOTAL COST OF RECTIFICATION/ RESTORATION :	1.925 Lacs
B	Seigniorage 10% on material @ Rs 101.87 Per Cum 94.13 101.87 :	0.096 Lacs
	TOTAL :	2.021 Lacs

Say Rs. 2.02 Lacs

[Signature]
Junior Engineer

[Signature]
Asstt. Engineer

[Signature]
Executive Engineer

As Per S.E. RWD (W) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division *[Signature]* SE RWD

Technically Sanctioned for Rs. 2.02 Lacs (Rs. Two
lacs two thousand) only (provisionally)

[Signature]
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

GENERAL ABSTRACT OF COST FOR FDR

NAME OF ROAD :

Restoration of Road From Hasanpur Panja Chowk To Hasanpur High MMGSY[SC]hool Via Bajrangbali

DISTRICT

Vaishali

BLOCK

Mahnar

DIVISION

Mahnar

LENGTH OF ROAD (in Km)

0.600

Sl. No.	DESCRIPTION	Amount	1 % Labour Cess	12 % GST	GROSS AMOUNT (LAKHS)
	INITIAL RECTIFICATION /RESTORATION WORK				
1	BRICK BATS	170326.35	1703.264	20439.162	192468.778
TOTAL COST OF PROJECT IN LACS =		1.703	0.017	0.204	1.925

[Signature]
JE
8/11/22
RWD

[Signature]
8/11/22
AE
RWD

[Signature]
8/11/22
EE
RWD

[Faint handwritten text at the bottom of the page]

Sl. No.	SDB SL-NO	MORD RefNo	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	8.1.3.2	OLD SOR	BRICK BATS								
	(iii)		Providing brick bats including spreading laying hand packing and compacting with C.I.Hammer in layers not exceeding 75mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks.								
Qty taken from MB No 875					Vide Page No 01 to 02						
				Cum					94.13	1,809.48	1,70,326.35
TOTAL COST OF INITIAL RECTIFICATION / RESTORATION WORK											1,70,326.35

[Signature]
JE 8/1/22
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD