



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

ESTIMATE FOR FLOOD DAMAGED REPAIR

Bihar(बिहार)Map



Name of the Road :-

NH-80 Chimni Bhatta To Sabikpur village

DISTRICT	:	Lakhisarai	
DIVISION	:	Lakhisarai	
BLOCK	:	Lakhisarai	
TOTAL LENGTH OF ROAD	:	4.150 4.65	KM
TOTAL COST	:	9.565	Lac
AVERAGE COST PER KM	:	2.305	Lac
TOTAL COST OF PROJECT	:	9.565	Lac

Submitted By:
Executive Engineer
RWD WORKS DIVISION
Lakhisarai

स्थल निरीक्षण प्रतिवेदन

वर्ष 2021-22 के बाढ़ में क्षतिग्रस्त पथों में कराये गए मोटरेबुल कार्य की जाँच।

पथ का नाम :- NH-80 चिमनी भट्ठा साबिकपुर 15/11/21

पथ की लम्बाई :- 4.650 कि०मी०

प्राक्कलित राशि :- 9.565 /- लाख

अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर के पत्रांक 1162 दिनांक 16.11.2021 द्वारा प्राप्त निदेश के अनुपालन में आज दिनांक 21.11.2021 को ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय के अधीन बाढ़ से क्षतिग्रस्त पथ का निरीक्षण सहायक अभियंता श्री लौडिक प्रसाद राय के साथ वर्ष 2021-22 में बाढ़ में क्षतिग्रस्त पथ का कराये गए मोटरेबुल कार्य का स्थल निरीक्षण किया। जाँच के समय कार्य प्रखंडल, लखीसराय के सहायक अभियंता श्री संदीप कुमार एवं श्री ब्रजेश कुमार सिंह, कनीय अभियंता श्री श्याम सुन्दर प्रसाद एवं श्री रंजीत कुमार उपस्थित रहे।

उक्त पथ के निरीक्षण के दौरान पाया गया कि पथ में बने बड़े गड्ढों में Moorum से भरकर उसके उपर G.S.B. (Gr.II) (जगह-जगह 200mm एवं 150mm मुटाई में) डालकर सम्पीडन का कार्य कराया गया है, जिसका शत प्रतिशत जाँच किया गया है, एवं उक्त पथ के प्राक्कलन एवं मापीपुस्त में दर्ज की गई मापी को कार्य स्थल के अनुसार पाया।


सहायक अभियंता

ग्रा०का०वि०, कार्य प्रमं०

खड़गपुर-तारापुर


30/11/2021
कार्यपालक अभियंता

ग्रा०का०वि०, कार्य प्रमं०

खड़गपुर-तारापुर

ESTIMATE FOR FLOOD DAMAGED REPAIR

NAME OF ROAD : NH-80 Chimni Bhatta To Sabikpur

DISTRICT Lakhisarai

BLOCK Lakhisarai

DIVISION Lakhisarai

LENGTH OF ROAD (in Km) ~~4.150~~ 4.65

CD STRUCTURES 8

SI. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	RESTORATION COST	
1	EARTHWORK / SAND / MOORUM FILLING	1.306
2	Brick Bat Filling	5.859
3	GSB GR-II	0.942
	SUB TOTAL	8.107
	LABOUR CESS 1% of cost	0.081
	GST 12 % of cost	0.973
	SEIGNORAGE FEE @ 10 % on Minor Mines	0.404
	TOTAL	9.565
	TOTAL COST OF PROJECT IN LACS =	9.565

Deduct Contractor Profit 9.1% = - 0.870 Lakh

Total = Rs. 8.695 Lakh

RL
10/11/2021
JE
RWD

SL
10/11/2021
AE
RWD

W
10.11.21
EE
RWD

T.S Amount

Construction Cost: Rs. 9.565 lakh

Deduct Contractor Profit 9.1% = Rs. 0.870 lakh

Total = Rs. 8.695 lakh

Ref. E.E. Letter No. 548 dt. 18.4.2022
Technically Sanctioned for Rs. 8.695 lakh
(Rupees Eight lakh sixty nine
thousand five hundred) Only.
for construction work & 5 Years Maintenance.


Superintending Engineer
Rural Works Department
Works Circle, Munger


20/04/2022

NH-80 Chimni Bhatta To Sabikpur



NH-80 Chimni Bhatta To Sabikpur



NH-80 Chimni Bhatta To Sabikpur



Schedule XLV-Form No. 134

with the name given to section

1-2-2 DIVISION

1-2-2 SUB-DIVISION

MEASUREMENT BOOK - 681

[illegible]