



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

2021-22

FDR

FLOOD DAMAGED REPORT



Baghnocha - Hasanpur Chandel tola

DISTRICT	:-	Vaishali	
DIVISION	:-	Mahnar	
BLOCK	:-	Mahnar	
TOTAL LENGTH OF ROAD	:-	2.050	KM
PART-A TOTAL COST OF INTIAL RECTIFICATION / RESTORATION	:-	0.430 0.31	Lac
TOTAL COST OF PROJECT	:-	0.430 0.31	Lac

Inspection Report for Flood Damage Report


Date :


1 Name of PIUs	- EP, Mahnas
2 Name of Block/ Road	- Mahnas
A. For Road	: Bagmaoha Housanpur chandhtola
1 Damage Location/Chainage	: On 600 mtr Approx
2 Damage Length	: 10 mtr
3 Nature of Damage	: cutting of Rd
4 Details of Restoration Works	: Temp Restoration
i. Material being used in Restoration works	: Hume Pipe, Soil, Brick Bats 7.5" & found Sahilfuch.
ii. Equipments/Tools being used in Restoration works	: Roller, Protector, water tank
iii. Procedure taken up in Restoration works	: Hume pipe
iv. Restored Length	: 10 mtr
B For Bridge	: Hume Pipe
1 Damage Location/Chainage	: At CP 600 mtr
2 Damage Length	: 10 mtr
3 Nature of Damage	: Rd cutting
4 Details of Restoration Works	: Hume Pipe (Temp Restoration)
i. Material being used in Restoration works	: Hume Pipe, Soil, Brick Bats
ii. Equipments/Tools being used in Restoration works	: Roller, Protector water tank
iii. Procedure taken up in Restoration works	: Restoration Rd cutting
iv. Restored Length	: 10 mtr
Signature of JE / AE / EE	Signature (Name of Inspector) Executive Engineer R.W.D. Works Division Hajipur

प्रतिवेदन

1. पथ का नाम :- Baghmocha to Masapur Chandel Jola
2. पथ की लम्बाई :- 2.05 km
3. प्रखण्ड का नाम :- महनार
4. क्षतिग्रस्त की लम्बाई :- 0.0010 (10 मीटर)
5. प्राक्कलित राशि :- 0.43 लाख
6. वर्ष-2021 का बाढ़ एवं अतिवृष्टि :-

यह प्राक्कलन उक्त पथ के वर्ष-2021 में आई बाढ़/अतिवृष्टि के कारण
चैनैज..... CH 760 to 770 मीटर चैनैज
कुल 10.71 किलोमीटर में पथ की हुई क्षति के अस्थायी मरम्मत/पुनर्स्थापन कार्य का है।
इस मूल पथ की कुल लम्बाई- 2.05 कि०मी० है। यह पथ पंचवर्षीय अनुरक्षण अवधि
के अन्दर/बाहर है। इस प्राक्कलन में कराये गये अस्थायी मोटरेबुल कार्य मद आदि
सम्मिलित है। क्षतिग्रस्त कार्य MIS पर अंकित है तथा इसके फोटोग्राफ लिये जा चुके
हैं, जो संलग्न है। कराये जाने वाले कार्य के दर वर्तमान चालू अनुसूचित दर पर
आधारित है। यह प्राक्कलन विभागीय पत्रांक-4555, पटना, दिनांक-05.11.2021 एवं
विभागीय पत्र संख्या-4589, दिनांक-13.11.2021 से प्राप्त निदेशानुसार तैयार किया गया
है। यह पथ MIS के 86 क्रमांक पर अंकित है।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, महनार।

91.05
12.40
37
82
08

FLOOD DAMAGED REPORT

GENERAL ABSTRACT OF COST

Block:-- **Mahnar** District:- **Valshall**
 Length of Road:-- **2.050 KM**
 Name of Road:-- **Baghnocha - Hasanpur Chandel tola**

SL. No.	Item of Work	Amount
A	TOTAL COST OF RECTIFICATION/ RESTORATION :	27525.07 0.426 Lacs
		25936.69
	TOTAL :	0.426 Lacs

ADD Singgetee —

1 turn pipe - 502 = 61
 BSO 101.87 / for cuny Brck bal - 751.80
 ADD EST 12%
 L. cer 1%
~~28779.46~~ 27191.05
~~3452.52~~ 312.40
~~28707.9~~ 259.37
~~32521.7~~
30,562.82

[Signature]
 06/9/21
 Junior Engineer

[Signature]
 7/9/21
 Asstt. Engineer

[Signature]
 9/9/21
 Executive Engineer

Say B ~~0.33 lacs~~
0.31 lacs

As per S.E. RWD (M) Circle Muz
 Letter No. 1173 Dated 01.10.2021
 Estimate ~~1173~~ verified by Inspecting
 E. E. RWD. (M) Division

SE
 RWD

Technically Sanctioned for Rs. 0.31 lacs (Rs. ~~Thousand~~
 one thousand) only

[Signature]
 18.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

Sl.No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	11.10	300	Excavation for Structures								
			Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material								
			Qty taken from MB No 850	Cum					9.24	300.02	2772.18
2	8.1.3.2	OLD SOR	BRICK BATS							411.54	3802.63
	(iii)		Providing brick bats including spreading laying hand packing and compacting with C.I.Hammer in layers not exceeding 75mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks.								
			Qty taken from MB No 850	Cum						1809.49	13354.03
3	9.30	1100	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row			(2.14+1.125)			7.38	2161.18	15949.51
			Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.								
			Qty taken from MB No 850	Mtr						1433.61	7168.05
4	11.20	300 & 1200	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9						5.00	3937.00	19685.00
			Sand filling								
			Qty taken from MB No 850	Cum					5.40	489.33	2642.38
										592.66	3200.36
			TOTAL COST OF INITIAL RECTIFICATION / RESTORATION WORK								42,637.50

27525.07
25936.64

26/9/24
EE
RWD

26/9/24
AE
RWD

26/9/24
JE
RWD