



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-	Chochahi PWD Road to Chochahi Road		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur West		
BLOCK	Paroo		
TOTAL LENGTH OF ROAD	:	2.340	KM
CONSTRUCTION COST	:	7.698 8.02	Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur West

7.691

प्रतिवेदन

कार्य का नाम:- chochahi P.W.P Road to chochahi

..... पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- पारा
वित्तीय वर्ष - 2021-22
प्राक्कलित राशि - Rs. 7.698 (लाख)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 7.698 (लाख) है, chochahi P.W.D
Road to chochahi, प्रखण्ड- पारा में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4589 दिनांक 13.11.2021 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है। पथ की प्रकृति मृत्त है। प्रति मलजल है।

15/11/21
कनीय अभियंता

15/11/2021
सहायक अभियंता

16/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Inspection Report for Flood Damage Work

Date: 02.12.2021

1 Name of PIUs :- E.E. R.W.D, Mauza Adapur West.

2 Name of Block/Road :- Paroo/chochahi P.W.D Road to chochahi

(A) For Road:

1. Damage Location/Chainage :- 25077.

2. Damage Length :- 54 M.

3. Nature of Damage :- Road Cully by flood & heavy rain

4. Details of Restoration Works :-

(i) Material being used in Restoration works:- Bricks Ball - 366-5217, Sand - 22-95 M³

(ii) Equipment's/Tools being used in Restoration works:- Road roller

(iii) Procedure taken up in Restoration works:-

(iv) Restored Length :- 54 M.

The work found satisfactory

(B) For Bridge:

1. Damage Location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works :-

(i) Material being used in Restoration works:-

(ii) Equipment's/Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:-

(iv) Restored Length :-

N.A.

Signature of JE/AE/EE
02.12.21

Signature
02.12.21

(Name of Inspection)

GENERAL ABSTRACT

Name of Road Chochahi PWD Road to Chochahi Road
 District Muzaffarpur
 Block Paroo
 Division Muzaffarpur West
 Length of Road (in Km) 2.340 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	7.561
3	Sand Filling	0.130
4	Sand bag	0.000
5	H.P.	0.000
	SUB TOTAL	7.691
	GRAND SUB TOTAL	7.691

7.691 Lakhs

JE
 RWD

AE
 RWD

EE
 RWD

As Per S.E. RWD (W) Circle Muz.
 Letter No 1179 Dated 01/10/2021
 Estimate has been verified by Inspecting
 E.E. RWD. (W) Division

Technically sanctioned for Rs. 7.691 lakhs
 (Rs. Seven lakhs Sixty nine thousand one
 hundred) only (provisionally)

Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

27/12/21