



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L047-T05 TO MADHOPUR (VR47)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1900		
DISTRICT	KATIHAR		
BLOCK	BALRAMPUR		
DIVISION	BARSOI		
TOTAL LENGTH OF ROAD	1.900		KM
TOTAL COST OF F.D.R. PART - A	Rs. 12.052		Lacs
ADD G.S.T @ 12%	Rs. 1.446		Lacs
ADD Labour Cess @ 1%	Rs. 0.121		Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.630		Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 14.249		Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल ०१(२)ई अन्तर्गत बलरामपुर प्रखंड के पथ 2022-105 to MADHOPUR (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 20.11.21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का गइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

28/11/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,

28/11/21

28/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,

Inspection Report for Flood damage work

Date:

1. Name of PIUs- E.E. RWD Barsoi

2. Name of Block/Road- LO47- TOS to MADHOPUR (VR47)
Block- Balrampur

A. For Road

1. Damage Location/Chainage : CH 0.00 km to 1.300 km

2. Damage Length : 254.9 m

3. Nature of Damage : Shoulder

4. Details of Restoration :

i Material being used in Restoration

: Bamboo pile, local cement, Sand, Bags, Brick bats etc

ii Equipment/Tools being used in Restoration works:

: JCB, tractor, C.I. hammer etc

iii Procedure taken up in Restoration works

iv Restored Length

: 254.90 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AS/

Signature
08/01/22
AE
E.E.
RWD Barsoi
Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L047-T05 TO MADHOPUR (VR47)
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BALRAMPUR
LENGTH OF ROAD (IN KM) 1.900

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	11.565
4	SAND BAGS	0.000
5	BAMBOO WORK	0.487
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		12.052
Add G.S.T. @ 12%		1.446
Add Labour Cess @ 1%		0.121
Add Seigniorage Fee @ 10%		0.630
Total Cost of Restoration Work =		14.249

U.S. Kumar
J.E.
RWD
10/11/22

Q. S. Kumar
A.E.
RWD
28/11/24

W. S. Kumar
E.E.
RWD
28/11/24

Provisional Technical sanction of Rs 14.249 Lac
(Rupees Fourteen Lac twenty Four Hundred Nine -
Hundred) only

W. S. Kumar
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णिया