



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MOHADDIPUR MAHADALIT TOLA TO SONA TOLA BARSOI SIMA TAK
VIA SHERSAHBADI TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2575	
DISTRICT	KATIHAR	
BLOCK	BALRAMPUR	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	2.575	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.451	Lacs
ADD G.S.T @ 12%	Rs. 0.894	Lacs
ADD Labour Cess @ 1%	Rs. 0.075	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.406	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.826	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारा अन्तर्गत मोहदपुर प्रखंड के पथ MOHADDIPUR MAHADAI TOLA TO SONA TOLA BARSETHI (.....) जो VIA SHERSARHADI TOLA विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक ...02/11/2021... का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,
28/11/2021

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, ...01.11.21

Inspection Report for Flood damage work

Date:

1. Name of PIUs- *EE. RWD. Barsoi*

2. Name of Block/Road- *Mohaddipur Mahadalit tola to Sena tola Barsoi*
(Blaen- Balsampur) *Sima tak via Shersabadi tola*

A. For Road

1. Damage Location/Chainage : *2.00 km to 2.200 km*

2. Damage Length : *34.30 m*

3. Nature of Damage

4. Details of Restoration : *Shoulder & crest (full)*

i Material being used in Restoration

: *Brick bats, local sand, Empty cement bags, bombs etc*

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: *JCB, tractor, c-1 labour etc*

iv Restored Length

: *34.30 m*

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

C. Kumar
Signature of JEAE/EE

08/01/22
AE
Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MOHADDIPUR MAHADALIT TOLA TO SONA TOLA BARSOI SIMA TAK VIA
SHERSAHBADI TOLA

DISTRICT KATIHAR

DIVISION BARSOI

BLOCK BALRAMPUR

LENGTH OF ROAD (IN KM) 2.575

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	7.451
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.451
Add G.S.T. @ 12%		0.894
Add Labour Cess @ 1%		0.075
Add Seigniorage Fee @ 10%		0.406
Total Cost of Restoration Work =		8.826

45
J.E. 10/11/21
RWD

28/11/21
A.E.
RWD

28/11/21
E.E.
RWD

Provisional Technical Sanction of Rs 8.826 Lac
(Rupees eight lac eighty two thousand six -
hundred) only

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णियाँ