

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- L014-PMGSY Road Babu Narha House of Kishori Mallik
to Garhiya Bridge
Block:-Bajpatti.

F.D.R

Rs.759504.00 450078²⁰


Year-2021-22.

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई० विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	22-12-2021
3	पथ का नाम (शीर्ष के साथ)	L014-PMGSY Road Babu Narha House of Kishori Malik to Garhwa Bridge
4	पथ की लम्बाई	0.35 KM
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	बाजपट्टी।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	330m
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 176.2152 cum Qty of Rubbish:- 44.0538 cum Total Qty :- 220.2690 cum Entered in MB No:- 2701 Page No:- 01 to 03.
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	संतोष प्रद


 22-12-2021
 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-L014-PMGSY Road Babu Narha House of Kishori Mallik to Garhiya Bridge.

Length of Approach:- 0.350 Km

Block:-Bajpatti.


District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	653559.00
2	Labour cess @1%	6535.59
3	GST @12%	78427.08
4	Seigniorage Fee @ 10%	20982.82
5	Total Cost of Road Repair	759504.49


Say Rs.

759504.00

450078.20


5-11-21

JE


5-11-21

AE


5-11-21

अभिियन्ता-प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849

दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक


स्वीकृति के प्रत्याशा में औपबंधित तकनीकी स्वीकृति प्रदान

की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त

पुनः तकनीकी स्वीकृति प्रदान की जायेगी। औपबंधित तकनीकी

स्वीकृति रुपये...45.0078.20 (Four lakh fifty thousand seventy eight/100)

की प्रदान की जाती है।


22/4/22

अधीक्षण अभियन्ता

ग्रामीण कार्य विभाग

कार्य अंचल, सीतामढ़ी

Schedule of Quantity

Name of Road:-L014-PMGSY Road Babu Narha House of Kishori Mallik to Garhiya Bridge.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	85.39	Cum	488.11	41679.71
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	220.2690			0.00
	Less 20% for Voids	44.0538			
		176.2152	Cum	2105.01	370934.7582
3	Single bamboo palasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	600.00	m	1739.25 140.4 124	305415 84240.00 74400
4	Providing, Laying and placing empty cement bag filled with local sand including stitching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	9165.00	no.	9.63 3.50	88258.95 32077
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	0.00	m	3400.00	0.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	0.00	m	850.00	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and diredtion of E/I.			873.01	38456
	Taking 20% of Brick Qty for Rabbish	44.0538	Cum	1553.68	68445.50798

Total 653558.93

Say 653559.00

Rs 4 50 078 20

[Signature]
5-11-21

JE

[Signature]
5-11-21

AE

[Signature]
5-11-21

Details of Measurement of ditches filled by brick bats and rabbish

Name of Road:-L014-PMGSY Road Babu Narha House of Kishori Mallik to Garhiya Bridge.

	Nos.	L	W		H	VOLUME
Toward Narha Apporach	1	90.00	1.030	Av	0.580	53.7660
	1	90.00	1.000		0.580	52.2000
Toward Garhiya	1	70.00	1.630	Av	0.580	66.1780
	1	70.00	1.250		0.550	48.1250
		Total (in Cum)				220.2690
Laying Hume Pipe of 1000 mm dia		0	0		0	0.00
Laying Hume Pipe of 600 mm dia	2	2.5	0		0	5.00
Cement Bage						
Local Sand with cement Bag calculation	1	70	1.25		0.55	48.125
	1	70	1.63		0.95	108.395
	1	90	1.00		0.55	49.5
	1	90	1.03		0.58	53.766
				Total		259.786
No of Bags				259.786*35.28/1		9165 No

[Signature]
5-11-24

JE

[Signature]
5-11-24

AE

[Signature]
5-11-24