

**RURAL WORKS DEPARTMENT
GOVT OF BIHAR**



Name Of Work : Bya Mod -Bya Urf Nonahi

BLOCK

Parihar

FDR

Rs. 131599.00

Year - 2021-22

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI


NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

पथ का नाम:- B7a mod to B7a urb Mahuli

प्रस्तुत प्राक्कलन कार्य प्रमंडल, सीतामढ़ी अंतर्गत परिहार प्रखंड में 2021 के जुलाई माह में आई भीषण बाढ़ से क्षतिग्रस्त पथ में मरम्मत मद से यातायात चालू करने हेतु योजना शीर्ष FDR के अंतर्गत तैयार किया गया है। जिसकी प्राक्कलित राशि Rs. 131599.00 है। पथ के क्षतिग्रस्त भाग में आवश्यकतानुसार Brick Bats, Rabbish/ Local Sand भरकर यातायात चालू करने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन में पथ के अंतर्गत सूचित प्रावधानों एवं वर्तमान अनुसूचित दर के अनुसार कार्यहित एवं स्थलीय आवश्यकता के अनुरूप तैयार किया गया है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : Bya Mod -Bya Urf Nonahi
Length of Road : 1.500 KM
Block : Parihar
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in
	Total Cost for Motorable Roads	131599.00
	Total Cost of Road Repair	131599.00
	Say	131599.00

JE 12/11/22

AE 12/11/22

EE 12.01.22

अभियन्ता-प्रमुख ग्रामीण कार्य विभाग के फ़ांक-4849
दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक
स्वीकृति के प्रत्याशा में औपबंधित तकनीकी स्वीकृति प्रदान
की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त
पुनः तकनीकी स्वीकृति प्रदान की जायेगी। औपबंधित तकनीकी
स्वीकृति रुपये 1,31,599.00 (Rupees one lac
thirty one thousand five
hundred ninety nine only) की प्रदान की जाती है।

19/11/22
Superintending Engineer
Rural Works Department
Works Circle, Sitamarhi

Schedule of Quantity

Work : Bya Med -Bya Urf Nonahi

Block : Parihar


Sl. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	457.21	0.00
2	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	80.42			0.00
	Less 20% for Voids	-16.08			
		64.34	Cum	1827.25	117557.89
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	Each	140.40	0.00
4	Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	20.41	0.00
5	Providing and Laying 1000 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3740.68	0.00
6	Providing and Laying 600 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3091.44	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	16.08	Cum	873.01	14041.46

Total 131599.36

Say 131599.00


12/1/22
JE


12/01/22
AE


12.01.22
EE

Details of Measurement of ditches filled by brick bats and rubbish

Record ENTRY

L	W	H	VOLUME
7.80	2.50	0.30	5.85
5.70	3.40	0.25	4.85
7.00	2.70	0.25	4.73
4.50	3.00	0.30	4.05
15.00	$3.00+4.00+3.00/3$	0.25	12.50
14.00	3.00	0.25	10.50
10.00	4.00	0.30	12.00
13.00	3.20	0.30	12.48
5.50	3.00	0.30	4.95
11.00	$3.00+3.20/2$	0.25	8.52
Total (in Cum)			80.42

17/11/21
002

12/10/22
AE

12/10/22
EE