

(21)

RURAL WORKS DEPARTMENT
GOVT OF BIHAR



Name Of Work : Mujaulia Rajput Chowk -Dhanta

BLOCK

Parihar

FDR

Rs. 253101.00

Year - 2021-22

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

पथ का नाम:- Gajulata Road Chara and School

प्रस्तुत प्राक्कलन कार्य प्रमंडल सीतामढ़ी अंतर्गत परिहार प्रमंडल में 2501 की जमीन में सड़क चौड़ाई 10 मीटर से अधिक करने के लिए किया गया है। निम्नलिखित प्राक्कलन की लागत Rs. 2,53,101/- है। पथ को शीघ्रतः बनाने में आवश्यकता है।
Brick Bats, Rabbish Local Sand

प्रस्तुत प्राक्कलन में पथ के अंतर्गत सूचित प्राक्कलन एवं वर्तमान अनुमानित पथ की आवश्यकता कार्यहित एवं स्थलीय आवश्यकता के अनुरूप तैयार किया गया है।

12/1/22
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।

12/1/22
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।

12/1/22
कनिष्ठ अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।

General Features of Cork

[Signature]

[Signature]

~~2/23~~

(Handwritten notes in Hindi script, likely bleed-through from the reverse side of the page)

Superintending Engineer
Rural Works Department
Works Circle, Bitamathi


Schedule of Quantity


Work : Mujaulia Rajput Chowk - Dhanta

Block Parhar

Sl. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	ITEMS Sand Filling in Foundation Trenches as per Drawing & Technical Specification	215.96	Cum	457.21	98739.40
2	Providing and laying of Brick bat obtained from chimney with mechanical means with all spreading, grading to required slope and compacted at CMK to achieve required density with all complete as per the direction of engineer in charge	79.32			0.00
	Less 20% for Voids	-15.86			
		63.45	Cum	1827.25	115942.61
3	Single bamboo palaxiding walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1.3.2.5	175.00	Each	140.40	24570.00
4	Providing, laying and placing empty cement bag filled with local sand including stitching with sutali etc. ----- do ----- do ----- all complete job as per specification and direction of E/I. (Including Royalty and all Taxes)	0.00	no	20.41	0.00
5	Providing and Laying 1000 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3740.68	0.00
6	Providing and Laying 600 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3091.44	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	15.86	Cum	873.01	13848.53
				Total Say	253100.53
					253101.00


JE


12/10/22
AE


12-61-22
EE

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : Mujaulia Rajput Chowk - Dhanta

Record ENTRY	L	W	H	VOLUME
	15.00	$3.60+2.50+2.20/3$	0.20	8.30
	15.00	$3.00+2.50/2$	0.30	12.37
	15.00	$2.50+2.00/2$	0.25	8.44
	13.00	2.00	0.25	6.50
	11.00	$1.00+2.00/2$	0.20	3.30
	9.00	$1.50+1.50/2$	0.25	3.37
	15.00	$2.00+1.60/2$	0.50	13.50
	15.00	$2.50+1.80/2$	0.60	19.35
	9.30	1.50	0.30	4.19
Total (in Cum)				79.32

12/11/22
or

12/11/22
AE

12/01/22
EE