



ग्रामीण कार्य विभाग

RURAL WORKS DEPARTMENT, GOVT OF BIHAR

DETAILED PROJECT REPORT FOR FDR 2021-2022



Name of Road :-	RAM JANKI COHWK SITAKUND SE BEDIBAN MADHUBAN MALLAH TOLA		
DISTRICT	EAST CHAMPARAN		
DIVISION	CHAKIA		
BLOCK	CHAKIA		
TOTAL LENGTH OF ROAD	2.401	KM	
COST OF RECTIFICATION	0.92 0.05	LAC	


Inspection Report For Flood Damage Work

Date :-

1. Name of PIUs- Executive Engineer RWD, Chakia
2. Name of Block- Chakia
3. Name of Road- Ramjanki chowk sitekund se bedi ban madhuban
mallah tola.

(A) For Road

1. Damage Location/ Chainage:- 1100 - 1150 mtr
2. Damage Length:- 20 mtr
3. Nature Of Damage:- Breach & surface damage due to heavy rain.
4. Details Of Restoration works:-
 - (i) Material being used in restoration works:- Brick bat, local Sand,
 - (ii) equipments /Tools being used in Restoration works:- Tractor, JCB, Static Roller,
 - (iii) Procedure taken up in Restoration Works:- Departmental.
 - (iv) Restored length:- 20 mtr


Signature of Inspecting Officer
(Executive Engineer)
R.W.D. W.D. Raxaul

प्रतिवेदन

कार्य का नाम :- Ramjanki chowk Sitakund se Bedi ban madhuban
malah tola.....पथ में अप्रत्याशित बाढ़ / अतिवृष्टि 2021 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड :- चकिया


वित्तीय वर्ष : 2021-2022


प्रकलित राशि :-

प्रस्तुत प्राक्कलन, जिसकी प्रकलित राशि0.92..... है, प्रखण्ड चकिया में यातायात
बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4275 दिनांक 22/10/21 द्वारा
दिये गए निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त भाग में brick Bats & Local sand भरकर पथ को
चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा चकिया


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल चकिया


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल चकिया

GENERAL ABSTRACT OF COST FOR FDR

Name of road RAM JANKI COHWK SITAKUND SE BEDIBAN MADHUBAN
District EAST CHAMPARAN
Block CHAKIA
Division CHAKIA
length of road (in Km) 2.401

SL NO	DESCRIPTION	AMOUNT (LAKHS)
1	Excavation in soil using hydraulic excavator	-
2	Brick bats	84159.00 90,555.00
3	Sand filling	1104.00 1,679.00
4	Sand bags	
5	Bamboo piles	
Total		INR 92,234.00

Say 85,300/- 85,263.00

Swi
23/10/21

Junior Engineer
Rural Works Department
Work Section,
Chakia

Pm
23/10/21

Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

Swi
23/10/21

Executive Engineer
Rural Works Department
Works Division,
Chakia

Post facto T.A./TS is accorded for Rs. 85,300.00
.....crore.....lacs.....thousand
Eighty five
.....hundred.....) only.

S.E. (R.W.D.)
works Circle
Motihari

SL NO.	SBD SL NO.	MORD REF NO.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT (IN RS.)
1	3.5	302(iii)	Excavation in soil using Hydraulic Excavator excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting only and as per Technical Specification Clause 302.3				
			Appendix -I	cum	0	112.47	0
2			Brick Bats laying Brick Bats in ditches as per direction and specification with all complete job				
			Appendix -II	cum	43.95	2060.40	90555
			Sand Filling Filling in foundation trenches as per drawing and technical specification clause 305.3.9				
3			Appendix -III	cum	3.65	459.91	1679

1914.89 84159.00

302.50

1104.00


Name of Road :- COHWK SITAKUND SE BEDIBAN MADHUBAN MA


Block :- CHAKIA


Appendix - II

sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thickness (M)	Av. Thickness (M)	quantity (Cum)
1		1	6		4		1	24
2		1	7		3		0.95	19.95

Total 43.95


22/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia


23/11/21
Assistant Engineer
Rural Works Department
Work Sub Division
Chakia


23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia

Name of Road :- RAM JANKI COHWK SITAKUND SE BEDIBAN MADHUB/

Block :- CHAKIA

Appendix - II


sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thicknes s(M)	Av. Thicknes s (M)	quantity (Cum)
1		1	6		3.75		0.1	2.25
2		1	7		2		0.1	1.4
Total								3.65


23/10/21

Junior Engineer
Rural Works Department
Work Section,
Chakia


23/10/21

Assistant Engineer
Rural Works Department
Work Sub Division
Chakia


23/10/21

Executive Engineer
Rural Works Department
Works Division,
Chakia