



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD-FDR YEAR 2021

**DISTRICT :- WEST CHAMPARAN
BLOCK :- RAMNAGAR**

Scheme Head - New M/R (3054) (Under Maintenance)

**Estimate for Repair of Road breaches
(Damaged by Flood) for Motorability in
Gram Balua Bangla Tola To Dumri via
Sinahai**

**LENGTH OF ROAD (in Km)- 2.87 KM
DAMAGED LENGTH (in Km)- 0.192 KM**

ESTIMATED COST	35.379	Lacs
-----------------------	---------------	-------------

**SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BAGHAHA-1**

TECHNICAL REPORT

Name of Road :- Gram Balua Bangla Tola to Dumari via Singhai

Name of Block:- Ramnagar

Name of Division:- Bagaha-1

Name of District:- West Champaran

Estimated Cost:- Rs. 35.379 Lacs

This Estimate is prepared for Restoration Gram Balua Bangla Tola to Dumari via Singhai. under FDR as per the instruction of Secretary, Rural Works Department, Patna vide, 23 -60 /2020-1937 , Patna, Date- 07.07.2021. Road remains effected from flood about 01 to 02 weeks and heavy amount of water passed through it.

Honorable Chief Minister/Secretary, Rural Works Department, Bihar, Patna/D.M., West Champaran,

Bettiah/Concerned MP/MLA has instructed to maintain the traffic and movement of public etc. at the earliest so that public of this area may get connected and for the same Departmental instruction has also been issued to fill the gap made by flooded immediately.

The area surrounding is submerged in water and hence provision of Bricks Bats/ Earth Work/Sand Filling/ Bamboo Pilling/Hume Pipe has been made to maintain the road damage due to flood/heavy rainfall as per availability of material from available place by tractor. Presently there is no Contractor is employed for Construction and Maintenance of this road hence the work has been carried out Departmentally and due to this, provision of Contractor profit is not mentioned in the estimate.

In view of above, it is requested to approve the estimate amounting to Rs. 35.379 Lacs please.

Submitted for Administrative Approval please.

17-11-2021

Junior Engineer,
Ramnagar

[Signature]

17/11/21

Assistant Engineer,
Ramnagar

[Signature]
17/11/21

Executive Engineer
R.W.D.(W) Division, Bagaha-1

Scheme Head - New M/R (3054) (Under Maintenance)

GENERAL ABSTRACT OF COST

**ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR
MOTORIBILITY IN GRAM BALUA BANGLA TOLA TO DUMRI VIA SINGHAI**

DISTRICT - WEST CHAMPARAN

DIVISION - BAGAIHA-1

BLOCK - RAMNAGAR

LENGTH OF ROAD (in Km)- 2.87 KM

DAMAGED LENGTH (in Km)- 0.192 KM

Scheme Head - New M/R (3054) (Under Maintenance)

SL. No.	Item of Work	Amount
1	EARTH WORK :	0.743 Lacs
2	BRICK BATS :	25.556 Lacs
3	SAND BAGS :	0.000 Lacs
4	BAMBOOS PILING AND RUNNER :	0.000 Lacs
5	HUME PIPE :	2.940 Lacs
	COST OF RESTORATION :	29.238 Lacs
	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST :	2.339 Lacs
	ADD LABOUR CESS @ 1% :	0.292 Lacs
	ADD GST @ 12% :	3.509 Lacs
	TOTAL COST OF RESTORATION OF ROAD :	35.379 Lacs

[Signature]
17-11-2017
Junior Engineer

[Signature]
17/11/21
Asstt. Engineer

[Signature]
17/11/21
Executive Engineer


[Signature]
Technically ~~approved~~ ^{sanctioned} for Rs 3537900=00 (Thirty five
Lac thirty seven thousand nine hundred) only /-

[Signature]
25/11/21
S.E.
RWD (W) Circle
Bettiah


Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Gram Balua Bangla Tola To Dumri via Singhal

ad - FDR

Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
	EARTH WORK - Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m. transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	cum		As Per Appendix I			552.92	134.33	74273.744
	Providing and Labour for consolidation in Brick Bats by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller driver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .	cum		As Per Appendix II			1247.650	2048.30	2555561.50
	Providing and Labour for laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum		As per Mesurment Sheet			0.000	1790.14	0.00
	Providing, Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/I.	Nos.		As per Mesurment Sheet			0.000	19.67	0.00
	Providing and Labour for cutting 62 mm to 75 dia Bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I.	RM		As per Mesurment Sheet			0.000	47.61	0.00
	Providing and Labour for fitting & fixing 62 mm to 75 dia Bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails etc. complete job as per specification and direction of E/I.	RM		As per Mesurment Sheet			0.000	26.85	0.00
	Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		18 Nos*2.5m			45.000	6533.53	294008.85
	Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0.000	2724.34	0.00
TOTAL (In Re.)									2923844.09


17-11-2017
Junior Engineer,
Rural Works Department,
Works Section, RAMNAGAR


17/11/21
Assistant Engineer,
Rural Works Department,
Works Sub Division, RAMNAGA


17/11/21
Executive Engineer,
Rural Works Department,
Works Division, BAGAHA-1

SEIGNIORAGE FEE CALCULATION SHEET

Item description	unit	Quantity of Consuming Item	Materials Required/ Unit	Unit	Quantity/ Unit	Total Quantity Required	Rate	Amount	Seigniorage Fee (RS)	Final Amount (RS)
Earth Work	Cum	552.92	Earth	Cum	1.0	552.92	34.82	19252.67	1925.27	1925.27
Brick bats	Cum	1247.65	Brick bats	Cum	1.2	1497.18	1549.51	2319895.38	231989.54	231989.54
Sand Bags	per bag	0.00	sand	Cum	0.034	0.00	286.55	0.00	0.00	0.00
1000 MM Dia	RM	45.00	Sand at site	Cum	0.04	1.80	0.00	0.00	0.00	0.00
600 MM Dia	RM	0.00	Sand at site	Cum	0.0032	0.00	0.00	0.00	0.00	0.00
Total Amount of seigniorage fee in construction (Rs)										233914.81

Subscribed
17/11/21
JG.

By 17/11/21
AZ

Per 17/11/21

अधीक्षण अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया

पत्रांक-1325 / बेतिया, दिनांक-14/11/2021 /

प्रेषक:-

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

सेवा में,

कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बेतिया / नरकटियागंज / बगहा-1 / बगहा-2

विषय:-

वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

प्रसंग:-

वाट्स ऐप के माध्यम से प्राप्त विभागीय निदेश के आलोक में।

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि वर्ष 2021 में बाढ़ में क्षतिग्रस्त पथों को मोटरबुल कराने हेतु किये गये कार्यों की जाँच हेतु वाट्स ऐप के माध्यम से विभागीय निदेश प्राप्त हुआ है। जिसमें कार्यपालक अभियन्ता एवम् उनके अधीनस्थ पदाधिकारियों के माध्यम आवंटित प्रमंडल का जाँच करना है।

अतः विभागीय आदेश के आलोक में क्षतिग्रस्त पथों के जाँच हेतु अधोहस्ताक्षरी के द्वारा जाँच दल का गठन किया जा रहा है तथा जाँच दल दिनांक-22.11.2021 तक जाँच प्रतिवेदन अधोहस्ताक्षरी के समक्ष प्रस्तुत करेंगे। अन्यथा इसकी सारी जवाबदेही जाँचदल की होगी।

—:जाँच दल तथा उनके जाँच करने का स्थल निम्नलिखित है:-

क्रमांक	जाँच दल	जाँच स्थल	प्रतिवेदन जमा करने की अंतिम तिथि
1	कार्यपालक अभियन्ता, सहायक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बेतिया।	ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-1 एवम् नरकटियागंज का जाँच कर जाँच प्रतिवेदन समर्पित करेंगे।	22.11.2021
2	कार्यपालक अभियन्ता, सहायक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-1।	ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2 का जाँच कर जाँच प्रतिवेदन समर्पित करेंगे।	22.11.2021
3	कार्यपालक अभियन्ता, सहायक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2।	ग्रामीण कार्य विभाग, कार्य प्रमंडल, बेतिया का जाँच कर जाँच प्रतिवेदन समर्पित करेंगे।	22.11.2021

विश्वासभाजन

अधीक्षण अभियन्ता

ग्रा0का0वि0, का0अ0, बेतिया।

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बेतिया

पत्रांक-..... / बेतिया, दिनांक..... /

प्रेषक:-

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बेतिया।

सेवा में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

विषय :-

कार्य प्रमंडल, बगहा-1 में वर्ष 2021 के बाद में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

प्रसंग:-

भवदीय पत्रांक-1325/बेतिया, दिनांक-14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0) विविध (कार्य)-23-291 /2019-4589, दिनांक-13.11.2021।

महाशय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बगहा-1 द्वारा उपलब्ध कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अचोहस्ताक्षरी द्वारा सहायक अभियन्ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बगहा-1 द्वारा प्रतिवेदित सभी पथों पर कार्य कराया गया है एवम् यातायात चालू है। (क्याम गमना मोटरेबुल कार्य प्रमंडल द्वारा है।)
सादर सूचनार्थ एवम् अग्रत्तर कार्रवाई हेतु समर्पित।

अनु0- निरीक्षण किये गये पथों की सूची।

विश्वासभाजन,

Sol

कार्यपालक अभियन्ता
ग्रा0का0वि0, का0प्र0, बेतिया।

ज्ञापांक- 3246(अनु0) / बेतिया, दिनांक- 25/11/2021 /

प्रतिलिपि:- कार्यपालक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-1 को सूचनार्थ सम्प्रेषित।

25.11.21

कार्यपालक अभियन्ता
ग्रा0का0वि0, का0प्र0, बेतिया।

Division	Road/Bridge Name	Status	Length (In KM)	Damage Part Length During Flood	Estimated Cost (In Lakh)	Remarks
Bagaha-I	PMGSY Lauriya-Tirhut Canal Road To Nandangarh	Under Agreement				
Bagaha-I	PWD Sathi To Sugarchhap	Under Agreement	2.100	0.225	11.218	Motorable & Traffic Restored.
Bagaha-I	PWD Ramnagar To Parsauna Dich	Under Agreement	3.470	0.200	5.237	Motorable & Traffic Restored.
Bagaha-I	PWD Chanpatia To Baulh Tola	Under Agreement	3.400	0.140	1.368	Motorable & Traffic Restored.
Bagaha-I	PMGSY Kataiya to Sohadarapur	Under Agreement	2.930	0.170	4.668	Motorable & Traffic Restored.
Bagaha-I	Gulab Sekhnagar road to Dharampur	Out of Agreement	2.000	0.270	6.944	Motorable & Traffic Restored.
Bagaha-I	PMGSY Daniyal Parsauna to Parsauna Harijan Tola	Out of Agreement	1.000	0.194	9.620	Motorable & Traffic Restored.
Bagaha-I	Construction of I.L. R.C.C Bridge at Sheikh Toli in Between Narkatiaganj Assembly Constituency And Lauriya Assembly Constituency in Bagaha RWD Road To Dumra In West Champaran	Under Agreement	1.500	0.135	3.874	Motorable & Traffic Restored.
Bagaha-I	JHARAWA - KANGUSERI	Out of Agreement	58.000	0.100	6.384	Motorable & Traffic Restored.
Bagaha-I	L035 - Done Canal Khatauri to Pakri Semra (VR68)	Out of Agreement	15.000	0.100	5.975	Motorable & Traffic Restored.
Bagaha-I	L040 - Simrauni to Betahni (VR20)	Out of Agreement	7.000	0.100	6.465	Motorable & Traffic Restored.
Bagaha-I	PWD Road Hardia - Sherwa	Under Agreement	12.000	0.185	53.895	Motorable & Traffic Restored.
Bagaha-I	T 07 - Bankatwa	Out of Agreement	8.000	0.220	31.878	Motorable & Traffic Restored.
Bagaha-I	L042-PWD Road to Gobardhana (VR22)	Out of Agreement	7.000	0.390	13.125	Motorable & Traffic Restored.
Bagaha-I	L057-PMGSY Done Canal to Phagunahta (VR98)	Out of Agreement	1.300	0.040	5.235	Motorable & Traffic Restored.
Bagaha-I	L062-PMGSY Baluahwa mor to Hariharpur (VR97)	Out of Agreement	5.048	0.340	14.116	Motorable & Traffic Restored.
Bagaha-I	L065-Dhanrappa bhawal Banwari Road (VR46)	Out of Agreement	1.616	0.100	1.137	Motorable & Traffic Restored.
Bagaha-I	L069-Phulwariya tola to Purab Kuriya devi Asthan tak Sarak nirman (VR50)	Out of Agreement	2.900	0.199	1.163	Motorable & Traffic Restored.
Bagaha-I	Gram Balua Bangla Tola to Dumari via Singhai	Under Agreement	1.913	0.150	5.370	Motorable & Traffic Restored.
Bagaha-I	Dhanrappa Bhawal to Banwari	Under Agreement	2.870	0.198	35.379	Motorable & Traffic Restored.
Bagaha-I	Khataura - KUMHIYA	Out of Agreement	13.000	0.441	23.582	Motorable & Traffic Restored.
Bagaha-I	PWD ROAD - SEMRA	Out of Agreement	6.411	0.042	3.29	Motorable & Traffic Restored.
Bagaha-I	PWD ROAD CANAL - BALOORA	Under Agreement	3.825	0.304	12.056	Motorable & Traffic Restored.
Bagaha-I	PWD ROAD RAMNAGAR - BANKATWA	Under Agreement	20.357	0.065	2.338	Motorable & Traffic Restored.
Bagaha-I	L061-PMGSY Bhakhari Ghora ghat to Baijiya (VR42)	Under Agreement	6.108	0.044	10.507	Motorable & Traffic Restored.
Bagaha-I	Gardi to Banhawa tola Gardi	Under Agreement	1.500	0.050	0.668	Motorable & Traffic Restored.
Bagaha-I		Under Agreement	2.100	0.200	4.373	Motorable & Traffic Restored.


घोषणा-पत्र

1. इस प्राक्कलन को असंबद्ध कार्यपालक अभियन्ता से जाँच करा ली गयी है।
2. अस्थायी पुनर्स्थापन के सामग्री का समायोजन स्थायी पुनर्स्थापन के प्राक्कलन में कर ली गयी है।



25/11/2021

सहायक अभियन्ता / कर्मचारी अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बगहा-1



25/11/2021

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बगहा-1