

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Benipur

Name of Block/Road:- Alwagan / Baghola chokke to Nandu chandhy
road

A. For Road

1. Damage Location Chainage:- Ch 200m, 250m

2. Damage Length :- 20.70m

3. Nature of Damage :- road work

4. Details of Restoration Works

i. Material being used in Restoration works:- brick bats

ii. Equipment's /Tools being used in Restoration works:- JCB & tractor

iii. Procedure taken up in Restoration works:- filling & levelling

iv. Restored Length:- 20.70m

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:- "work found satisfactory"

N/A

Signature of JE/AE/EE

Signature
(Name of Inspection)

FDR 2021-22

पथ का नाम :- लखीला चौक से गन्धु चौधरी हाउस

पथ की लम्बाई :- 1.500 कि० मी०

प्राक्कलित राशि :- 26,697.00


प्रतिवेदन

माह मई के अंतिम सप्ताह से लेकर माह अक्टूबर के तीसरे सप्ताह तक लगातार भारी वर्षा, परिणामस्वरूप आयी बाढ़ के चलते अधिकांश पथ अंशतः अथवा पूर्णतः जलमग्न हो गये, पथ में कटाव हो गया एवं यातायात बाधित हो गया।

जनहित, कार्यहित एवं आसन्न पंचायत आम चुनाव एवं विभागीय सचिव महोदय के आदेश (पत्रांक- मु0अ0-4(मू0) विविध कार्य-23-60/2020-1937 पटना, दिनांक-07.07.2021) के आलोक में क्षतिग्रस्त पथों को ईट टुकड़ों से भरकर यातायात बहाल किया गया।

जलस्तर कम होने एवं पानी का बहाव बन्द होने के पश्चात् आदेशानुसार किये गये कार्य के अनुसार प्राक्कलन तैयार कर घटनोत्तर स्वीकृति हेतु समर्पित की जा रही है। कार्यहित में प्राक्कलन की स्वीकृति अपेक्षित है।

प्राक्कलन को कार्य अंचल, दरभंगा द्वारा स्वीकृत अद्यतन दर के आधार पर तैयार कर अग्रेतर कार्रवाई हेतु समर्पित की जाती है।


१६.१०.२०२१

कनीय अभियंता
ग्रा०का०वि०, कार्य प्रशाखा,
अलीनगर


२४/१०/२०२१

सहायक अभियंता
ग्रा०का०वि० कार्य अवर प्रमंडल,
अलीनगर


१६/१०/२१

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेनीपुर

Name of work - Restoration of traffic in Baghaila chowk to Nandu chandhary house

Item no. (01) Providing and filling brick bats including cart of brick, loading, unloading & light ramming, all complete job.

$$\text{Ch. 200m } 1 \times 6.00 \times 2.90 \times \frac{0.075 + 0.20 + 0.075}{3} = 2.03 \text{ m}^3$$

$$\text{Ch. 250m } 1 \times 6.00 \times 2.30 \times \frac{0.150 + 0.300 + 0.150}{3} = 2.76 \text{ m}^3$$

$$1 \times 5.00 \times \frac{2.00 + 2.40 + 2.45}{3} \times \frac{0.20 + 0.60 + 0.30}{3} = 4.19 \text{ m}^3$$

$$1 \times \frac{4.30 + 3.10}{2} \times 3.10 \times \frac{0.150 + 0.30 + 0.150}{3} = 2.29 \text{ m}^3$$

$$\text{total Qty} = 11.27 \text{ m}^3$$

$$@ 2004.96/\text{m}^3 = 22596.00$$

$$\text{Add. 12\% GST} = 2712.00$$

$$\text{Add 1\% L.C} = 226.00$$

Add S.F @ 10%.

$$11.27 \times 1032.00 \times 0.10 = 1163.00$$

$$\text{total} = 26,697.00$$

Temporarily sanctioned for 26,697.00 (Rupees Twenty Six thousand Six hundred Ninety seven) only

24.10.2021

JCB

Aswagar

24/10/2021

AB

Aswagar

24/10/2021

AB

Baidya

Checked and Verified

14.12.2021
AE

325
14/12/21
CC

P.T.O

P.T.O