

RURAL WORKS DEPARTMENT

GOVT. OF BIHAR



Name of Work:- PMGSY Sondahi to Sondahi tola..
Block:-Sursand.

F.D.R

Rs. ~~1179253.00~~ 816652.00

793088

Year-2021-22.

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

General Abstract of Cost

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	1002995.00
2	Labour cess @1%	10029.95
3	GST @12%	120359.40
4	Seigniorage Fee @ 10%	45868.92
5	Total Cost of Road Repair	1179253.27

793088

JE

AE

5.11.97

793088 (Seven Lac Ninety Three Eighty Eight) only.

22/4/22
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, सीतामढ़ी

Schedule of Quantity

Name of Road:-PMGSY Sondahi to Sondahi tola.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	481.5129			0.00
	Less 20% for Voids	96.30258			
		385.2103	Cum	2105.01	810871.576
3	Single bamboo paia siding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stitching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	10.00	m	3400.00 3300	34000.00 33000.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	10.00	m	835 850.00 3091.44	8350 8500.00 30914.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and diretion of E/I.			873.01	84073
	Taking 20% of Brick Qty for Rabbish	96.30258	Cum	1553.68	149623.392

Total 1002994.97

Say 1002995.00

816652.00
793088.00

[Signature]
05/11/21
JE

[Signature]
5-11-21
AE

[Signature]
5/11/21
EE

Details of Measurement of ditches filled by brick bats and rabbish

Name of Road:-PMGSY Sondahi to Sondahi tola.

	Nos.	L	W		H		VOLUME
CH at 0.050 Km	1	4.20	3.000		0.800		10.0800
Ch at 0.200 km	1	12.00	3.750	Av	1.200		54.0000
	1	21.00	4.366	Av	1.400		128.3604
	1	14.50	3.100	Av	1.200	Av	53.9400
	1	8.40	3.000		0.900		22.6800
	1	21.00	3.400		0.600		42.8400
	1	30.00	3.500		0.800		84.0000
	1	20.00	3.100	Av	0.400		24.8000
	1	5.00	2.500		0.500		6.2500
	1	5.00	3.250	Av	0.450		7.3125
	1	15.00	3.000		0.600		27.0000
	1	15.00	3.000		0.450		20.2500
		Total (in Cum)					481.5129
Laying Hume Pipe of 1000 mm dia	4	2.5	0		0		10.00
Laying Hume Pipe of 600 mm dia	4	2.5	0		0		10.00
Cement Bage							


Sondahi
05/11/21
JE

PKP
5.11.21
AE

EE
5.11.21

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	20-12-2021
3	पथ का नाम (शीर्ष के साथ)	पन्ना से सीतामढ़ी से सीतामढ़ी रोड
4	पथ की लम्बाई	2.4 Km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	सुरसंड।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	250 मीटर
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 385.21 m³ Qty of Rubbish:- 36.3 m³ Total Qty :- 421.51 m³ Entered in MB No:- 2602 Page No:- 01 to 05.
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	21/12/21


 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित