

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



**Name of Work:- PMGSY Karwanna to Karwanna Tola.
Block:-Sursand.**

F.D.R

Rs.741477.00 20 492742 20

Year-2021-22.

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-PMGSY Karwanna to Karwanna Tola.

Length of Road:-2.2 Km

Block:-Pupri

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	629568.00
2	Labour cess @1%	6295.68
3	GST @12%	75548.16
4	Seigniorage Fee @ 10%	30065.35
5	Total Cost of Road Repair	741477.19

Say Rs. ~~741477.00~~
492742.20

Shandey
05/11/21
JE

Shandey
5.11.21
AE

Shandey
5.11.21
PE

अभियन्ता-प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849
दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक
स्वीकृति के प्रत्याशा में औपबंधित तकनीकी स्वीकृति प्रदान
की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त
पुनः तकनीकी स्वीकृति प्रदान की जायेगी। औपबंधित तकनीकी
स्वीकृति रुपये...4,92,742.20...
की प्रदान की जाती है।

Four hundred Ninety Two thousand Seven hundred forty Two only.

Shandey
22/4/22

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य विभाग, सिकंदरगढ़

Schedule of Quantity

Name of Road:-PMGSY Karwanna to Karwanna Tola.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	315.6137			0.00
	Less 20% for Voids	63.122733			
		252.4909	Cum	2105.01	531495.9368
3	Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	0.00	m	3400.00	0.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	0.00	m	850.00	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	63.122733	Cum	1553.68	98072.52781

Total 629568.46

Say ~~629568.00~~

492742.00

[Signature]
JE 05/11/21

[Signature]
AE 5.11.21

[Signature]
EE 5.11.21

Details of Measurement of ditches filled by brick bats and rabbish

Name of Road:-PMGSY Karwanna to Karwanna Tola.

	Nos.	L	W		H		VOLUME
CH 0.00 Km	1	30.00	5.200	Av	0.500		78.0000
	1	30.00	5.400	Av	0.900		145.8000
	1	10.50	4.633	Av	0.900		43.7819
CH 1.50 Km	1	20.00	3.950	Av	0.900		71.1000
	1	5.00	3.000	Av	0.800		12.0000
		Total (in Cum)					350.6819
		Less @ 10% Old Salvage Material					35.0682
		Net Qty (in Cum)					315.6137
Laying Hume Pipe of 1000 mm dia							
Laying Hume Pipe of 600 mm dia	0	0			0		0.00
Cement Bage							


Bhander
05/11/21
JE

GRK
5-11-21
AE

EE
5-11-21

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	20-12-2021
3	पथ का नाम (शीर्ष के साथ)	PMGSY Karwanna to Karwanna Tola
4	पथ की लम्बाई	2.2km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	सुरसंड।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	95.5m
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 252.4909com Qty of Rubbish:- 63.1222733com Total Qty :- 315.6137com Entered in MB No:- 2607 Page No:- 3
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	20-12-2021


 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित