

नीण कार्य विभाग

al Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2021-22

ISTRICT: WEST CHAMPARAN

BLOCK:- Lauriya

(D of Flood) for Motoribility in PWD

and To Satwariya South

NoTH OF ROAD (in Km)- $0.62~\mathrm{KM}$

ESTAVA COST - 1.705 Lacs

SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BAGAHA-1

ग्रामीण कार्य विमाग बिहार, सरकार

पत्रांक — मु0अ0—4 (मु0) विविध कार्य—23—60/2020 — 1937 पटना, दिनांक ०७/०७/2021 प्रेषक,

> पंकज कुमार पाल (भा०प्र०२१०) सचिव

सेवा में,

सभी कार्यपालक अभियंता ग्रामीण कार्य विभाग,

विषय— बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों / पुलियों को यातयात लायक (Motorable) करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़ / अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों / पुलियों के क्षतिग्रस्त भाग से पानी उत्तरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

(पंकर्ज कुमार पाल)

वेश्वासभाज

(पपाण पुनार पाल)

ज्ञापांक – मु0अ0–4 (मु0) विविध कार्य – 23–60 / 2020 - 1937 पटना, दिनांक ०७ / ७/२०२१ प्रतिलिपिः – सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अितशीघ्र यातायात लायक बनवाने की कारवाई सुनिश्चित करेंगे।

सिचिव

ज्ञापांक—मु0अ0—4 (मु0) विविध कार्य—23—60/2020 - 1937 पटना, दिनांक ज्य/त/2021 प्रतिलिपि:—सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।

संचिव

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बेतिया

पत्रकि-----

🖊 बेतिमा विशोक/

प्रेषक:--

कार्यपालक अभियन्ता यामीण कार्य विभाग कार्य प्रमंडल, बेतिया।

रोवा में

अधीक्षण अभियन्ता. ग्रामीण कार्य विभाग कार्य अंचल, बेतिया।

विषय:-

कार्य प्रमंडल, बगहा--1 में वर्ष 2021 के बाद में क्षतिग्रस्त पर्धों को मोटरेबुल कराने हेतु किये गये कार्यों की जॉच के संबंध में।

प्रसंग:-

भवदीय पत्रांक—1325 / बेतिया, दिनांक—14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु०अ०-4(मु०) विविध (कार्य)-23-231 / 2019-4589, दिनांक-13.11.2021।

महाशय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बगहा-1 द्वारा उपलब्ध कराये गर्ये मोटरेबुल पथों की सूची में अंकित पथों का अधाहस्ताक्षरी द्वारा सहायक अभियन्ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बगहा-1 द्वारा प्रतिवेदित सभी पथों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।

अनु0- निरीक्षण किये गये पथों की सूची।

विश्वासभाजन,

कार्यपालक अभियन्ता ग्रा०का०वि०, का०प्र०, बेतिया।

ज्ञापांक- 3246(अर्रे) / बेतिया, दिनांक- 25 11 22 /

कार्यपालक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-1 को सूचनार्थ प्रतिलिपि:-सम्प्रेषित।

> कार्यपालक अभियन्ता ग्रा०का०वि०, का०प्र०, बेतिया।

Division	Road/Bridge Name	Status	Length (In KM)	Damage Part Length During Flood	Estimated Cost (In Lakh)	Hemarks
Bagaha-1	Bishunpura to Brahman Tola	Under Agreement	1,010	0.120	6,308	Motorable & Traffic Restored
Bagaha-1	PMGSY Telpur to Inarbarwa Litya	Under Agreement	2.545	0.235	9.886	Motorable & Traffic Restored.
Bagaha-1	Parsauni (Pandey Nadi) PMGSY to Parsauni Tola	Under Agreement	0,905	0.125	3.257	Motorable & Traffic Restored
Bagaha-1	PMGSY Paroraha to Maltolwa Yadav Tola	Under Agreement	2,205	0.115	4.127	Motorable & Traffic Restored.
Bagaha-1	PWD Road to Satwariya South	Under Agreement	0.605	0.055	1,705	Motorable & Traffic Restored.
Bagah a-1	Pmgsy Road to Noniwa Tola Laker	Under Agreement	1.010	0.325	12,888	Motorable & Traffic Restored,
Bag aha-1	Telpur to Islampur	Under Agreement	1.670	0.090	2,59	Motorable & Traffic Restored,
Bagah a-1	Paroraha to Lohar Tola	Under Agreement	0.755	0.044	6,411	Motorable & Traffic Restored,
Bagah a-1	NH Road to Praua tola	Under Agreement	0.885	0.025	1,45	Motorable & Traffic Restored.
Bagah a-1	L066 Parsauni Dih PMGSY Road to Deurwa via Pandey Patti	Under Agreement	3.250	0.067	2.72	Motorable & Traffic Restored.
Bagaha-1	Sathi Mukhya Path to Bahuarwa Bhedi Hari Tola	Under Agreement	1.600	0.220	5.013	Motorable & Traffic Restored.
Bagaha-1	Siswaniya To Mahadalit Bastee	Under Agreement	1.775	0.070	5.98	Motorable & Traffic Restored.
Bagaha-1	PMGSY Lachnauta Path Vridhavan Harizan Tola (Dera Tola)	Under Agreement	1.120	0.030	2.074	Motorable & Traffic Restored.
Bagaha-1	Paroraha To Badai Tola Paroraha	Under Agreement	0.665	0.130	1.778	Motorable & Traffic Restored.
Bagaha-1	Barwa to Nawka Tola	Under Agreement	0.855	0.166	17.58	Motorable & Traffic Restored.
Bagaha-1	Pmgsy Road at Ganauli to Maal Tola	Under Agreement	1.300	0.107	7.412	Motorable & Traffic Restored.
Bagaha-1	Khairatia Yoga Pati to Yadu Rai Tola Barwa	Under Agreement	1.500	0.093	8.736	Motorable & Traffic Restored.
Bagaha-1	Ram Parsauna to Malahi Tola	Under Agreement	1.000	0.180	14.318	Motorable & Traffic Restored.
Bagaha-1	Dhobani Tola to Pandey Tola	Under Agreement	2.165	0.582	12.384	Motorable & Traffic Restored.
Bagaha-1	Baswariya to Baswariya North Tola	Under Agreement	0.770	0.100	2.625	Motorable & Traffic Restored.
Bagaha-1	PWD Chanpatia - Bashantpur	Under Agreement	2.500	0.190	8.849	Motorable & Traffic Restored.
Bagaha-1	PWD Bagha - Dumara	Under Agreement	6.500	0.072	24.393	Motorable & Traffic Restored.
Bagaha-1	PWD Bagha Siswania - Kataiya	Out of Agreement	4.100	0.171	15.296	Motorable & Traffic Restored.
Bagaha-1	PWD Narkatiyaganj To Mathiya	Under Agreement	4.210	0.150	9.018-	Motorable & Traffic Restored.
Bagaha-1	PWD Bettiah-Narkatiaganj road, Gulab nagar to Daniyal	Out of Agreement	7.250	0.650	36,553	Motorable & Traffic Restored.
Bagaha-1	Bahurwa Bherihari tola to Ramparsauna tak	Out of Agreement	1.750	0.350	9.809	Motorable & Traffic Restored.
Bagaha-1	PWD Ramnagar Lauriya To Sisahahi Road	Under Agreement	3.550	0.380	14.381	Motorable & Traffic Restored.
			///		THE RESIDENCE OF THE PROPERTY	The second section of the second section is the second section of the second section of the second section of the second section is the second section of the

(X).

TECHNICAL REPORT

Name of Road :- PWD Road to Satwariya South

Name of Block:- Lauriya

Name of Division:- Bagaha-1

Name of District:- West Champaran

Estimated Cost:- Rs. 1.705 Lacs

This Estimate is prepared for Restoration of Construction of PWD Road to Satwariya South under FDR as per the instruction of Secretary, Rural Works Department, Patna vide, 23 -60 /2020-1937, Patna, Date-07.07.2021. Road remains effected from flood about 01 to 02 weeks and heavy amount of water passed through it.

Honorable Chief Minister/Secratery, Rural Works Department, Bihar, Patna/D.M., West Champaran, Bettiah/Concerned MP/MLA has instructed to maintain the traffic and movement of public etc. at the earliest so that public of this area may get connected and for the same Departmental instruction has also been issued to fill the gap made by flooded immediately.

The area surrounding is submerged in water and hence provision of Bricks Bats/ Earth Work/Sand Filling/ Bamboo Pilling/Hume Pipe has been made to maintain the road damage due to flood/heavy rainfall as per availability of material from available place bytractor. Presently there is no Contractor is employed for Construction and Maintenance of this road hence the work has been carried out Departmentally and due to this, provision of Contractor profit is not mentioned in the estimate.

In view of above, it is requested to approve the estimate amounting to Rs. 1.705 Lacs please.

Submitted for Administrative Approval please.

ior Engineer,

Lauriya

Lauriya

Executive Engineer R.W.D.(W) Division, Bagaha-1

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR MOTORIBILITY IN PWD ROAD TO SATWARIYA SOUTH

DISTRICT - WEST CHAMPARAN

DIVISION - BAGAHA-1

BLOCK - Lauriya

LENGTH OF ROAD (in Km)- 0.62 KM

SL. No.	tem of Work		Amount
1	EARTH WORK	:	0.281 Lacs
2	BRICK BATS	:	1.203 Lacs
3	SAND BAGS	:	0.000 Lacs
4	BAMBOOS PILING AND RUNNER	:	0.000 Lacs
5	HUME PIPE	:	0.000 Lacs
	COST OF RESTORATION	:	1.484 Lacs
	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST	:	0.028 Lacs
	ADD LABOUR CESS @ 1%	:	0.015 Lacs
	ADD GST @ 12%	:	0.178 Lacs
	TOTAL COST OF RESTORATION OF ROAD	:	1.705 Lacs

Executive Engineer

Technically apported B. 1.705 lacs (Repess one laws Seventy Thomass five hundred) only.

R.W.D. (W) Circle Bettiah

me of Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motoribility in PWD Road To Satwariya South

d - FDR

punientenn									
Item No.	Name of Item	unit	N _O	Length	Width	Height	Qty.	Rate	Amount
	EARTH WORK - Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5			As P Appen			209.33	134.33	28119.2989
	Providing and Labour for laying dry graded Brick Bats by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi etc. all complete as per approved design, specification and direction of E/I.			As P Append			58.74	2048.30	120317.14
	Providing, Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/l.	Nos.					0	21.75	0.00
	Providing and Labour for cutting 62 mm to 75 dia Bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I.	RM					0.00	47.61	0.00
	Providing and Labour for fitting & fixing 62 mm to 75 dia Bamboo runners in position at every virtical pile with 150 mm long nails or 38 swg G.l. wire including cost of G.l. wire or nails etc. complete job as per specification and direction of E/l.	RM					0.00	26.85	0.00
	Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonary.	RM		0 Nos*2	2.5m		0.00	6189.30	0.00
	Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonary.	RM		0 Nos*2	2.5m		0.00	2586.64	0.00
							TO	TAL (in Re.)	148436.44

Junior Engineer, Rural Works Department, Works Section, Lauriya Assistant Engineer, Rural Works Department, Works Sub Division, Lauriya Executive Engineer, Rural Works Department, Works Division, BAGAHA-1

EET	
L	

Item dexcription	unit	Quantity of Consuming Item	Materials Required/ Unit	Unit	Quantity/ Unit	Total Quantity Requeired	Rate	Amount	Seigniorage Fee (RS)	Final Amount (RS)
Earth Work	Cum	209.33	Earth	Cum	1.0	209.33	34.82	7288.87	728.89	728.89
Brick bats	Cum	58.74	Brick bats	Cum	1.0	58.74	347.72	20425.07	2042.51	2042.51
Sand Bags	per bag	0.00	sand	Cum	0.034	0.00	347.72	0.00	0.00	0.00
		Total An	nount of segin	orage fee	in construc	etion (Rs)				2771.39
							talen enger			

12/2/2/ 12/2/2/ Bhu (202)

S.

अधीक्षण अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया पत्रोक-1,325 / बेतिया, विनाक 14 / 2021 /

प्रेषक:-

अधीक्षण अभियन्ता ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया।

सेवा में

कार्यपालक अभियन्ता, ग्रामीण कार्य विभाग

कार्य प्रमंडल, बेतिया / नरकटियागंज / बगहा-1 / बगहा-2

विषय:--

वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जॉच के संबंध में।

प्रसंग:-

वाट्स ऐप के माध्यम से प्राप्त विमागीय निदेश के आलोक में।

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि वर्ष 2021 में बाढ़ में क्षितिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जॉच हेतु वाट्स ऐप के माध्यम से विभागीय निदेश प्राप्त हुआ है। जिसमें कार्यपालक अभियन्ता एवम् उनके अधीनस्थ पदाधिकारीयों के माध्यम आवंटित प्रमंडल का जॉच करना है।

अतः विभागीय आदेश के आलोक में क्षतिग्रस्त पथों के जॉच हेतु अधोहस्ताक्षरी के द्वारा जॉच दल का गठन किया जा रहा है तथा जॉच दल दिनांक—22.11.2021 तक जॉच प्रतिवेदन अधोहस्ताक्षरी के समक्ष प्रस्तुत करेगें। अन्यथा इसकी सारी जबाबदेही जॉचदल की होगी।

∹जॉच दल तथा उनके जॉच करने का स्थल निम्नलिखित है:-

क्रमांक	जॉच दल	जॉच स्थल	प्रतिवेदन जमा करने
			की अंतिम तिथि
1	कार्यपालक अभियन्ता,	ग्रामीण कार्य विभाग, कार्य प्रमंडल,	22.11.2021
	सहायक अभियन्ता,	बगहा—1 एवम् नरकटियागंज का	
	ग्रामीण कार्य विभाग, कार्य	जॉच कर जॉच प्रतिवेदन समर्पित	
	प्रमंडल, बेतिया।	करेगें।	
2	कार्यपालक अभियन्ता,	ग्रामीण कार्य विभाग, कार्य प्रमंडल,	22.11.2021
	सहायक अभियन्ता,	बगहा-2 का जॉच कर जॉच	
	ग्रामीण कार्य विभाग, कार्य	प्रतिवेदन समर्पित करेगें।	
	प्रमंडल, बगहा–1।		
3	कार्यपालक अभियन्ता,	ग्रामीण कार्य विभाग, कार्य प्रमंडल,	22.11.2021
***************************************	सहायक अभियन्ता,	बेतिया का जॉच कर जॉच	1.6021
The same of the sa	ग्रामीण कार्य विभाग, कार्य	प्रतिवेदन समर्पित करेगे।	
	प्रमंडल, बगहा —2।		

अधीक्षण अभियन्ता ग्रा०का०वि०, का०अ०, बेतिया।

विश्वास्मभाजन

घोषणा-पत्र

- 1. इस प्राक्कलन को असंबद्ध कार्यपालक अभियन्ता से जॉच करा ली गयी है।
- 2. अस्थायी पुनर्स्थापन के सामग्री का समायोजन स्थायी पुनर्स्थापन के प्राक्कलन में ्कर ली गयी है।

सहायक अभियन्ता / कर्भीय अभियन्ता ग्रामीण कार्य विभाग कार्य प्रमंडल, बगहा-1

कार्यपालक अभियन्ता ग्रामीण कार्य विभाग कार्य प्रमंडल, बगहा-1