

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



**Name of Work:- Bajitpur (Satyndra Chaudhary Medicine Shop) to
PMGSY Teli Tola.**

Block:-Bajpatti.

F.D.R

Rs.411411.00 290281-00


Year-2021-22.

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	22/12/2021
3	पथ का नाम (शीर्ष के साथ)	Bajitpur (Satyendra Chaudhary Medicine Shop) to PMGSY Teli Tola
4	पथ की लम्बाई	2.100 km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	बाजपट्टी।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	24 25.8 m
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 110.6448 m³ Qty of Rubbish:- 27.6647 m³ Total Qty :- 138.3235 m³ Entered in MB No:- 2705 Page No:- 1-3
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	संतोष प्रद


 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-Bajitpur (Satyndra Chaudhary Medicine Shop) to PMGSY Teli Tola.

Length of Road:-2.100 Km

Block:-Bajpatti

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	352420.00
2	Labour cess @1%	3524.20
3	GST @12%	42290.40
4	Seigniorage Fee @ 10%	13176.70
5	Total Cost of Road Repair	411411.30

Say Rs.

411411.00

290281.20

[Signature]
S-11-21

JE

[Signature]
S-11-21

AE

[Signature]
S-11-21

अभियन्ता-ग्रामाण कार्य विभाग के पत्रांक-4849 दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक स्वीकृति के प्रत्याशा में औपबंधित तकनीकी स्वीकृति प्रदान की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त पुनः तकनीकी स्वीकृति प्रदान की जायेगी। औपबंधित तकनीकी स्वीकृति रुपये.....290281.20...[दो लाख नब्बे हजार दो सौ शताब्दी] की प्रदान की जाती है।

[Signature]

अधीक्षण अभियन्ता
ग्रामाण कार्य विभाग
कार्य अंचल, सीतामढ़ी

Schedule of Quantity

Name of Road:-Bajitpur (Satyendra Chaudhary Medicine Shop) to PMGSY Teli Tola.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	138.3235			0.00
	Less 20% for Voids	27.6647			
		110.6588	Cum	2105.01	232937.8806
3	Single bamboo paiaiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stitching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	20.00	m	3400.00 3300	68000.00 66000.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	10.00	m	850.00 835	8500.00 8350.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and direction of E/I.			873.01	24147.00
	Taking 20% of Brick Qty for Rabbish	27.6647	Cum	1553.68	42982.0911

Total 352419.97

Say 352420.00

290281.00

JE

AE

Details of Measurement of ditches filled by brick bats and rabbish

ne of Road:-Bajitpur (Satyndra Chaudhary Medicine Shop) to PMGSY Teli Tola.

	Nos.	L	W		H		VOLUME
CH 1800 M	1	2.00	3.300		0.440		2.9040
	1	16.00	4.900		1.880		147.3920
	1	2.00	3.400		0.440		2.9920
CH 1400 M	1	2.60	3.000		0.250	Av	1.9500
	1	1.10	2.500		0.370	Av	1.0175
	1	1.30	3.000		0.120		0.4680
		Total (in Cum)					156.7235
ss Laying Hume Pipe Volume of 1000 mm	8	0	0		0		15.60
ss Laying Hume Pipe Voulme of 600 mm d	4	0	0		0		2.80
Cement Bage							138.3235

Handwritten signature
5-11-21

JE

Handwritten signature
5-11-21

AE

Handwritten signature
5-11-21