



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MORTABLE REPAIRING OF ROAD

F.D.R MORTABLE RESTORATION (YEAR - 2021)

THAKURGANJ ISLAMPUR PATH TO POTHIA BASTI

DETAILED ESTIMATE OF F. D. R MORTABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1625M		
DISTRICT	KISHANGANJ		
BLOCK	POTHIA		
DIVISION	KISHANGANJ-2		
TOTAL LENGTH OF ROAD	:	1.625	KM
TOTAL COST OF F.D.R PART - A	:	12.440	LAKH
ADD GST @ 12 %	:	1.493	LAKH
ADD LABOUR CESS @ 1 %	:	0.124	LAKH
ADD Seigniorage Fee @ 10%	:	0.349	LAKH
TOTAL COST OF RESTORATION WORK in Rs.	:	14.407	LAKH


-:Submitted By:-
EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT
WORKS DIVISION KISHANGANJ-2


प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत Poltra
प्रखंड के पथ Thakeurgevi, 1stambur Path to Poltra, Barhi (Munimay) जो
विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में इ.के.सी. अतिवृष्टि/बाढ़ उपचार से आए बाढ़ के कारण इस पथ के
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में
अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। गोटेरेवल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
पाइल, चघरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक गेट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धृत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,
5/11/21


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,
05/11/21


गार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-2
11/11/21

Inspection Report for Flood Damage Work

1. Name of PIUs

: Kishangani-2

2. Name Of Block / Road

: Pothig /

Thakurganj Islampur Path To Pothig Batti

A. For Road

1. Damage Location / Chainage

: 288M

2. Damage Length

: 288M

3. Nature Of Damage

: Cut and erosion of Bank & Crest

4. Details Of Restoration

: Earthwork, sand filling Brickbat laying
Le bag with C-sand

i) Material Being Used In Restoration

: Soil, sand, Brickbat, Le bag, C-sand

ii) Equipment / Tools Being Used In Restoration Works

: Tractor Trolley JCB

iii) Procedure Taken Up In Restoration Works

: Manually

iv) Restored Length

: 288M

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

:

Work has been Completed Satisfactory

Signature of JE / AE / EE
25/11/21

Signature
25/11/2021


(Name Of Inspector)

ABSTRACT OF COST


Name of Work :-	THAKURGANJ ISLAMPUR PATH TO POTHIA BASTI	
Block :-	Pothia	
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 1244048.00
B	Add 12 % GST	Rs 149286.00
C	Add 1 % L. Cess	Rs 12440.00
D	Add S.Fee @ 10 % of Material Cost	Rs 34886.00
	Total Cost with GST, LC & S.Fee	Rs 1440660.00


J.E.


R.W.D
Pothia



A.E.

R.W.D
Pothia


E.E.
R.W.D
Kishanganj - 2

Technically sanction for Rs. 14,40,660.00 (Rupees
fourteen lacs forty thousand six hundred sixty) only.


04/04/22
E.O.



अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD


NAME OF ROAD :-	THAKURGANJ ISLAMPUR PATH TO POTHIA BASTI	
DISTRICT :	KISHANGANJ	
DIVISION :	KISHANGANJ-2	
BLOCK :-	POTHIA	
LENGTH OF ROAD (IN KM)	1.625	
Sl. No.	ITEM OF WORK	Amount. (In LAKHS.)
1	LOCAL SAND	0.957
2	HUME PIPE	0.000
3	BRICK BATS	4.159
4	SAND BAGS	5.639
5	BAMBOO WORK	1.684
6	STEEL DRUM SHEET	0.000
	TOTAL COST OF PROJECT	12.440
	Add 12 % GST	1.493
	Add 1 % L. Cess	0.124
	Add Seigniorage Fee @ 10 % of Material Cost	0.349
	Total Cost of Restoration Work	14.406


J.E.

R.W.D
POTHIA


A.E.

R.W.D
POTHIA


R.W.D.

Kishanganj - 2

Detailed Estimate

Name of Work :- THAKURGANJ ISLAMPUR PATH TO POTHIA BASTI													
Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)	
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I										
				1	105	3.50	-	-	367.50				
				1	4	3.50		-	14.00				
				1	105	3.50			367.50				
				1	11	3.50			38.50				
				1	105	3.50			367.50				
				1	56	3.50			196.00				
				1	70	3.50			245.00				
				1	53	3.50			185.50				
				1	105	3.50			367.50				
				1	67	3.50			234.50				
				1	60	3.50			210.00				
				1	56	3.50			196.00				
									Total:-	2789.50	Mtr.	52.24	145723.00
2	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.										
				1	3	30.00	-	-	90.00				
				1	3	1.00			3.00				
				1	3	30.00		-	90.00				
				1	3	3.00			9.00				
				1	3	30.00			90.00				
				1	3	16.00			48.00				
				1	3	20.00			60.00				
				1	3	15.00			45.00				
				1	3	30.00			90.00				
				1	3	19.00			57.00				
				1	3	17.00			51.00				
				1	3	16.00			48.00				
				1	3	30.00			90.00				
				1	3	4.00			12.00				
				1	3	12.00			36.00				
						273.00			Total:-	819.00	Mtr.	27.71	22694.00
3	3.14	303.1	Construction of subgrade and earthen shoulders										
			Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.										
				1	1	30.00	1.00	0.45	13.50				
				1	1	1.00	1.45	0.60	0.87				
				1	1	30.00	1.30	0.55	21.45				
				1	1	3.00	1.25	0.35	1.31				
				1	1	30.00	1.10	0.45	14.85				
				1	1	16.00	1.25	0.40	8.00				
				1	1	20.00	1.30	0.55	14.30				
				1	2	15.00	1.40	0.65	27.30				
				1	1	30.00	1.50	0.35	15.75				
				1	1	19.00	1.15	0.45	9.83				
				1	1	17.00	1.20	0.50	10.20				
				1	1	16.00	1.35	0.60	12.96				
				1	1	30.00	1.25	0.45	16.88				
				1	1	4.00	1.20	0.55	2.64				
				1	1	12.00	1.35	0.50	8.10				
									Total:-	177.94	Cum	174.93	31127.00

Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
4	9.2 (i)	1100 & 800	Sand filling Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9									
				1	1	30.00	1.00	0.30	9.00			
				1	1	1.00	1.45	0.35	0.51			
				1	1	30.00	1.30	0.30	11.70			
				1	1	3.00	1.25	0.25	0.94			
				1	1	30.00	1.10	0.30	9.90			
				1	1	16.00	1.25	0.20	4.00			
				1	1	20.00	1.30	0.30	7.80			
				1	2	15.00	1.40	0.35	14.70			
				1	1	30.00	1.50	0.45	20.25			
				1	1	19.00	1.15	0.30	6.56			
				1	1	17.00	1.20	0.35	7.14			
				1	1	16.00	1.35	0.45	9.72			
				1	1	30.00	1.25	0.35	13.13			
				1	1	4.00	1.20	0.45	2.16			
				1	1	12.00	1.35	0.50	8.10			
						273.00			125.61	Cum	514.43	64618.00
5	WRD	5.7.40	Brick bats Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I									
				1	1	30.00	1.20	0.65	23.40			
				1	1	1.00	1.45	0.45	0.65			
				1	1	30.00	1.30	0.60	23.40			
				1	1	3.00	1.25	0.35	1.31			
				1	1	30.00	1.10	0.55	18.15			
				1	1	16.00	1.25	0.40	8.00			
				1	1	20.00	1.30	0.35	9.10			
				1	2	15.00	1.40	0.40	16.80			
				1	1	30.00	1.50	0.60	27.00			
				1	1	19.00	1.15	0.60	13.11			
				1	1	17.00	1.20	0.45	9.18			
				1	1	16.00	1.35	0.50	10.80			
				1	1	30.00	1.25	0.55	20.63			
				1	1	4.00	1.20	0.45	2.16			
				1	1	12.00	1.35	0.50	8.10			
								Total:-	191.79	Cum	2168.72	415939.00
6		5.7.53	Providing and filling empty cement bags Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.									
				1	1	30.00	1.00	1.25	37.50			
				1	1	1.00	1.45	1.35	1.96			
				1	1	30.00	1.30	1.40	54.60			
				1	1	3.00	1.25	1.25	4.69			
				1	1	30.00	1.10	1.30	42.90			
				1	1	16.00	1.25	1.50	30.00			
				1	1	20.00	1.30	1.55	40.30			
				1	2	15.00	1.40	1.45	60.90			
				1	1	30.00	1.50	1.35	60.75			
				1	1	19.00	1.15	1.25	27.31			
				1	1	17.00	1.20	1.60	32.64			
				1	1	16.00	1.35	1.50	32.40			
				1	1	30.00	1.25	1.30	48.75			
				1	1	4.00	1.20	1.25	6.00			
				1	1	12.00	1.35	1.45	23.49			
								Total:-	504.19	Cum		
						@ 0.034 Cum each bag			14829	No.	38.03	563947.00
											TOTAL	1244048.00

Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
SEIGNORAGE FEE 10% FOR ROYALTY MATERIAL												
			LOCAL SAND			125.61	1.20	=	150.73	Cum	141.85	21381.00
			BRICK BAT			191.79	1.20	=	230.15	Cum	1,050.00	241655.00
			GSB			0.00	1.28	=	0.00	Cum	285.35	0.00
			LOCAL SAND			504.19	1.20	=	605.03	Cum	141.85	85823.00
									TOTAL MATERIAL COST:-			348859.00
									SEIGNORAGE FEE 10%			34886.00

[Signature]
 J.E
 R.W.D
 Pothia

[Signature]
 A.E
 R.W.D
 Pothia

[Signature]
 E.E
 R.W.D
 Kishanganj - 2