



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. MOTRABLE RESTORATION (YEAR - 2021)

T01-THAKURGANJ SE KHARUDAH (RCC BRIDGE AT T01-THAKURGANJ SE KHARUDAH AT
CH 11.50 K.M.)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 34.58	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	0.035	KM
TOTAL COST OF F.D.R. PART - A	Rs. 42.429	Lacs
ADD G.S.T @ 12%	Rs. 5.091	Lacs
ADD Labour Cess @ 1%	Rs. 0.424	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.990	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 49.934	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत 61/2021-ज.....
 प्रखंड के पथ 61/2021-ज से सार्वजनिक रस्ते के लिए 61/2021-ज से सार्वजनिक रस्ते के लिए 61/2021-ज (.....) जो
 विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के
 कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
 विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
 22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
 अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में ~~सुरक्षित~~ अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्घृत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कार्य प्रमंडल किशनगंज-2

Inspection Report for Flood Damage Work

1. Name of PIUs

: Er. Uday Shankar Chaudhary, EE. Kishanganj-2

2. Name Of Block / Road

: Thakurganj / TBT Thakurganj se Kharudak (RCC bridge)
at TBT Thakurganj se Kharudak at ch- 11.50 KM

A. For Road

1. Damage Location / Chainage

: 12.50 KM

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used In Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

:

N/A.

B. For Bridge

1. Damage Location / Chainage

: 0.00 M

2. Damage Length

: 62 M

3. Nature Of Damage

: Diversions

4. Details Of Restoration

:

i) Material Being Used In Restoration

: H.P and Borole barks

ii) Equipment / Tools Being Used in Restoration Works

: Tractor and JCB

iii) Procedure Taken Up In Restoration Works

: manually

iv) Restored Length

: 62 M

work has been completed satisfactorily.

Signature of JE / AE / EE

Signature

(Name Of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01-THAKURGANJ SE KHARUDAH (RCC BRIDGE AT T01-THAKURGANJ SE KHARUDAH AT CH 11.50 K.M.)

DISTRICT KISHANGANJ

DIVISION KISHANGANJ - 2

BLOCK THAKURGANJ

LENGTH OF ROAD (IN KM) 0.035

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND	0.000
2	HUME PIPE	1.328
3	BRICK BATS	41.101
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		42.429
Add G.S.T. @ 12%		5.091
Add Labour Cess @ 1%		0.424
Add Seigniorage Fee @ 10%		1.990
Total Cost of Restoration Work =		49.934

[Signature]
15/10/21
J.E.
RWD

[Signature]
15/10/21
A.E.
RWD

[Signature]
16/11/21
E.E.
RWD

Technically Sanction for Rs. 49 93 382.00 (Rupees forty nine Lacs ninety three thousand four hundred) only

[Signature]
04/04/22
E.O

[Signature]
04/04/22
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज