

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Benipur

Name of Block/Road:- Benipur / Khabra to Sasampura

A. For Road

1. Damage Location Chainage:- Ch. 2.000 km to Ch. 3.000 km
2. Damage Length :- 15 m
3. Nature of Damage :- Road crust & slant
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Bitul Batts
 - ii. Equipment's /Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- manually filling
 - iv. Restored Length:- 15 m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipment's /Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

N/A

Signature of JE/AE/EE

Signature
(Name of Inspection) BR

तकनीकी प्रतिवेदन


पथ का नाम	:- रथखना से सजनपुरा
पथ की लंबाई	:- 3.654 कि०मी०
प्राक्कलित राशि	:- रु. 1,36,420/-
प्रमण्डल का नाम	:- बेनीपुर
अंचल का नाम	:- दरभंगा
योजना शीर्ष	:-
योजना वर्ष	:- 2021-22

प्रस्तुत प्राक्कलन विभागीय पत्रांक-मु.अ.-4-4275 व 21 दिनांक-22.10.21 के आदेशानुसार पथ में कराये गये यातायात पुर्नस्थापना कार्य के निमित्त तैयार की गयी है।

यह प्राक्कलन रथखना से सजनपुरा कार्य के लिए तैयार की गई है। वर्ष 2021 में आयी प्रलयंकार बाढ़/अतिवृष्टि के कारण पथ कई जगहो पर क्षतिग्रस्त हो गया था। जिसके कारण आवागमन अवरुद्ध हो गई थी जिसमें अस्थाई यातायात पुर्नस्थापन कार्य किया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक लाभांश को छोड़कर था, उसे प्रावधान करते हुए तैयार किया गया है।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की प्रशासनिक स्वीकृति अपेक्षित है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा बेनीपुर


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल बेनीपुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल बेनीपुर।

Abstract of cost.

Name of Road:- L032-L034 Khabna to Sajjanpura (VR32)

No	Particulars of Item	Quantity (In M ³)	Rate	Amount
1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I	57.59	2004.96	115466
			Total =	115466
	Add 12% GST		=	13856
	1% L.C		=	1155
	(S.Fee)- B/Bat(57.59*1032*0.1)=5943		=	5943
			Grand Total=	136420

Say Rupees 136420=00

[Signature]
J.E

RWD,Benipur

[Signature]
A.E

RWD,Benipur

[Signature]
E.E

RWD,Benipur

TECHNICALLY SANCTIONED FOR RS 136420=00 (RUPEES ONE LAKH THIRTY SIX THOUSAND FOUR HUNDRED TWENTY) ONLY

[Signature]
Superintending Engineer
RWD, Works Circle, Darbhanga


Flood Estimate

Name of Road:- L032-L034 Khabna to Sajjanpura (VR32)

Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty in cum
	3rd km	5.00	$(2+2.5)/2$	$(1+1.2+0.5)/3$	10.12
		2.00	$(1+1.5)/2$	$(0.6+1)/2$	2.00
		8.00	$(2+3.5)/2$	$(1.6+2+2.6)/3$	45.47
			Total =		57.59


J.E.
RWD, Benipur


A.E.
RWD, Benipur


E.E.
RWD, Benipur

Checked and Verified


12-12-2024
AE

330
12/12/24
E.E.