



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. MOTRABLE RESTORATION (YEAR - 2021)

T04-TATPOWA TO MUSLIM TOLA (TRACK 17)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1000		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD	1.000	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 2.115	Lacs	
ADD G.S.T @ 12%	Rs. 0.254	Lacs	
ADD Labour Cess @ 1%	Rs. 0.021	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 0.069	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 2.459	Lacs	


SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2


प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत Thakurgaon प्रखंड के पथ Toy Talpowa to muslim Tola (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में Mechi अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


23/10/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, Thakurgaon.....


23/10/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, Thakurgaon.....


16/12/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-2

Inspection Report for Flood Damage Work

1. Name of PIUs

: @ ER: UDAY SHANKAR CHOUDRY, EE IKN-2

2. Name Of Block / Road

: Thakurgaon, Tox Tappow, to Muslim Tale

A. For Road

1. Damage Location / Chainage

: CH-550M, 615M, 700M, 825M

2. Damage Length

: 97.20M

3. Nature Of Damage

: Culverts, and crust

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Bricks Batts, Local Sand

ii) Equipment / Tools Being Used In Restoration Works

: Tractors

iii) Procedure Taken Up In Restoration Works

: Manually

iv) Restored Length

: 97.20M

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

: Work has been completed
Satisfactory.

Signature of JE / AE / EE
02/12/21
J.E

Signature
02/12/21

Signature of JE / AE / EE

Signature
02/12/2021

(Name Of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T04-TATPOWA TO MUSLIM TOLA (TRACK 17)
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 1.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND	1.600
2	HUME PIPE	0.000
3	BRICK BATS	0.515
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		2.115
Add G.S.T. @ 12%		0.254
Add Labour Cess @ 1%		0.021
Add Seigniorage Fee @ 10%		0.069
Total Cost of Restoration Work =		2.459

[Signature]
23/10/21
J.E.
RWD

[Signature]
23/10/21
A.E.
RWD

[Signature]
16/12/21
E.E.
RWD

Technically sanction for Rs. 245900 (Rupees two Lacs forty five thousand nine hundred) only.

[Signature]
04/04/22
E.O

[Signature]
04.04.22
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज