



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. MOTRABLE RESTORATION (YEAR - 2021)

L057-L056 TO AAMBARI (TRACK 57)

### DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

|                                       |                |            |      |
|---------------------------------------|----------------|------------|------|
| ROAD LENGTH                           | 0 TO 1793      |            |      |
| DISTRICT                              | KISHANGANJ     |            |      |
| BLOCK                                 | THAKURGANJ     |            |      |
| DIVISION                              | KISHANGANJ - 2 |            |      |
| TOTAL LENGTH OF ROAD                  |                | 1.793      | KM   |
| TOTAL COST OF F.D.R. PART - A         |                | Rs. 13.555 | Lacs |
| ADD G.S.T @ 12%                       |                | Rs. 1.627  | Lacs |
| ADD Labour Cess @ 1%                  |                | Rs. 0.136  | Lacs |
| ADD Seigniorage Fee @ 10%             |                | Rs. 0.656  | Lacs |
| TOTAL COST OF RESTORATION WORK In Rs. |                | Rs. 15.974 | Lacs |

SUBMITTED BY  
The Executive Engineer,  
Works Division, Kishanganj - 2

## प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत *Thakurgaon*  
प्रखंड के पथ *L057-L056 TO HANBARI (T09015-57)* (.....) जो  
विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के  
कारण यातायात लायक **Moterable** हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य  
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-  
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान  
अपलोड करते हुए (**Moterable**) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में *Local River* अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के  
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु **Moterable** कार्य कराया गया है। MIS में  
उपलोडेड फोटो दिनांक ..... का Lat/Long के साथ लिया गया है। नेपाल तराई से  
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में  
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का  
पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए  
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की  
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन  
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

*[Signature]*  
12/10/21

कनीय अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रशाखा, *6/5/2021*

*[Signature]*  
12/10/21

सहायक अभियंता  
ग्रामीण कार्य विभाग  
कार्य अवर प्रमंडल, *6/5/2021*

*[Signature]*  
16/10/21

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल किशनगंज-2

## Inspection Report for Flood Damage Work

1. Name of PIUs

: Er. Uday Sankar Choudhary, EE Krishnagar-2

2. Name Of Block / Road

: Thakurganj / L053-L056 to Aambari (Tru-2)

A. For Road

1. Damage Location / Chainage

: 180' M

2. Damage Length

: 34' M

3. Nature Of Damage

: Road crust, culvert, flank

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Brick Bats

ii) Equipment / Tools Being Used In Restoration Works

: Tractor

iii) Procedure Taken Up In Restoration Works

: Manually

iv) Restored Length

: 34' 0" M

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

N/A

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

: 34' 0" M

Work has been completed satisfactory

Signature of JE / AE / EE

Signature

(Name Of Inspector)

**GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD**

NAME OF ROAD : L057-L056 TO AAMBARI (TRACK 57)

DISTRICT KISHANGANJ

DIVISION KISHANGANJ - 2

BLOCK THAKURGANJ

LENGTH OF ROAD (IN KM) 1.793

| Sl. No.                          | ITEM OF WORK     | AMOUNT (LAKHS) |
|----------------------------------|------------------|----------------|
| 1                                | LOCAL SAND       | 0.000          |
| 2                                | HUME PIPE        | 0.000          |
| 3                                | BRICK BATS       | 13.555         |
| 4                                | SAND BAGS        | 0.000          |
| 5                                | BAMBOO WORK      | 0.000          |
| 6                                | STEEL DRUM SHEET | 0.000          |
| TOTAL COST OF PROJECT =          |                  | 13.555         |
| Add G.S.T. @ 12%                 |                  | 1.627          |
| Add Labour Cess @ 1%             |                  | 0.136          |
| Add Seigniorage Fee @ 10%        |                  | 0.656          |
| Total Cost of Restoration Work = |                  | 15.974         |

J.E.  
RWD

A.E.  
RWD

E.E.  
RWD

Technically sanction for Rs. 1597400.00 (Rupees fifteen Lacs ninety seven thousand four hundred) only

अधीक्षण अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंचल, किशनगंज

Pallavi  
04/04/22  
R.O.