



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2021-22

DISTRICT :- WEST CHAMPARAN
BLOCK :- BAIRIA

Estimate for Repair of Road breaches
(Damaged by Flood) for Moteribility in
POKHARI TOLA NEAR RAMBABU SHAH To
DHOBI YADAV TOLA

LENGTH OF ROAD (in Km)- 0.15 KM

ESTIMATED COST -	1.868	Lacs
------------------	-------	------

SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

घोषणा-पत्र

1. इस प्राक्कलन को असंबद्ध कार्यपालक अभियन्ता से जाँच करा ली गयी है।
2. अस्थायी पुनर्स्थापन के सामग्री का समायोजन स्थायी पुनर्स्थापन के प्राक्कलन में कर ली गयी है।



सहायक अभियन्ता / कनीय अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया।



कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

पत्रांक-.....२५७...../ बगहा-2, दिनांक.....२२/११/२०२१

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बगहा-2

में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

प :- कार्य प्रमंडल, बेतिया में वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

T:- भवदीय पत्रांक-1325/बेतिया, दिनांक-14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0) विविध (कार्य)-23-291 /2019-4589, दिनांक-13.11.2021।

शय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बेतिया द्वारा तद्व्यंजित कराये गये मोटरबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी द्वारा सहायक अभियन्ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बेतिया द्वारा प्रतिवेदित पथों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।

— निरीक्षण किये गये पथों की सूची।

विश्वासभाजन,

Deewan
25.11.2021

सहायक अभियन्ता
ग्रा0का0वि0, का0प्र0, बगहा-2

कार्यपालक अभियन्ता
ग्रा0का0वि0, का0प्र0, बगहा-2

	Puja Sthan To Banrahi		
	Nimua Tola To Bema Tola	1.7	5.81
	Baghamberpur - Bintoli (1036)	2.15	2.057
	PALGIRWA - GADIYANI	3.12	1.738
	L038 Manwa Pul to Bhanduliya Tola	1.91	3.28
	Bettiah(Sant Ghat) to Pujahaw (103)	0.984	1.646
	Islam Chowk to Bathni Road	12	23.072
	Fumakaria chowk to bhutaha via motihari tar	2.5	14.261
	SAAKAHIYA MAI STHAN to PHULIYA KHAND	3.5	11.811
	SAMADIWA	0.71	2.86
	Repair of road from Betiya Sant Ghat to Pakhnaha	11.05	6.526
	Repair of road from Betiya Khiriya Ghat to Paterwa Ghat	12.04	7.062
	Daroga Ram Ke Ghar To Kolwa Ghat	0.88	5.439
	PUJAH BRAHAMAN TOLI to RAMADHAR SINGH TOLA	1.64	3.478
	DHANGAR TOLI to CHAMAR TOLI	1.81	1.924
	Pokhari Tola Near Rambabu Shah to Dhobi Yadav Tola	0.86	1.868
	L038 to Sirisiya Kothi	1.45	4.598
	Majharia Pitch Road to Refugee Colony	1.49	3.003
	Pakhnaha Pitch Road to Kohirapatti	0.92	3.594
	L025-T01 Laukharia to Kahni Tola (TRACK25)	2.866	5.468
	L067-Motipur Pitch Road To Motipur Nayaka Tola (TRACK67)	0.546	3.285
	L088-Loukariya Pitch Road Mugahi Tola To Murgahi Tola (TRACK88)	1.887	5.057
	Machhargaon - FuliyaKhand	3	4.181
	PALGIRWA - GODIANI	2	10.166
	L034-T02 TO SISWA SAREA (TRACK34)	2.19	11.039
	L051-Sahi Tola to Matia Bandobasti (TRACK51)	2.804	2.791
	L091-Dubaulia Bairiya To Ahir Tola (TRACK91)	1.64	6.547
	Pashim champaran jila antergant karya pramandal bettiah antergat bariya prakhand ke chandrawat nadi ke snatghat par chhtigrast pul ke asthan par high Level RCC Bridge ka Nirman	30.22	1.461
	L022 To Mallahi Tola	1.305	2.406
	Repair of road from Nautan to Tengrahi Ghat	8.1	15.262
	WORLD BANK - KHALWA	3.729	1.002
	Jagdishpur Mukhya Marg to Machhargawan path	7.35	23.705
	Jagdishpur - Machhargawn	7.35	23.821
	Koiri Tola to T01	2.58	4.987
	T05 To Kurum Tola	1.7	2.206
	L074-Dawariya Pitch Road to Mushar Tola Bard No.6 (TRACK74)	0.527	0.545
	K.R. Hight School to Sofwa toli	1.5	14.377
	South Telua Pokhar Chowk To Ahir Tola (Brahman Tola)	2.45	2.251
	Halkorwa BT Road - Ghamaria	2.75	3.683
	Betiya jila antargat sitaram paswan ke ghar se bhaya gahri misan pachaim champaran sima tak.	12.025	15.432
	Kathaiya baikunthwa road to nakti paterwa	0.3	25.401

Executive Engineer
RWD/WI. Div.-Bagraha-2

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR
MOTERIBILITY IN POKHARI TOLA NEAR RAMBABU SHAH TO DHOBI
YADAV TOLA

DISTRICT - WEST CHAMPARAN

DIVISION - BETTIAH

BLOCK - BAIRIA

LENGTH OF ROAD (in Km)- 0.15 KM


SL. No.	Item of Work	Amount
1	EARTH WORK	
2	BRICK BATS	: 1.277 Lacs
3	SAND BAGS	: 0.000 Lacs
4	BAMBOOS PILING AND RUNNER	: 0.000 Lacs
5	HUME PIPE	: 0.000 Lacs
	COST OF RESTORATION	: 1.277 Lacs
	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST	: 0.033 Lacs
	ADD LABOUR CESS @ 1%	: 0.043 Lacs
	ADD GST @ 12%	: 0.515 Lacs
	TOTAL COST OF RESTORATION OF ROAD	: 1.868 Lacs



Junior Engineer



Asstt. Engineer


05/11/21

Executive Engineer

Sanctioned/
Technically approved for Rs-1.868 lakh (One lakh
eighty six thousand eight hundred) only.


25/11/21


Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar

Name of Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motorability In POKHARI TOLA
NEAR RAMBABU SHAH To DHOBI YADAV TOLA

Bad - FDR

Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
	EARTH WORK - Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	cum					950.4	134.33	127667.232
	Providing and and Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .	cum					0.000	0.00	0.00
	Providing and Labour for laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum					0.000	2142.53	0.00
	Providing, Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/I.	Nos.					0.000	19.67	0.00
	Providing and Labour for cutting 62 mm to 75 dia Bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I.	RM					0.000	47.61	0.00
	Providing and Labour for fitting & fixing 62 mm to 75 dia Bamboo runners in position at every virtual pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails etc. complete job as per specification and direction of E/I.	RM					0.000	26.85	0.00
	Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM					0.000	2549.49	0.00
TOTAL (In Re.)									127667.23


Junior Engineer,
Rural Works Department,
Works Section, BAIRIA


Assistant Engineer,
Rural Works Department,
Works Sub Division, BAIRIA


Executive Engineer,
Rural Works Department,
Works Division, BETTIAH