



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-

PMGSY Path Mankauli Noniya Tola

DISTRICT

Muzaffarpur

DIVISION

Muzaffarpur East-1

BLOCK

Kurhani

TOTAL LENGTH OF ROAD

:

2.511

KM

CONSTRUCTION COST

:

7.214

Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs :- EE, RWD (W) DIV -Muzaffarpur East -1
- 2 Name of Block/Road PMGSY Path Mankauli Noniya Tola.


A For Road


- 1 Damage Location/Chainage:- At many places.
- 2 Damage Length:-0.319 km
- 3 Nature of Damage:-C/W,R/W Breached & embankment damaged.
- 4 Details of Restoration Works:-Brick Bats – 336.09 cum
 - i Material being used in Restoration Works:-Brick bats. **Work is Satisfactory.**
 - ii Equipments/Tools being used in Restoration Works:- Roller, tractor,tipper,trailer,jcb, manual tools.
 - iii Procedure Taken up in Restoration Works:-Breachd portion is filled with Brick bats & embankment repaired for protected from further damaged due to flood water using Brick bats.
 - iv Restored Length:- 0.319 km


B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length


Signature of JE/AE/EE
J.E.


25/11/21
A.E.


28.11.21
E.E.


Signature
(Name of Inspector) 25/11/21
E.E.
R.W.D. Works Div
MAHAR.

GENERAL ABSTRACT

Name of the Road :-

PMGSY Path Mankauli Noniya Tola

District

Muzaffarpur

Block

Kurhani

Division

Muzaffarpur East-I

2.511 KM


Length of Road (in Km)

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	7.214
2	Sand Filling	0.000
3	Sand bag	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	7.214
TOTAL COST OF PROJECT IN LACS =		7.214


7.21 Lacs



JE
RWD




AE
RWD



EE
RWD

T/s for 7.21 Lacs (Rupees seven lacs twenty one thousand only)
(provisionally)


15.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Name of the Road :- PMGSY Path Mankauli Noniya Tola

Sl No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt (1985)	Brick Bat Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalsi making and maintaining diversion light barrier - do - do - danger signal etc. Including cost of labour and Materials .all complete				
			Appendix - I	Cum	336.1		
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical Specification Clause 305.3.9	Total	336.09	1809.49	608152.58
			Appendix - II	Cum			
			Total	0.00	0.00		0.00
Sub Total Cost							608152.58
GST 12%							72978.31
LC 01%							6081.53
SF (101.87cum)							34237.55
Total Cost :-							721449.96


S.E.

K. Durbhuja
25/11/21
A.E.

Name of the Road :-

PMGSY Path Mankauli Noniya Tola

BLOCK

Kurhani

Appendix - I

Measurement for Surfacing the breach Brick Bats

S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness	Quantity (Cum)
1		1	113.000	2.300	2.300		0.430	111.76
2		1	37.000	3.700	3.700		0.410	56.13
3		1	62.000	2.600	2.600		0.390	62.87
4		1	15.000	2.100	2.100		0.420	13.23
5		1	53.000	2.300	2.300		0.750	91.43
6		1	39.000	1.500	1.500		0.650	38.03
7		1		0.000	0.000		0.890	0.00
8		1		0.000	0.000		0.800	0.00
9		1		0.000	0.000		0.450	0.00
10		4		0.000	0.000		0.000	0.00
11		1		0.000	0.000		0.000	0.00
12		1		0.000	0.000		0.000	0.00
13		1		0.000	0.000		0.000	0.00
14		1		0.000	0.000		0.000	0.00
15		1		0.000	0.000		0.000	0.00
16		1		0.000	0.000		0.000	0.00
Total (Cum) :-								373.43
10% Deduction for voids and compaction								37.34
Total Quantity (Cum)								336.09



Junior Engineer,
Rural Works Department,
Work Section Kurhani,
Muzaffarpur East-I



Assistant Engineer,
Rural Works Department,
Work Section Kurhani,
Muzaffarpur East-I

Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-I