RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- Naresh Ray House to PMGSY Road Bhaur Paktola. Block:- Bokhara.

F.D.R

Rs.97656.00 64884 = 50 Year-2021-22

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division: - R.W.D. Works Division, Pupri.

5- . 10

DETAILED ESTIMATE FOR F.D.R

Genearal Abstract of Cost

Name of Road:-Naresh Ray House to PMGSY Road Bhaur Paktola.

Length of Road:-0.500 Km

Block:-Pupri

District:-Sitamarhi

| District. | Sitamai III | | | |
|-----------|---------------------------------------|-------------------------|--|--|
| S. No. | Particulars | Total Cost (in Lakh) | | |
| 1 | Total Cost for Motorable Roads | 82917.0 0 | | |
| 2 | Labour cess @1% | -829.17 | | |
| 3 | GST @12% | 9950.04 | | |
| 4 | Seigniorage Fee @ 10% | 3959.72 | | |
| 5 | | | | |

Say Rs.

97656.00

64884200

AE

अियंता प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849 दिनांक-07/12/2021 र के अमानुसार प्रशासनिक स्वीकृति के प्रत्याशा में औपबंधित तकनाकी

र ः प्रदान की जा रही हैं।प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त

पु नकनीकी स्वीकृति प्रदान की जायेगी।

ऑपबंधित तकनीकी स्वीकृति रुपये 6 488 4-00/-

(Sixty four thousand Eight hundred Eight

अधीक्षण अभियन्ता

ग्रामीण कार्य विभाग कार्य अंचल, सीतामढ़ी

5= .10

Schedule of Quantity

ime of Road:-Naresh Ray House to PMGSY Road Bhaur Paktola.

| 1 | | | | | |
|-----|---|---------|------|---------|-------------|
| SI. | Description of Item | Qty | Unit | Rate | Amount |
| 1 | Sand Filling in Foundation Trenches as per Drawing & Technical Specification. | 0.00 | Cum | 488.11 | 0.00 |
| 2 | Providing and laying of Brick Bat obtained from Chimney with machenical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge. | 41.5675 | | | 0.00 |
| | Less 20% for Voids | 8.3135 | | 1733=25 | 57630= |
| | Dess 20 /V for Votes | 33.2540 | Cum | | 70000.00254 |
| 3 | Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5 | 0.00 | m | 140.4 | 0.00 |
| 4 | Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc dodoall complete job as per specification and direction of E/I. (including Royalty and all Taxes) | 0.00 | no. | 9.63 | 0.00 |
| 5 | Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe | 0.00 | m | 3400.00 | 0.00 |
| 6 | Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe | 0.00 | m | 850.00 | 0.00 |
| 7 | Providing Quarry Material Rabbish for filling the voids in bricks batsdoall complete job as per specification and diretion of E/I. | | | 873=01 | 7254 20 |
| | Taking 20% of Brick Qty for Rabbish | 8.3135 | Cum | 1553.68 | 12916.51868 |

Total

82916.52

Say

-82917.00

64884 200

Sinist

AE

EP LULINA CONTRACTOR

5- . 10

Details of Measurement of ditches filled by brick bats and rabbish

ame of Road:-Naresh Ray House to PMGSY Road Bhaur Paktola.

| | Nos. | L | W | H | | VOLUME |
|---------------------------------|------|----------------|-----------|-------|------|---------|
| CH 100 M | 1 | 4.00 | 2,400 | 0.300 | | 2.8800 |
| CH 100 M | 1 | 1.50 | 2.000 | 0.250 | TE T | 0.7500 |
| | 1 | 3.50 | 2.500 | 0.250 | | 2.1875 |
| | 1 | 3.00 | 2,800 | 0.300 | | 2.5200 |
| CH 250 M | 1 | 3.50 | 4.000 | 0.400 | | 5.6000 |
| CH 250 M | 1 | 9.00 | 2,500 | 0.300 | | 6.7500 |
| Nanda Sahni House | 1 | 30.00 | 2,600 | 0.200 | Av | 15.6000 |
| | 1 | 11.00 | 2.400 | 0.200 | Av | 5.2800 |
| | 1 | Total (in Cum) | | | | 41.5675 |
| | 0 | 0 | | 0 | | 0.00 |
| Laying Hume Pipe of 1000 mm dia | _ | 0 | | 0 | | 0.00 |
| Laying Hume Pipe of 600 mm dia | 0 | U | | | | |
| Cement Bage | | | Manager 1 | | | |

JE

AT

SEEMMUND WAS TO

三、同

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

| 1 | THE STATE OF STATE | त्रगंडलाय जाय प्रातियम हतु प्रयत्र |
|----|--|--|
| 1 | निरीक्षी पदाधिकारी का नाम एवं पदनाम:— | ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी। |
| 2 | निरीक्षण की तिथि:- | 22/12/2021 |
| 3 | पथ का नाम (शीर्ष के साथ) | Road Bhave. Paktola |
| 4 | पथ की लम्बाई | 0.200 km |
| 5 | कार्य प्रमंडल का नाम | ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी। |
| 6 | प्रखंड का नाम | बोखड़ा। |
| 7 | पथ की स्थिति | (Completed/Ongoing) |
| 8 | पथ अनुरक्षण अवधि में हैं | (Yes/No) |
| 9 | क्षतिग्रस्त भाग की लम्बाई | |
| 10 | क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई) | All Mesurment are attached in estimate Qty of Brick Bats: - 33.2540 m ³ Qty of Rubbish: - 8.3135 m ³ Total Qty: - 41.5175 m ³ Entered in MB No: - 2677 Page No: - 1-3 |
| 11 | अस्थायी पुर्नस्थापन में किस—किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी | Brick Bats & Rubbish |
| 12 | अभ्युक्ति | र्शिवयाः |

निरीक्षी पदाधिकारी का हस्ताक्षर पदनाम सहित