

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- Choti Soriya Main Road to Saku Sahni Tola.
Block:- Bokhara.

F.D.R

Rs. ~~374040.00~~ 248542 = 10

Year-2021-22

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-Choti Soriya Main Road to Saku Sahni Tola.

Length of Road:-1.20 Km


Block:-Pupri

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	317587.00
2	Labour cess @1%	3175.87
3	GST @12%	38110.44
4	Seigniorage Fee @ 10%	15166.54
5	Total Cost of Road Repair	374039.85

Say Rs. ~~374040.00~~
Rs 248542.20



JE


AE


EE

अभियंता प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849 दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक स्वीकृति के प्रत्याशा में औपबंधित तकनीकी स्वीकृति प्रदान की जा रही हैं। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त पुनः तकनीकी स्वीकृति प्रदान की जायेगी।

औपबंधित तकनीकी स्वीकृति रुपये 248542.00/- - Two lakh forty eight thousand five hundred forty two only की प्रदान की जाती हैं।


24/12/21

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, सीतामढ़ी

Schedule of Quantity

of Road:-Choti Soriya Main Road to Saku Sahni Tola.

	Description of Item	Qty	Unit	Rate	Amount
	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	159.2120			0.00
	Less 20% for Voids	31.8424			
		127.3696	Cum	2105.01	268114.2817
				1733.25	220746.25
3	Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	0.00	m	3400.00	0.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	0.00	m	850.00	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and diretion of E/I.			873.04	27796.20
	Taking 20% of Brick Qty for Rabbish	31.8424	Cum	1553.68	49472.90003
				Total	317587.18
				Say	317587.00
					248542.20


JE


AE


Engineer

Details of Measurement of ditches filled by brick bats and rabbish

of Road:-Choti Soriya Main Road to Saku Sahni Tola.

	Nos.	L	W		H		VOLUME
CH 0M	1	6.00	4.400	Av	1.430	Av	37.7520
CH 250 M	1	6.20	4.000		0.700	Av	17.3600
	1	18.00	3.500	Av	0.900	Av	56.7000
	1	9.50	3.500	Av	1.200	Av	39.9000
Samar Paschim Tola	1	2.50	3.000		1.000		7.5000
Total (in Cum)							159.2120
Laying Hume Pipe of 1000 mm dia	0	0			0		0.00
Laying Hume Pipe of 600 mm dia	0	0			0		0.00
Cement Bage							

[Signature]
5-11-21

JE


[Signature]
5-11-21

AE

[Signature]
5-11-21
CEE

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	22-12-2021
3	पथ का नाम (शीर्ष के साथ)	Choti Soriya Main Road to Saku Sahnii Tola
4	पथ की लम्बाई	1.20 km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	बोखड़ा।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 127.3696 m³ Qty of Rubbish:- 31.8424 m³ Total Qty :- 159.2120 m³ Entered in MB No:- 2676 Page No:- 1403.
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	सोनीचप्रद


 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित