



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BAIRGACHHI TO KUSHA TAK PATH ME KUSHA DHAR PAR 3X25 H.L. BRIDGE

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 90.66	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	90.660	M
TOTAL COST OF F.D.R. PART - A	Rs. 12.812	Lacs
ADD G.S.T @ 12%	Rs. 1.537	Lacs
ADD Labour Cess @ 1%	Rs. 0.128	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.698	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 15.175	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मगधहारी.. अन्तर्गत ...मगधहारी..... प्रखंड
 के पथ ..Bairgachhi..To..Kusha..tak..Path..me..Kusha..Dhar..pat..3X25HL... (.....) जो
 वेभागीय Online Morititring System MIS पर अपलोड है के बाढ 2021 से क्षतिग्रस्त हो जाने के
 कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
 वेभाग, बिहार सरकार के पत्रांक:—मु0अ0—4(मु0) विविध (कार्य) —23—291 / 2019—4275 / पटना, दिनांक—
 22 / 10 / 2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
 अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में ~~अतिवृष्टि~~ अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक ~~24-08-2021~~ 24-08-2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्घत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, ...

Sany 25/11/24
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अनिहारी.....

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,।

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Rwd Mariani

2. Name of Block/Road- Mariani / BAIRGACHHI TO KUSHA TAK PATH ME KUSHA DHAR PAR 3x25 M H.L. Bridge.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 2

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

B. For Bridge

1. Damage Location/Chainage : At different chainage

2. Damage Length : 233.05m

3. Nature of Damage : Shoulder, surface of approach road

4. Details of Restoration :

i Material being used in Restoration :

Bamboo piling, Bridge Pile

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length :

233.05m


Signature of JE/AE/EE

Say 25/11/21
AR


20/11


Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BAIRGACHHI TO KUSHA TAK PATH ME KUSHA DHAR PAR 3X25 H.L. BRIDGE

DISTRICT KATIHAR


DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM) 0.091

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	12.812
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		12.812
Add G.S.T. @ 12%		1.537
Add Labour Cess @ 1%		0.128
Add Seigniorage Fee @ 10%		0.698
Total Cost of Restoration Work =		15.175


J.E.
RWD


A.E.
RWD


E.A.
RWD

Technically Sanction for Rs. 15.175 Lac (Rs.)

C. Fifteen Lac Seventeen

Thousand Five Hundred Only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea