



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L036-T01 TO BAJEDOGACHH (VR36)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 3009	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	3.009	KM
TOTAL COST OF F.D.R. PART - A	Rs. 15.097	Lacs
ADD G.S.T @ 12%	Rs. 1.812	Lacs
ADD Labour Cess @ 1%	Rs. 0.151	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.822	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 17.882	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- BARSOI / L036 - To1 TO BAJEDOGACHH (VR36)

A. For Road : L036 - To1 TO BAJEDOGACHH (VR36).

1. Damage Location/Chainage : CH 540 To 1220

2. Damage Length : 365.90 M[±]8.

3. Nature of Damage : Shoulder and crust

4. Details of Restoration : Brick Bat

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Tractor & JCB.

iii Procedure taken up in Restoration works

iv Restored Length : Manual.
365.90 M[±]8.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature


(Name of Inspector)


प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारसोई अन्तर्गत बारसोई..... प्रखंड के
थ Lo36-To1 To BAJEDOGACHH (VR36)..... (.....) जो विभागीय
Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण
गतायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग,
बेहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में
उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, बारसोई.....



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बारसोई


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L036-T01 TO BAJEDOGACHH (VR30)
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BARSOI
LENGTH OF ROAD (IN KM) 3.009

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	15.097
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		15.097
Add G.S.T. @ 12%		1.812
Add Labour Cess @ 1%		0.151
Add Seigniorage Fee @ 10%		0.822
Total Cost of Restoration Work =		17.882


J.E.
RWD


A.E.
RWD



E.E.
RWD

provisional Technically Sanctioned For Rs.....17.882 Lacs.

(Rupees.....Crore.....Seventeen

lacs.....eighty eight -

Thousands.....Two.....Hundred) Only


अधीक्षक अभियंता
ग्रामीण कार्य विभाग,
कार्य अंश, पूर्णिया