



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BIJURIA NH-31 BIJARGON TO ADAMPUR VIA DHAPI TELTA
BALRAMPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 13500	
DISTRICT	KATIHAR	
BLOCK	BALRAMPUR	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	13.500	KM
TOTAL COST OF F.D.R. PART - A	Rs. 23.227	Lacs
ADD G.S.T @ 12%	Rs. 2.787	Lacs
ADD Labour Cess @ 1%	Rs. 0.232	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.161	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 27.407	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल अन्तर्गत प्रखंड
के पथ BIVRIAMH 31 BITARGON TO ADAMPUR VIA DHAD TELTA (.....) जो
विभागीय Online Monitoring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में
उपलोडेड फोटो दिनांक ... 28/11/2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धृत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

28/11/2021

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,

US 9/11/22

28/11/2021

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

28/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, ... 9/11/22

Inspection Report for Flood damage work

Date:

1. Name of PIUs- EE. RWD. Barsoi

2. Name of Block/Road- Bijuria NH31 Bijargon to Adampur via Dhabitella
MADHOPUR

A. For Road

1. Damage Location/Chainage : 6.100 km to 12.235 km

2. Damage Length : 545.15 km

3. Nature of Damage : Shoulder and court

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Brick bats, bamboo, local sand, Empty Cement bags

iii Procedure taken up in Restoration works: JCB, tractor, C.C. Hammer etc

iv Restored Length : 545.15 km

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE
8/11/22

Signature
08/01/2022
AE
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BIJURIA NH-31 BIJARGON TO ADAMPUR VIA DHAPI TELTA MADHOPUR
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BALRAMPUR
LENGTH OF ROAD (IN KM) 13.500

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	20.007
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
7	GSB	3.220
TOTAL COST OF PROJECT =		23.227
Add G.S.T. @ 12%		2.787
Add Labour Cess @ 1%		0.232
Add Seigniorage Fee @ 10%		1.161
Total Cost of Restoration Work =		27.407

US
C Kumar
J.E. 9/10/22
RWD

Q. P. Singh
28/11/21
A.E.
RWD

W. Singh
E.E.
RWD

Provisional Technical Sanction of Rs 27.407 Lacs
(Rupees twenty seven lacs forty thousand seven
hundred) only

अध्यक्ष अभियंता
जमीन एवं विभाग
कावे अंश, पूर्णिया