



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BABULAL RISHI TO KARWAR DHAR KEWALA PANCHAYAT

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 3000	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	3.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 12.346	Lacs
ADD G.S.T @ 12%	Rs. 1.482	Lacs
ADD Labour Cess @ 1%	Rs. 0.123	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.659	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 14.610	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मणिहारी अन्तर्गत मणिहारी प्रखंड के पथ Babulal Rishi To Karwar Dhar Kewala Panchayat (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में वर्तमान वर्ष-2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 10/10/2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, मणिहारी.....

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, मणिहारी.....

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मणिहारी.....

Inspection Report for flood damage work

Date:

1. Name of PIUs-

Manihari

2. Name of Block/Road-

Babulal Rishi To Karwar Dhar Kewala
Panchayat

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

33 m/r
Side Cured cutting due To Flood

Brick Bats

Tractor

Manual

33 m/r

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

25/11/21

25/11/21
AR

Signature of JE/AE/EE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BABULAL RISHI TO KARWAR DHAR KEWALA PANCHAYAT

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM) 3.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.242
3	BRIKCK BAT	12.104
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		12.346
Add G.S.T. @ 12%		1.482
Add Labour Cess @ 1%		0.123
Add Seigniorage Fee @ 10%		0.659
Total Cost of Restoration Work =		14.610

25/11/21
J.E.
RWD

San 25/11/21
A.E.
RWD

25/11/21
E.E.
RWD

Technically Sanction for Rs. 14,610 Lac (Rs. _____
Crore. Fourteen Lac Sixty one
Thousand. _____ Hundred. _____ Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea